



2 April 1999
EA Project No. 296.0043.7296

Northern Division
Naval Facilities Engineering Command
10 Industrial Highway, MS #82
Lester, Pennsylvania 19113-2090

Attn: Mr. Ed Boyle
Remedial Project Manager

Re: Contract No. N62472-92-D-1296; CTO No. 0043
Summary Report for October 1998 Quarterly Ground-Water Sampling Event at Naval Air Warfare Center (NAWC) Trenton (Ewing Township), New Jersey

Dear Mr. Boyle:

The purpose of this report is to provide the Navy with the results from laboratory analyses of ground-water samples collected from 55 monitoring wells (51 onsite and 4 offsite) and 8 storm drains (4 onsite and 4 offsite) located at Naval Air Warfare Center (NAWC) Trenton. These samples were collected by EA Engineering, Science, and Technology (EA) between 5 October and 16 October 1998 in accordance with the Draft First Year Monitoring Plan (EA 1998). This letter and the attached tables and figures comprise the subject report.

The analytical results for the October 1998 sampling event are summarized in Tables 1 through 5. On each table, the samples are listed in numerical order, beginning with bedrock wells, followed by overburden wells. New Jersey Department of Environmental Protection (NJDEP) Ground-Water Quality Criteria for Class II-A Ground Water (N.J.A.C. 7:9-6) are also included on the tables for comparison with the analytical results. The criteria used (unless otherwise noted) are the Higher of Practical Quantitation Levels (PQLs) and Ground-Water Quality Criteria. Concentrations of analytes that are greater than NJDEP ground-water criteria are highlighted in bold on the tables. Analytical results for field blank and trip blank samples are listed at the end of each table (trip blanks are only listed on Tables 1A and 1B, as they were only analyzed for volatile organics). Data qualifiers, acronyms, and other notes referenced on the individual analytical summary tables are listed and defined in Table 6. Monitoring well locations are provided on Figure 1 and storm drain locations are provided on Figure 2. Field Record of Well Gauging, Purging, and Sampling forms for each well are also attached as Appendix A.

Additional considerations regarding this report include the following:

- As directed by the Navy on 9 June 1998, the scope of this quarterly report was reduced from a full ground-water sampling report (which typically includes ground-water elevation maps and an interpretation of analytical results) to a submittal of only analytical data summary tables. Ground-water elevation maps and isoconcentration maps will be developed by the USGS using the October 1998 sampling data and submitted to the Navy under separate cover. Additional figures (as needed) and interpretation of results will be incorporated into a yearly report following the fourth quarter sampling event.
- No sample was collected from monitoring well 2S, because the well has been abandoned.
- No sample was collected from monitoring well 41S because there was no water present at the time of collection.
- Ground water collected from monitoring well BRP-3 contained unusually high levels of turbidity, possibly due to nearby construction.
- Surface water samples were not collected from three storm drains (ST-21, ST-28, and ST-29), because there was no water present at the time of collection.
- No samples were taken from monitoring wells 24BR and 25BR, because both wells were obstructed. The Navy removed the obstructions subsequent to the October 1998 sampling event.
- Analyses of samples for volatile organic compounds (VOCs) were generally performed on undiluted samples. In some samples, however, analyte concentrations (particularly trichloroethene [TCE], 1,2-dichloroethene [1,2-DCE], and vinyl chloride) exceeded the instrument calibration range during analyses of the undiluted samples. When this occurred, the sample was reanalyzed at a secondary dilution to quantify those analytes that exceeded the calibration range during the undiluted analysis. Both the undiluted and the diluted analytical results are presented on Table 1 for those samples where this applies. Copies of the sample narratives for all sample delivery groups within this round are attached as Appendix B.
- The initial sample analyses (including those samples requiring dilution prior to the first run) were performed within the method holding times except for VOC analyses of samples collected from seven locations (35BR, ST27, ST26, OF25, OF24, OF22 [and OF22 duplicate], and OF23). Initial VOC analyses for these samples were performed one day past holding times due to analytical instrument maintenance. For those samples requiring secondary dilution, holding times were exceeded; however, analyses of the secondary dilution generally confirmed the elevated concentrations reported in the initial analyses. Diluted samples for anions were analyzed within holding times.
- Ground-water samples from twelve of the wells (4BR, 6BR, 8BR, 22BR, 29BR, 31BR, 38BR, 41BR, 43BR, 44BR, 46BR, and 31S) were reanalyzed for VOCs due to surrogate recoveries of bromofluorobenzene that were outside of quality control limits. The reanalyses holding times were exceeded; however, if either the initial analysis or the reanalysis result

exceeded NJDEP ground-water criteria, then the highest analyte concentration of the two reported results was highlighted in bold to be conservative. If the initial result exceeded calibration range and was qualified with an "E", then the reanalysis result was highlighted in bold if it exceeded criteria.

- During anion analyses, three samples had a pH value greater than 10 and required dilution to effect neutralization prior to analysis (43BR, 44BR, and 46BR). Additional samples also required dilution in order to achieve concentrations of target analytes within calibration range. Both the undiluted and the diluted analytical results are presented on Table 4 for those samples where this applies.
- During the sampling event, EA collected samples that were submitted to the USGS for laboratory analyses. Analytical results for these samples are not included in this report.
- Third-party data validation of the October 1998 analytical results presented in this report has not been performed.

If you have any questions or need further information after reviewing the tables, please feel free to call us at (732) 404-9370.

Sincerely,



Laurie B. Wylie
Project Geologist



Steven G. Feldmann, P.G.
CTO Manager

SGF
Attachment

TABLE 1A
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812414 02BR-100798 10/7/98	9812312 03BR-100598 10/5/98	9812571 04BR-100998 10/9/98	9812571RE 04BR-100998RE 10/9/98	9812757 05BR-101498 10/14/98	9812419 06BR-100798 10/7/98
1,1,1-Trichloroethane	ug/L	30	10 U	1 U	100 U	100 U	1 U	1 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	10 U	1 U	100 U	100 U	1 U	1 U
1,1,2-Trichloroethane	ug/L	3	10 U	1 U	100 U	100 U	1 U	1 U
1,1-Dichloroethane	ug/L	50(3)	10 U	1 U	100 U	100 U	1 U	1 U
1,1-Dichloroethene	ug/L	2	10 U	1 U	100 U	100 U	1 U	1 U
1,2-Dichloroethane	ug/L	2	10 U	1 U	100 U	100 U	1 U	1 U
1,2-Dichloroethene, cis-	ug/L	70	37 D	0.4 J	1000	890	1 J	1 U
1,2-Dichloroethene, trans-	ug/L	100	10 U	1 U	100 U	100 U	1 U	1 U
1,2-Dichloropropane	ug/L	1	10 U	0.4 U	100 U	100 U	1 U	1 U
2-Butanone	ug/L	300	50 U	5 U	500 U	500 U	5 U	5 U
2-Hexanone	ug/L	NA	50 U	5 U	500 U	500 U	5 U	5 U
4-Methyl-2-pentanone	ug/L	400	50 U	1 U	500 U	500 U	5 U	5 U
Acetone	ug/L	NA	50 U	5 U	500 U	500 U	5 U	5 U
Benzene	ug/L	1	10 U	0.4 U	100 U	100 U	1 U	1 U
Bromodichloromethane	ug/L	1	10 U	0.3 U	100 U	100 U	1 U	1 U
Bromoform	ug/L	4	10 U	1 U	100 U	100 U	1 U	1 U
Bromomethane	ug/L	NA	10 U	1 U	100 U	100 U	1 U	1 U
Carbon disulfide	ug/L	NA	10 U	1 U	100 U	100 U	1 U	1 U
Carbon tetrachloride	ug/L	2	10 U	1 U	100 U	100 U	1 U	1 U
Chlorobenzene	ug/L	4	10 U	1 U	100 U	100 U	1 U	1 U
Chloroethane	ug/L	NA	10 U	1 U	100 U	100 U	1 U	1 U
Chloroform	ug/L	6	10 U	1 U	100 U	100 U	1 U	1 U
Chloromethane	ug/L	NA	10 U	1 U	100 U	100 U	1 U	1 U
cis-1,3-Dichloropropene	ug/L	NA	2 U	0.4 U	20 U	20 U	0.2 U	0.2 U
Dibromochloromethane	ug/L	10	10 U	1 U	100 U	100 U	1 U	1 U
Ethylbenzene	ug/L	700	10 U	1 U	100 U	100 U	1 U	1 U
Methylene chloride	ug/L	3(4)	10 U	1 U	100 U	100 U	1 U	1 U
Styrene	ug/L	100	10 U	1 U	100 U	100 U	1 U	1 U
Tetrachloroethene	ug/L	1	10 U	0.5 U	100 U	100 U	1 U	1 U
Toluene	ug/L	1000	10 U	1 U	100 U	100 U	1 U	1 U
trans-1,3-Dichloropropene	ug/L	0.02	2 U	0.3 U	20 U	20 U	0.2 U	0.2 U
Trichloroethene	ug/L	1	87 D	0.4 U	280	190 D	0.3 J	0.2 J
Vinyl chloride	ug/L	5	11 D	1 U	300	310 D	0.2 J	1 U
Xylenes, total	ug/L	1000(2)	10 U	1 U	100 U	100 U	1 U	1 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812419RE 06BR-100798RE 10/7/98	9812530 07BR-100898 10/8/98	9812530DL 07BR-100898DL 10/8/98	9812569 08BR-100998 10/9/98	982569RE 08BR-100998RE 10/9/98	9812416 09BR-100798 10/7/98
1,1,1-Trichloroethane	ug/L	30	1 U	2000 U	5000 U	25 U	25 U	1 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	1 U	2000 U	5000 U	25 U	25 U	1 U
1,1,2-Trichloroethane	ug/L	3	1 U	2000 U	5000 U	25 U	25 U	1 U
1,1-Dichloroethane	ug/L	50(3)	1 U	2000 U	5000 U	25 U	25 U	8
1,1-Dichloroethene	ug/L	2	1 U	2000 U	5000 U	25 U	25 U	0.4 J
1,2-Dichloroethane	ug/L	2	1 U	2000 U	5000 U	25 U	25 U	1 U
1,2-Dichloroethene, cis-	ug/L	70	1 U	50000 E	17000 D	10 J	11 J	10
1,2-Dichloroethene, trans-	ug/L	100	1 U	2000 U	5000 U	25 U	25 U	1 U
1,2-Dichloropropane	ug/L	1	1 U	2000 U	5000 U	25 U	25 U	1 U
2-Butanone	ug/L	300	5 U	10000 U	25000 U	130 U	130 U	5 U
2-Hexanone	ug/L	NA	5 U	10000 U	25000 U	130 U	130 U	5 U
4-Methyl-2-pentanone	ug/L	400	5 U	2000 U	5000 U	130 U	130 U	5 U
Acetone	ug/L	NA	5 U	10000 U	25000 U	130 U	130 U	5 U
Benzene	ug/L	1	1 U	2000 U	5000 U	25 U	25 U	1 U
Bromodichloromethane	ug/L	1	1 U	2000 U	5000 U	25 U	25 U	1 U
Bromoform	ug/L	4	1 U	2000 U	5000 U	25 U	25 U	1 U
Bromomethane	ug/L	NA	1 U	2000 U	5000 U	25 U	25 U	1 U
Carbon disulfide	ug/L	NA	1 U	2000 U	5000 U	25 U	25 U	1 U
Carbon tetrachloride	ug/L	2	1 U	2000 U	5000 U	25 U	25 U	1 U
Chlorobenzene	ug/L	4	1 U	2000 U	5000 U	25 U	25 U	1 U
Chloroethane	ug/L	NA	1 U	2000 U	5000 U	25 U	25 U	1 U
Chloroform	ug/L	6	1 U	2000 U	5000 U	25 U	25 U	1 U
Chloromethane	ug/L	NA	1 U	2000 U	5000 U	25 U	25 U	1 U
cis-1,3-Dichloropropene	ug/L	NA	0.2 U	400 U	1000 U	5 U	5 U	0.2 U
Dibromochloromethane	ug/L	10	1 U	2000 U	5000 U	25 U	25 U	1 U
Ethylbenzene	ug/L	700	1 U	2000 U	5000 U	25 U	25 U	1 U
Methylene chloride	ug/L	3(4)	1 U	2000 U	2200 JD	25 U	25 U	1 U
Styrene	ug/L	100	1 U	2000 U	5000 U	25 U	25 U	1 U
Tetrachloroethene	ug/L	1	1 U	2000 U	5000 U	25 U	25 U	1 U
Toluene	ug/L	1000	1 U	2000 U	5000 U	25 U	25 U	1 U
trans-1,3-Dichloropropene	ug/L	0.02	0.2 U	400 U	1000 U	5 U	5 U	0.2 U
Trichloroethene	ug/L	1	1 U	6300	4800 JD	500	520 D	5
Vinyl chloride	ug/L	5	1 U	7000	4000 JD	25	25 U	2
Xylenes, total	ug/L	1000(2)	1 U	2000 U	5000 U	25 U	25 U	1 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812360 11BR-100698 10/6/98	9812413 12BR-100798 10/7/98	9812564 15BR-100998 10/9/98	9812564DL 15BR-100998DL 10/9/98	9812756 16BR-101498 10/14/98	9812756DL 16BR-101498DL 10/14/98
1,1,1-Trichloroethane	ug/L	30	2 U	1 U	100 U	1000 U	0.2 J	20 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	2 U	1 U	100 U	1000 U	1 U	20 U
1,1,2-Trichloroethane	ug/L	3	2 U	1 U	100 U	1000 U	1 U	20 U
1,1-Dichloroethane	ug/L	50(3)	2 U	1 U	100 U	1000 U	0.5 J	20 U
1,1-Dichloroethene	ug/L	2	2 U	1 U	68 J	1000 U	1 U	20 U
1,2-Dichloroethane	ug/L	2	2 U	1 U	100 U	1000 U	1 U	20 U
1,2-Dichloroethene, cis-	ug/L	70	22	4	22000 E	5100 D	93 E	110 D
1,2-Dichloroethene, trans-	ug/L	100	2 U	1 U	100 U	1000 U	1 U	20 U
1,2-Dichloropropane	ug/L	1	2 U	1 U	100 U	1000 U	1 U	20 U
2-Butanone	ug/L	300	10 U	5 U	500 U	5000 U	5 U	100 U
2-Hexanone	ug/L	NA	10 U	5 U	500 U	5000 U	5 U	100 U
4-Methyl-2-pentanone	ug/L	400	10 U	5 U	500 U	5000 U	5 U	100 U
Acetone	ug/L	NA	10 U	5 U	500 U	5000 U	5 U	100 U
Benzene	ug/L	1	2 U	1 U	100 U	1000 U	1 U	20 U
Bromodichloromethane	ug/L	1	2 U	1 U	100 U	1000 U	1 U	20 U
Bromoform	ug/L	4	2 U	1 U	100 U	1000 U	1 U	20 U
Bromomethane	ug/L	NA	2 U	1 U	100 U	1000 U	1 U	20 U
Carbon disulfide	ug/L	NA	2 U	1 U	100 U	1000 U	1 U	20 U
Carbon tetrachloride	ug/L	2	2 U	1 U	100 U	1000 U	1 U	20 U
Chlorobenzene	ug/L	4	2 U	1 U	100 U	1000 U	1 U	20 U
Chloroethane	ug/L	NA	2 U	1 U	100 U	1000 U	1 U	20 U
Chloroform	ug/L	6	2 U	1 U	100 U	1000 U	1 U	20 U
Chloromethane	ug/L	NA	2 U	1 U	100 U	1000 U	1 U	20 U
cis-1,3-Dichloropropene	ug/L	NA	0.4 U	0.2 U	20 U	200 U	0.2 U	4 U
Dibromochloromethane	ug/L	10	2 U	1 U	100 U	1000 U	1 U	20 U
Ethylbenzene	ug/L	700	0.3 JD	1 U	100 U	1000 U	1 U	20 U
Methylene chloride	ug/L	3(4)	2 U	1 U	100 U	1000 U	1 U	20 U
Styrene	ug/L	100	2 U	1 U	100 U	1000 U	1 U	20 U
Tetrachloroethene	ug/L	1	2 U	1 U	100 U	1000 U	1 U	20 U
Toluene	ug/L	1000	0.2 JD	1 U	100 U	1000 U	1 U	20 U
trans-1,3-Dichloropropene	ug/L	0.02	0.4 U	0.2 U	20 U	200 U	0.2 U	4 U
Trichloroethene	ug/L	1	7 D	0.8 J	7000 E	860 JD	80 E	110 D
Vinyl chloride	ug/L	5	2 U	1 U	3500 E	570 JD	6 U	5 JD
Xylenes, total	ug/L	1000(2)	0.7 JD	1 U	100 U	1000 U	1 U	20 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812357 19BR-100698 10/6/98	9812755 20BR-101498 10/14/98	9812755DL 20BR-101498DL 10/14/98	9812356 21BR-100698 10/6/98	9812568 22BR-100998 10/9/98	9812568RE 22BR-100998RE 10/9/98
1,1,1-Trichloroethane	ug/L	30	1 U	50 U	1000 U	0.8 J	5 U	5 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	1 U	50 U	1000 U	1 U	5 U	5 U
1,1,2-Trichloroethane	ug/L	3	1 U	50 U	1000 U	1 U	5 U	5 U
1,1-Dichloroethane	ug/L	50(3)	1 U	50 U	1000 U	1 U	5 U	5 U
1,1-Dichloroethene	ug/L	2	1 U	180 D	1000 U	0.3 J	5 U	1 JD
1,2-Dichloroethane	ug/L	2	1 U	50 U	1000 U	1 U	5 U	5 U
1,2-Dichloroethene, cis-	ug/L	70	1 U	11000 DE	8900 D	2	88	87
1,2-Dichloroethene, trans-	ug/L	100	1 U	50 U	1000 U	1 U	5 U	5 U
1,2-Dichloropropane	ug/L	1	1 U	50 U	1000 U	1 U	5 U	5 U
2-Butanone	ug/L	300	5 U	250 U	5000 U	5 U	25 U	25 U
2-Hexanone	ug/L	NA	5 U	250 U	5000 U	5 U	25 U	25 U
4-Methyl-2-pentanone	ug/L	400	5 U	250 U	5000 U	5 U	25 U	25 U
Acetone	ug/L	NA	5 U	250 U	5000 U	5 U	25 U	25 U
Benzene	ug/L	1	1 U	50 U	1000 U	1 U	5 U	5 U
Bromodichloromethane	ug/L	1	1 U	50 U	1000 U	1 U	5 U	5 U
Bromoform	ug/L	4	1 U	50 U	1000 U	1 U	5 U	5 U
Bromomethane	ug/L	NA	1 U	50 U	1000 U	1 U	5 U	5 U
Carbon disulfide	ug/L	NA	1 U	50 U	1000 U	1 U	5 U	5 U
Carbon tetrachloride	ug/L	2	1 U	50 U	1000 U	1 U	5 U	5 U
Chlorobenzene	ug/L	4	1 U	50 U	1000 U	1 U	5 U	5 U
Chloroethane	ug/L	NA	1 U	50 U	1000 U	1 U	5 U	5 U
Chloroform	ug/L	6	1 U	50 U	1000 U	0.5 J	5 U	5 U
Chloromethane	ug/L	NA	1 U	50 U	1000 U	1 U	5 U	5 U
cis-1,3-Dichloropropene	ug/L	NA	0.2 U	10 U	200 U	0.2 U	1 U	1 U
Dibromochloromethane	ug/L	10	1 U	50 U	1000 U	1 U	5 U	5 U
Ethylbenzene	ug/L	700	1 U	50 U	1000 U	1 U	5 U	5 U
Methylene chloride	ug/L	3(4)	1 U	50 U	1000 U	1 U	5 U	5 U
Styrene	ug/L	100	1 U	50 U	1000 U	1 U	5 U	5 U
Tetrachloroethene	ug/L	1	1 U	50 U	1000 U	1 U	5 U	5 U
Toluene	ug/L	1000	1 U	50 U	1000 U	1 U	5 U	5 U
trans-1,3-Dichloropropene	ug/L	0.02	0.2 U	10 U	200 U	0.2 U	1 U	1 U
Trichloroethene	ug/L	1	1 U	280 D	1000 U	4	25	21 D
Vinyl chloride	ug/L	5	1 U	7200 DE	2900 D	1 U	5 U	5 U
Xylenes, total	ug/L	1000(2)	1 U	50 U	1000 U	1 U	5 U	5 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812526 27BR-100898 10/8/98	9812358 28BR-100698 10/6/98	9812567 29BR-100998 10/9/98	9812567RE 29BR-100998RE 10/9/98	9812681 30BR-101398 10/13/98	9812523 31BR-100898 10/8/98
1,1,1-Trichloroethane	ug/L	30	1 U	1 U	100 U	100 U	5000 U	5 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	1 U	1 U	100 U	100 U	5000 U	5 U
1,1,2-Trichloroethane	ug/L	3	1 U	1 U	100 U	100 U	5000 U	5 U
1,1-Dichloroethane	ug/L	50(3)	1 U	1 U	100 U	100 U	27000	2 J
1,1-Dichloroethene	ug/L	2	1 U	1 U	100 U	100 U	5000 U	5 U
1,2-Dichloroethane	ug/L	2	1 U	1 U	100 U	100 U	5000 U	5 U
1,2-Dichloroethene, cis-	ug/L	70	0.2 J	1 U	110	83 J	13000	7
1,2-Dichloroethene, trans-	ug/L	100	1 U	1 U	100 U	100 U	5000 U	5 U
1,2-Dichloropropane	ug/L	1	1 U	1 U	100 U	100 U	5000 U	5 U
2-Butanone	ug/L	300	5 U	5 U	500 U	500 U	25000 U	25 U
2-Hexanone	ug/L	NA	5 U	5 U	500 U	500 U	25000 U	25 U
4-Methyl-2-pentanone	ug/L	400	1 U	5 U	500 U	500 U	25000 U	25 U
Acetone	ug/L	NA	5 U	5 U	500 U	500 U	25000 U	25 U
Benzene	ug/L	1	1 U	1 U	100 U	100 U	5000 U	5 U
Bromodichloromethane	ug/L	1	1 U	1 U	100 U	100 U	5000 U	5 U
Bromoform	ug/L	4	1 U	1 U	100 U	100 U	5000 U	5 U
Bromomethane	ug/L	NA	1 U	1 U	100 U	100 U	5000 U	5 U
Carbon disulfide	ug/L	NA	1 U	1 U	100 U	100 U	5000 U	5 U
Carbon tetrachloride	ug/L	2	1 U	1 U	100 U	100 U	5000 U	5 U
Chlorobenzene	ug/L	4	1 U	1 U	100 U	100 U	5000 U	5 U
Chloroethane	ug/L	NA	1 U	1 U	100 U	100 U	5000 U	5 U
Chloroform	ug/L	6	1 U	0.3 J	100 U	100 U	5000 U	5 U
Chloromethane	ug/L	NA	1 U	1 U	100 U	100 U	5000 U	5 U
cis-1,3-Dichloropropene	ug/L	NA	0.2 U	0.2 U	20 U	20 U	1000 U	1 U
Dibromochloromethane	ug/L	10	1 U	1 U	100 U	100 U	5000 U	5 U
Ethylbenzene	ug/L	700	1 U	1 U	100 U	100 U	5000 U	5 U
Methylene chloride	ug/L	3(4)	1 U	1 U	100 U	100 U	2900 J	5 U
Styrene	ug/L	100	1 U	1 U	100 U	100 U	5000 U	5 U
Tetrachloroethene	ug/L	1	1 U	1 U	100 U	100 U	5000 U	5 U
Toluene	ug/L	1000	1 U	1 U	100 U	100 U	5000 U	5 U
trans-1,3-Dichloropropene	ug/L	0.02	0.2 U	0.2 U	20 U	20 U	1000 U	1 U
Trichloroethene	ug/L	1	1 U	1 U	3000 E	2100 D	19000	19
Vinyl chloride	ug/L	5	1 U	1 U	100 U	100 U	5000 U	5 U
Xylenes, total	ug/L	1000(2)	1 U	1 U	100 U	100 U	5000 U	5 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812523RE 31BR-100898RE 10/8/98	9812679 33BR-101398 10/13/98	9812819 35BR-101598 10/15/98	9812759 36BR-101498 10/14/98	9812359 37BR-100698 10/6/98	9812682 38BR-101398 10/13/98
1,1,1-Trichloroethane	ug/L	30	5 U	1 U	1 U	10000 U	1 U	2000 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	5 U	1 U	1 U	10000 U	1 U	2000 U
1,1,2-Trichloroethane	ug/L	3	5 U	1 U	1 U	10000 U	1 U	2000 U
1,1-Dichloroethane	ug/L	50(3)	6	1 U	1 U	10000 U	1 U	2000 U
1,1-Dichloroethene	ug/L	2	5 U	1 U	1 U	10000 U	1 U	2000 U
1,2-Dichloroethane	ug/L	2	5 U	1 U	1 U	10000 U	1 U	2000 U
1,2-Dichloroethene, cis-	ug/L	70	7 D	1 U	1 U	10000 U	0.2 J	2700
1,2-Dichloroethene, trans-	ug/L	100	5 U	1 U	1 U	10000 U	1 U	2000 U
1,2-Dichloropropane	ug/L	1	5 U	1 U	1 U	10000 U	1 U	2000 U
2-Butanone	ug/L	300	25 U	5 U	5 U	50000 U	5 U	10000 U
2-Hexanone	ug/L	NA	25 U	5 U	5 U	50000 U	5 U	10000 U
4-Methyl-2-pentanone	ug/L	400	5 U	5 U	5 U	50000 U	5 U	10000 U
Acetone	ug/L	NA	25 U	5 U	5 U	50000 U	5 U	10000 U
Benzene	ug/L	1	5 U	1 U	1 U	10000 U	1 U	2000 U
Bromodichloromethane	ug/L	1	5 U	1 U	1 U	10000 U	1 U	2000 U
Bromoform	ug/L	4	5 U	1 U	1 U	10000 U	1 U	2000 U
Bromomethane	ug/L	NA	5 U	1 U	1 U	10000 U	1 U	2000 U
Carbon disulfide	ug/L	NA	5 U	1 U	1 U	10000 U	1 U	2000 U
Carbon tetrachloride	ug/L	2	5 U	1 U	1 U	10000 U	1 U	2000 U
Chlorobenzene	ug/L	4	5 U	1 U	1 U	10000 U	1 U	2000 U
Chloroethane	ug/L	NA	5 U	1 U	1 U	10000 U	1 U	2000 U
Chloroform	ug/L	6	5 U	1 U	1 U	10000 U	1 U	2000 U
Chloromethane	ug/L	NA	5 U	1 U	1 U	10000 U	1 U	2000 U
cis-1,3-Dichloropropene	ug/L	NA	1 U	0.2 U	0.2 U	2000 U	0.2 U	400 U
Dibromochloromethane	ug/L	10	5 U	1 U	1 U	10000 U	1 U	2000 U
Ethylbenzene	ug/L	700	5 U	1 U	1 U	10000 U	1 U	2000 U
Methylene chloride	ug/L	3(4)	5 U	1 U	1 U	10000 U	1 U	2000 U
Styrene	ug/L	100	5 U	1 U	1 U	10000 U	1 U	2000 U
Tetrachloroethene	ug/L	1	5 U	1 U	1 U	10000 U	1 U	2000 U
Toluene	ug/L	1000	5 U	1 U	1 U	10000 U	1 U	2000 U
trans-1,3-Dichloropropene	ug/L	0.02	1 U	0.2 U	0.2 U	2000 U	0.2 U	400 U
Trichloroethene	ug/L	1	24	1 U	1 U	10000 D	2	22000
Vinyl chloride	ug/L	5	3 J	1 U	1 U	10000 U	1 U	2000 U
Xylenes, total	ug/L	1000(2)	5 U	1 U	1 U	10000 U	1 U	2000 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812682RE 38BR-101398RE 10/13/98	9812527 39BR-100898 10/8/98	9812532 40BR-100898 10/8/98	9812565 41BR-100998 10/9/98	9812565RE 41BR-100998RE 10/9/98	9812528 42BR-100898 10/8/98
1,1,1-Trichloroethane	ug/L	30	2000 U	1 U	20 U	20 U	20 U	1 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	2000 U	1 U	20 U	20 U	20 U	1 U
1,1,2-Trichloroethane	ug/L	3	2000 U	1 U	20 U	20 U	20 U	1 U
1,1-Dichloroethane	ug/L	50(3)	2000 U	1 U	20 U	20 U	20 U	1 U
1,1-Dichloroethene	ug/L	2	2000 U	1 U	20 U	4 J	20 U	1 U
1,2-Dichloroethane	ug/L	2	2000 U	1 U	20 U	20 U	20 U	1 U
1,2-Dichloroethene, cis-	ug/L	70	6700	1 U	110	560	560	1 U
1,2-Dichloroethene, trans-	ug/L	100	2000 U	1 U	20 U	20 U	20 U	1 U
1,2-Dichloropropane	ug/L	1	2000 U	1 U	20 U	20 U	20 U	1 U
2-Butanone	ug/L	300	10000 U	5 U	100 U	100 U	100 U	5 U
2-Hexanone	ug/L	NA	10000 U	5 U	100 U	100 U	100 U	5 U
4-Methyl-2-pentanone	ug/L	400	10000 U	1 U	20 U	100 U	100 U	1 U
Acetone	ug/L	NA	10000 U	5 U	100 U	100 U	100 U	5 U
Benzene	ug/L	1	2000 U	1 U	20 U	20 U	20 U	1 U
Bromodichloromethane	ug/L	1	2000 U	1 U	20 U	20 U	20 U	1 U
Bromoform	ug/L	4	2000 U	1 U	20 U	20 U	20 U	1 U
Bromomethane	ug/L	NA	2000 U	1 U	20 U	20 U	20 U	1 U
Carbon disulfide	ug/L	NA	2000 U	1 U	20 U	20 U	20 U	1 U
Carbon tetrachloride	ug/L	2	2000 U	1 U	20 U	20 U	20 U	1 U
Chlorobenzene	ug/L	4	2000 U	1 U	20 U	20 U	20 U	1 U
Chloroethane	ug/L	NA	2000 U	1 U	20 U	20 U	20 U	1 U
Chloroform	ug/L	6	2000 U	1 U	20 U	20 U	20 U	1 U
Chloromethane	ug/L	NA	2000 U	1 U	20 U	20 U	20 U	1 U
cis-1,3-Dichloropropene	ug/L	NA	400 U	0.2 U	4 U	4 U	4 U	0.2 U
Dibromochloromethane	ug/L	10	2000 U	1 U	20 U	20 U	20 U	1 U
Ethylbenzene	ug/L	700	2000 U	1 U	20 U	20 U	20 U	1 U
Methylene chloride	ug/L	3(4)	2000 U	1 U	20 U	20 U	20 U	1 U
Styrene	ug/L	100	2000 U	1 U	20 U	20 U	20 U	1 U
Tetrachloroethene	ug/L	1	2000 U	1 U	20 U	20 U	20 U	1 U
Toluene	ug/L	1000	2000 U	1 U	20 U	20 U	20 U	1 U
trans-1,3-Dichloropropene	ug/L	0.02	400 U	0.2 U	4 U	4 U	4 U	0.2 U
Trichloroethene	ug/L	1	40000	1 U	120	550 E	300 D	1 U
Vinyl chloride	ug/L	5	2000 U	1 U	20 U	26	20 U	1 U
Xylenes, total	ug/L	1000(2)	2000 U	1 U	20 U	20 U	20 U	1 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812591 43BR-101298 10/12/98	9812591RE 43BR-101298RE 10/12/98	9812592 44BR-101298 10/12/98	9812592RE 44BR-101298RE 10/12/98	9812760 45BR-101498 10/14/98	9812760DL 45BR-101498DL 10/14/98
1,1,1-Trichloroethane	ug/L	30	1 U	1 U	1 U	1 U	200 U	1000 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	1 U	1 U	1 U	1 U	200 U	1000 U
1,1,2-Trichloroethane	ug/L	3	1 U	1 U	1 U	1 U	200 U	1000 U
1,1-Dichloroethane	ug/L	50(3)	1 U	1 U	1 U	1 U	200 U	1000 U
1,1-Dichloroethene	ug/L	2	1 U	1 U	1 U	1 U	200 U	1000 U
1,2-Dichloroethane	ug/L	2	1 U	1 U	1 U	1 U	200 U	1000 U
1,2-Dichloroethene, cis-	ug/L	70	1 U	1 U	1 U	1 U	2300 D	880 DJ
1,2-Dichloroethene, trans-	ug/L	100	1 U	1 U	1 U	1 U	200 U	1000 U
1,2-Dichloropropane	ug/L	1	1 U	1 U	1 U	1 U	200 U	1000 U
2-Butanone	ug/L	300	5 U	5 U	5 U	5 U	1000 U	5000 U
2-Hexanone	ug/L	NA	5 U	5 U	5 U	5 U	1000 U	5000 U
4-Methyl-2-pentanone	ug/L	400	5 U	5 U	5 U	5 U	1000 U	5000 U
Acetone	ug/L	NA	5 U	5 U	5 U	5 U	1000 U	5000 U
Benzene	ug/L	1	1 U	1 U	0.3 J	0.2 J	200 U	1000 U
Bromodichloromethane	ug/L	1	1 U	1 U	1 U	1 U	200 U	1000 U
Bromoform	ug/L	4	1 U	1 U	1 U	1 U	200 U	1000 U
Bromomethane	ug/L	NA	1 U	1 U	1 U	1 U	200 U	1000 U
Carbon disulfide	ug/L	NA	1 U	1 U	1 U	1 U	200 U	1000 U
Carbon tetrachloride	ug/L	2	1 U	1 U	1 U	1 U	200 U	1000 U
Chlorobenzene	ug/L	4	1 U	1 U	1 U	1 U	200 U	1000 U
Chloroethane	ug/L	NA	1 U	1 U	1 U	1 U	200 U	1000 U
Chloroform	ug/L	6	1 U	1 U	1 U	0.1 J	200 U	1000 U
Chloromethane	ug/L	NA	1 U	1 U	1 U	1 U	200 U	1000 U
cis-1,3-Dichloropropene	ug/L	NA	0.2 U	0.2 U	0.2 U	0.2 U	40 U	200 U
Dibromochloromethane	ug/L	10	1 U	1 U	1 U	1 U	200 U	1000 U
Ethylbenzene	ug/L	700	1 U	1 U	1 U	1 U	200 U	1000 U
Methylene chloride	ug/L	3(4)	1 U	1 U	1 U	1 U	200 U	1000 U
Styrene	ug/L	100	1 U	1 U	1 U	1 U	200 U	1000 U
Tetrachloroethene	ug/L	1	1 U	1 U	1 U	1 U	200 U	1000 U
Toluene	ug/L	1000	0.1 J	0.2 J	0.2 J	0.2 J	200 U	1000 U
trans-1,3-Dichloropropene	ug/L	0.02	0.2 U	0.2 U	0.2 U	0.2 U	40 U	200 U
Trichloroethene	ug/L	1	1 U	1 U	0.2 J	1 U	17000 DE	4500 D
Vinyl chloride	ug/L	5	1 U	1 U	1 U	1 U	200 U	1000 U
Xylenes, total	ug/L	1000(2)	1 U	1 U	1 U	1 U	200 U	1000 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812761 45BR-101498DUP3 10/14/98	9812761DL 45BR-101498DUP3DL 10/14/98	9812594 46BR-101298 10/12/98	9812594RE 46BR-101298RE 10/12/98	9812529 47BR-100898 10/8/98	9812529DL 47BR-100898DL 10/8/98
1,1,1-Trichloroethane	ug/L	30	1 U	200 U	500 U	500 U	5 U	20 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	1 U	200 U	500 U	500 U	5 U	20 U
1,1,2-Trichloroethane	ug/L	3	1 U	200 U	500 U	500 U	5 U	20 U
1,1-Dichloroethane	ug/L	50(3)	1 U	200 U	500 U	500 U	1 J	20 U
1,1-Dichloroethene	ug/L	2	3	200 U	500 U	500 U	2 J	20 U
1,2-Dichloroethane	ug/L	2	1 U	200 U	500 U	500 U	5 U	20 U
1,2-Dichloroethene, cis-	ug/L	70	290 E	330 DE	500 U	500 U	260 E	90 D
1,2-Dichloroethene, trans-	ug/L	100	7	200 U	500 U	500 U	2 J	20 U
1,2-Dichloropropane	ug/L	1	1 U	200 U	500 U	500 U	5 U	20 U
2-Butanone	ug/L	300	5 U	1000 U	2500 U	2500 U	25 U	100 U
2-Hexanone	ug/L	NA	5 U	1000 U	2500 U	2500 U	25 U	100 U
4-Methyl-2-pentanone	ug/L	400	5 U	1000 U	2500 U	2500 U	5 U	20 U
Acetone	ug/L	NA	5 U	1000 U	2500 U	2500 U	25 U	100 U
Benzene	ug/L	1	1 U	200 U	500 U	500 U	5 U	20 U
Bromodichloromethane	ug/L	1	1 U	200 U	500 U	500 U	5 U	20 U
Bromoform	ug/L	4	1 U	200 U	500 U	500 U	5 U	20 U
Bromomethane	ug/L	NA	1 U	200 U	500 U	500 U	5 U	20 U
Carbon disulfide	ug/L	NA	1 U	200 U	500 U	500 U	5 U	20 U
Carbon tetrachloride	ug/L	2	1 U	200 U	500 U	500 U	5 U	20 U
Chlorobenzene	ug/L	4	1 U	200 U	500 U	500 U	5 U	20 U
Chloroethane	ug/L	NA	1 U	200 U	500 U	500 U	5 U	20 U
Chloroform	ug/L	6	1 U	200 U	500 U	500 U	5 U	20 U
Chloromethane	ug/L	NA	1 U	200 U	500 U	500 U	5 U	20 U
cis-1,3-Dichloropropene	ug/L	NA	0.2 U	40 U	100 U	100 U	1 U	4 U
Dibromochloromethane	ug/L	10	1 U	200 U	500 U	500 U	5 U	20 U
Ethylbenzene	ug/L	700	1 U	200 U	500 U	500 U	5 U	20 U
Methylene chloride	ug/L	3(4)	1 U	200 U	500 U	500 U	5 U	20 U
Styrene	ug/L	100	1 U	200 U	500 U	500 U	5 U	20 U
Tetrachloroethene	ug/L	1	1 U	200 U	500 U	500 U	5 U	20 U
Toluene	ug/L	1000	0.4 J	200 U	500 U	500 U	5 U	20 U
trans-1,3-Dichloropropene	ug/L	0.02	0.2 U	40 U	100 U	100 U	1 U	4 U
Trichloroethene	ug/L	1	420 E	2500 D	5600 D	4700 D	160 E	110 D
Vinyl chloride	ug/L	5	2	200 U	500 U	500 U	29	16 JD
Xylenes, total	ug/L	1000(2)	1 U	200 U	500 U	500 U	5 U	20 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812562 48BR-100998 10/9/98	9812562DL 48BR-100998DL 10/9/98	9812595 49BR-101298 10/12/98	9812754 50BR-101498 10/14/98	9812758 50BR-101498DUP4 10/14/98	9812417 51BR-100798 10/7/98
1,1,1-Trichloroethane	ug/L	30	5 U	50 U	1 U	1 U	1 U	1 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	5 U	50 U	1 U	1 U	1 U	1 U
1,1,2-Trichloroethane	ug/L	3	5 U	50 U	1 U	1 U	1 U	1 U
1,1-Dichloroethane	ug/L	50(3)	5 U	50 U	1 U	1 U	1 U	1 U
1,1-Dichloroethene	ug/L	2	0.6 J	50 U	1 U	1 U	1 U	1 U
1,2-Dichloroethane	ug/L	2	5 U	50 U	1 U	1 U	1 U	1 U
1,2-Dichloroethene, cis-	ug/L	70	21	21 JD	1	2	2	26
1,2-Dichloroethene, trans-	ug/L	100	5 U	50 U	1 U	1 U	1 U	1 U
1,2-Dichloropropane	ug/L	1	5 U	50 U	1 U	1 U	1 U	1 U
2-Butanone	ug/L	300	25 U	250 U	5 U	5 U	5 U	5 U
2-Hexanone	ug/L	NA	25 U	250 U	5 U	5 U	5 U	5 U
4-Methyl-2-pentanone	ug/L	400	25 U	250 U	5 U	5 U	5 U	5 U
Acetone	ug/L	NA	25 U	250 U	5 U	5 U	5 U	5 U
Benzene	ug/L	1	5 U	50 U	1 U	1 U	1 U	1 U
Bromodichloromethane	ug/L	1	5 U	50 U	1 U	1 U	1 U	1 U
Bromoform	ug/L	4	5 U	50 U	1 U	1 U	1 U	1 U
Bromomethane	ug/L	NA	5 U	50 U	1 U	1 U	1 U	1 U
Carbon disulfide	ug/L	NA	5 U	50 U	1 U	1 U	1 U	1 U
Carbon tetrachloride	ug/L	2	5 U	50 U	1 U	1 U	1 U	1 U
Chlorobenzene	ug/L	4	5 U	50 U	1 U	1 U	1 U	1 U
Chloroethane	ug/L	NA	5 U	50 U	1 U	1 U	1 U	1 U
Chloroform	ug/L	6	5 U	50 U	1 U	1 U	1 U	0.3 J
Chloromethane	ug/L	NA	5 U	50 U	1 U	1 U	1 U	1 U
cis-1,3-Dichloropropene	ug/L	NA	1 U	10 U	0.2 U	0.2 U	0.2 U	0.2 U
Dibromochloromethane	ug/L	10	5 U	50 U	1 U	1 U	1 U	1 U
Ethylbenzene	ug/L	700	5 U	50 U	1 U	1 U	1 U	1 U
Methylene chloride	ug/L	3(4)	5 U	50 D	1 U	1 U	1 U	1 U
Styrene	ug/L	100	5 U	50 U	1 U	1 U	1 U	1 U
Tetrachloroethene	ug/L	1	5 U	50 U	1 U	1 U	1 U	1 U
Toluene	ug/L	1000	5 U	50 U	1 U	1 U	1 U	1 U
trans-1,3-Dichloropropene	ug/L	0.02	1 U	10 U	0.2 U	0.2 U	0.2 U	0.2 U
Trichloroethene	ug/L	1	740 E	1000 D	1	3	3	78 E
Vinyl chloride	ug/L	5	2 J	50 U	1 U	1 U	1 U	0.4 J
Xylenes, total	ug/L	1000(2)	5 U	50 U	1 U	1 U	1 U	1 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812417DL 51BR-100798DL 10/7/98	9812418 51BR-100798DUP1 10/7/98	9812418DL 51BR-100798DUP1DL 10/7/98	9812313 11MW1-100598 10/5/98	9812589 35MW1-101298 10/12/98	9812590 35MW2-101298 10/12/98
1,1,1-Trichloroethane	ug/L	30	5 U	1 U	10 U	1 U	1 U	1 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	5 U	1 U	10 U	1 U	1 U	1 U
1,1,2-Trichloroethane	ug/L	3	5 U	1 U	10 U	1 U	1 U	1 U
1,1-Dichloroethane	ug/L	50(3)	5 U	1 U	10 U	1 U	1 U	1 U
1,1-Dichloroethene	ug/L	2	5 U	1 U	10 U	1 U	1 U	1 U
1,2-Dichloroethane	ug/L	2	5 U	1 U	10 U	1 U	1 U	1 U
1,2-Dichloroethene, cis-	ug/L	70	17 D	27	13 D	2	2	0.3 J
1,2-Dichloroethene, trans-	ug/L	100	5 U	0.2 J	10 U	1 U	1 U	1 U
1,2-Dichloropropane	ug/L	1	5 U	1 U	10 U	0.4 U	1 U	1 U
2-Butanone	ug/L	300	25 U	5 U	50 U	5 U	5 U	5 U
2-Hexanone	ug/L	NA	25 U	5 U	50 U	5 U	5 U	5 U
4-Methyl-2-pentanone	ug/L	400	25 U	5 U	50 U	1 U	5 U	5 U
Acetone	ug/L	NA	25 U	5 U	50 U	5 U	5 U	5 U
Benzene	ug/L	1	5 U	1 U	10 U	0.4 U	1 U	1 U
Bromodichloromethane	ug/L	1	5 U	1 U	10 U	0.3 U	1 U	1 U
Bromoform	ug/L	4	5 U	1 U	10 U	1 U	1 U	1 U
Bromomethane	ug/L	NA	5 U	1 U	10 U	1 U	1 U	1 U
Carbon disulfide	ug/L	NA	5 U	1 U	10 U	1 U	1 U	1 U
Carbon tetrachloride	ug/L	2	5 U	1 U	10 U	1 U	1 U	1 U
Chlorobenzene	ug/L	4	5 U	1 U	10 U	1 U	1 U	1 U
Chloroethane	ug/L	NA	5 U	1 U	10 U	1 U	1 U	1 U
Chloroform	ug/L	6	5 U	0.3 J	10 U	1 U	2	0.4 J
Chloromethane	ug/L	NA	5 U	1 U	10 U	1 U	1 U	1 U
cis-1,3-Dichloropropene	ug/L	NA	1 U	0.2 U	2 U	0.4 U	0.2 U	0.2 U
Dibromochloromethane	ug/L	10	5 U	1 U	10 U	1 U	1 U	1 U
Ethylbenzene	ug/L	700	5 U	1 U	10 U	1 U	1 U	1 U
Methylene chloride	ug/L	3(4)	5 U	1 U	10 U	1 U	1 U	1 U
Styrene	ug/L	100	5 U	1 U	10 U	1 U	1 U	1 U
Tetrachloroethene	ug/L	1	5 U	1 U	10 U	2	1 U	0.1 J
Toluene	ug/L	1000	5 U	1 U	10 U	1 U	1 U	1 U
trans-1,3-Dichloropropene	ug/L	0.02	1 U	0.2 U	2 U	0.3 U	0.2 U	0.2 U
Trichloroethene	ug/L	1	79 D	120 E	49 D	25	4	0.9 J
Vinyl chloride	ug/L	5	5 U	0.3 J	10 U	1 U	1 U	1 U
Xylenes, total	ug/L	1000(2)	5 U	1 U	10 U	1 U	1 U	1 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812683 BRP1-101398 10/13/98	9812683DL BRP1-101398DL 10/13/98	9812563 BRP2-100998 10/9/98	9812563DL BRP2-100998DL 10/9/98	9812531 BRP-3-100898 10/8/98	9812856 WD-101698 10/16/98
1,1,1-Trichloroethane	ug/L	30	10 U	50 U	100 U	1000 U	1 U	1 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	10 U	50 U	100 U	1000 U	1 U	1 U
1,1,2-Trichloroethane	ug/L	3	10 U	50 U	100 U	1000 U	1 U	1 U
1,1-Dichloroethane	ug/L	50(3)	10 U	50 U	100 U	1000 U	1 U	1 U
1,1-Dichloroethene	ug/L	2	4 J	50 U	39 J	1000 U	1 U	16
1,2-Dichloroethane	ug/L	2	10 U	50 U	100 U	1000 U	1 U	1 U
1,2-Dichloroethene, cis-	ug/L	70	470 E	650 D	19000 E	2700 D	9	450
1,2-Dichloroethene, trans-	ug/L	100	4	6 J	100 U	1000 U	1 U	20
1,2-Dichloropropane	ug/L	1	10 U	50 U	100 U	1000 U	1 U	1 U
2-Butanone	ug/L	300	100	250 U	500 U	5000 U	5 U	5 U
2-Hexanone	ug/L	NA	50 U	250 U	500 U	5000 U	5 U	5 U
4-Methyl-2-pentanone	ug/L	400	50 U	250 U	500 U	5000 U	1 U	5 U
Acetone	ug/L	NA	50 U	250 U	500 U	5000 U	5 U	5 U
Benzene	ug/L	1	10 U	50 U	100 U	1000 U	1 U	1 U
Bromodichloromethane	ug/L	1	10 U	50 U	100 U	1000 U	1 U	1 U
Bromoform	ug/L	4	10 U	50 U	100 U	1000 U	1 U	1 U
Bromomethane	ug/L	NA	10 U	50 U	100 U	1000 U	1 U	1 U
Carbon disulfide	ug/L	NA	10 U	50 U	100 U	1000 U	1 U	1 U
Carbon tetrachloride	ug/L	2	10 U	50 U	100 U	1000 U	1 U	1 U
Chlorobenzene	ug/L	4	10 U	50 U	100 U	1000 U	1 U	1 U
Chloroethane	ug/L	NA	10 U	50 U	100 U	1000 U	1 U	1 U
Chloroform	ug/L	6	10 U	50 U	100 U	1000 U	1 U	1 U
Chloromethane	ug/L	NA	10 U	50 U	100 U	1000 U	1 U	1 U
cis-1,3-Dichloropropene	ug/L	NA	2 U	10 U	20 U	200 U	0.2 U	0.2 U
Dibromochloromethane	ug/L	10	10 U	50 U	100 U	1000 U	1 U	1 U
Ethylbenzene	ug/L	700	10 U	50 U	100 U	1000 U	1 U	1 U
Methylene chloride	ug/L	3(4)	10 U	50 U	100 U	1000 U	1 U	1 U
Styrene	ug/L	100	10 U	50 U	100 U	1000 U	1 U	1 U
Tetrachloroethene	ug/L	1	10 U	50 U	100 U	1000 U	1 U	1 U
Toluene	ug/L	1000	10 U	50 U	100 U	1000 U	1 U	1 U
trans-1,3-Dichloropropene	ug/L	0.02	2 U	10 U	20 U	200 U	0.2 U	0.2 U
Trichloroethene	ug/L	1	200	620 D	37 J	1000 U	5	110 E
Vinyl chloride	ug/L	5	110	180 D	15000 E	2300 D	1 U	380 E
Xylenes, total	ug/L	1000(2)	10 U	50 U	100 U	1000 U	1 U	1 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812856DL WD-101698DL 10/16/98	9812415 12S-100798 10/7/98	9812570 31S-100998 10/9/98	9812570RE 31S-100998RE 10/9/98	9812680 32S-101398 10/13/98	9812684 32S-101398DUP2 10/13/98
1,1,1-Trichloroethane	ug/L	30	200 U	20 U	5 J	4 JD	11	10
1,1,2,2-Tetrachloroethane	ug/L	1(6)	200 U	20 U	10 U	10 U	1 U	1 U
1,1,2-Trichloroethane	ug/L	3	200 U	20 U	10 U	10 U	1 U	1 U
1,1-Dichloroethane	ug/L	50(3)	200 U	20 U	15	17 D	7	7
1,1-Dichloroethene	ug/L	2	200 U	20 U	6 J	12 D	4	4
1,2-Dichloroethane	ug/L	2	200 U	20 U	10 U	10 U	1 U	1 U
1,2-Dichloroethene, cis-	ug/L	70	1000 D	240 D	27	27	1 U	1 U
1,2-Dichloroethene, trans-	ug/L	100	200 U	20 U	10 U	10 U	1 U	1 U
1,2-Dichloropropane	ug/L	1	200 U	20 U	10 U	10 U	1 U	1 U
2-Butanone	ug/L	300	1000 U	100 U	50 U	50 U	5 U	5 U
2-Hexanone	ug/L	NA	1000 U	100 U	50 U	50 U	5 U	5 U
4-Methyl-2-pentanone	ug/L	400	1000 U	100 U	50 U	50 U	5 U	5 U
Acetone	ug/L	NA	1000 U	100 U	50 U	50 U	5 U	5 U
Benzene	ug/L	1	200 U	20 U	10 U	10 U	1 U	1 U
Bromodichloromethane	ug/L	1	200 U	20 U	10 U	10 U	1 U	1 U
Bromoform	ug/L	4	200 U	20 U	10 U	10 U	1 U	1 U
Bromomethane	ug/L	NA	200 U	20 U	10 U	10 U	1 U	1 U
Carbon disulfide	ug/L	NA	200 U	20 U	2 J	10 U	1 U	1 U
Carbon tetrachloride	ug/L	2	200 U	20 U	10 U	10 U	1 U	1 U
Chlorobenzene	ug/L	4	200 U	20 U	10 U	10 U	1 U	1 U
Chloroethane	ug/L	NA	200 U	20 U	10 U	10 U	1 U	1 U
Chloroform	ug/L	6	200 U	20 U	10 U	10 U	1 U	1 U
Chloromethane	ug/L	NA	200 U	20 U	10 U	10 U	1 U	1 U
cis-1,3-Dichloropropene	ug/L	NA	40 U	4 U	2 U	2 U	0.2 U	0.2 U
Dibromochloromethane	ug/L	10	200 U	20 U	10 U	10 U	1 U	1 U
Ethylbenzene	ug/L	700	200 U	20 U	10 U	10 U	1 U	1 U
Methylene chloride	ug/L	3(4)	200 U	20 U	10 U	10 U	1 U	1 U
Styrene	ug/L	100	200 U	20 U	10 U	10 U	1 U	1 U
Tetrachloroethene	ug/L	1	200 U	20 U	10 U	10 U	1 U	1 U
Toluene	ug/L	1000	200 U	20 U	10 U	10 U	1 U	1 U
trans-1,3-Dichloropropene	ug/L	0.02	40 U	4 U	2 U	2 U	0.2 U	0.2 U
Trichloroethene	ug/L	1	54 JD	94 D	70	57 D	1 U	1 U
Vinyl chloride	ug/L	5	380 D	58 D	2 J	10 U	1 U	1 U
Xylenes, total	ug/L	1000(2)	200 U	20 U	10 U	10 U	1 U	1 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812311 37S-10/5/98 10/5/98	9812309 FB - 1 10/5/98	9812355 FB2-100698 10/6/98	9812411 FB3-100798 10/7/98	9812525 FB4-100898 10/8/98	9812588 FB5-101298 10/12/98
1,1,1-Trichloroethane	ug/L	30	1 U	1 U	1 U	1 U	1 U	1 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	1 U	1 U	1 U	1 U	1 U	1 U
1,1,2-Trichloroethane	ug/L	3	1 U	1 U	1 U	1 U	1 U	1 U
1,1-Dichloroethane	ug/L	50(3)	1 U	1 U	1 U	1 U	1 U	1 U
1,1-Dichloroethene	ug/L	2	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloroethane	ug/L	2	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloroethene, cis-	ug/L	70	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloroethene, trans-	ug/L	100	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloropropane	ug/L	1	0.4 U	0.4 U	1 U	1 U	1 U	1 U
2-Butanone	ug/L	300	5 U	5 U	5 U	5 U	5 U	5 U
2-Hexanone	ug/L	NA	5 U	5 U	5 U	5 U	5 U	5 U
4-Methyl-2-pentanone	ug/L	400	1 U	1 U	5 U	5 U	1 U	5 U
Acetone	ug/L	NA	5 U	5 U	5 U	5 U	5 U	5 U
Benzene	ug/L	1	0.4 U	0.4 U	1 U	1 U	1 U	1 U
Bromodichloromethane	ug/L	1	0.3 U	0.3 U	1 U	1 U	1 U	1 U
Bromoform	ug/L	4	1 U	1 U	1 U	1 U	1 U	1 U
Bromomethane	ug/L	NA	1 U	1 U	1 U	1 U	1 U	1 U
Carbon disulfide	ug/L	NA	1 U	1 U	1 U	1 U	1 U	1 U
Carbon tetrachloride	ug/L	2	1 U	1 U	1 U	1 U	1 U	1 U
Chlorobenzene	ug/L	4	1 U	1 U	1 U	1 U	1 U	1 U
Chloroethane	ug/L	NA	1 U	1 U	1 U	1 U	1 U	1 U
Chloroform	ug/L	6	3	6	4	1 U	1 U	0.6 J
Chloromethane	ug/L	NA	1 U	1 U	1 U	1 U	1 U	1 U
cis-1,3-Dichloropropene	ug/L	NA	0.4 U	0.4 U	0.2 U	0.2 U	0.2 U	0.2 U
Dibromochloromethane	ug/L	10	1 U	1 U	1 U	1 U	1 U	1 U
Ethylbenzene	ug/L	700	1 U	1 U	0.2 J	1 U	1 U	1 U
Methylene chloride	ug/L	3(4)	1 U	2	1 J	2	2	0.5 JB
Styrene	ug/L	100	1 U	1 U	1 U	1 U	1 U	1 U
Tetrachloroethene	ug/L	1	0.5 U	0.5 U	1 U	1 U	1 U	1 U
Toluene	ug/L	1000	1 U	1 U	1 U	1 U	1 U	1 U
trans-1,3-Dichloropropene	ug/L	0.02	0.3 U	0.3 U	0.2 U	0.2 U	0.2 U	0.2 U
Trichloroethene	ug/L	1	3	0.4 U	1 U	1 U	1 U	0.2 J
Vinyl chloride	ug/L	5	1 U	1 U	1 U	1 U	1 U	1 U
Xylenes, total	ug/L	1000(2)	1 U	1 U	0.3 J	1 U	1 U	1 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812593 FB6-101298 10/12/98	9812678 FB7-101398 10/13/98	9812753 FB8-101498 10/14/98	9812827 FB9-101598 10/15/98	9812310 TRIP BLANK 10/5/98	9812354 TRIP BLANK 10/6/98
1,1,1-Trichloroethane	ug/L	30	1 U	1 U	1 U	1 U	1 U	1 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	1 U	1 U	1 U	1 U	1 U	1 U
1,1,2-Trichloroethane	ug/L	3	1 U	1 U	1 U	1 U	1 U	1 U
1,1-Dichloroethane	ug/L	50(3)	1 U	1 U	1 U	1 U	1 U	1 U
1,1-Dichloroethene	ug/L	2	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloroethane	ug/L	2	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloroethene, cis-	ug/L	70	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloroethene, trans-	ug/L	100	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloropropane	ug/L	1	1 U	1 U	1 U	1 U	0.4 U	1 U
2-Butanone	ug/L	300	5 U	5 U	5 U	5 U	5 U	5 U
2-Hexanone	ug/L	NA	5 U	5 U	5 U	5 U	5 U	5 U
4-Methyl-2-pentanone	ug/L	400	5 U	5 U	5 U	5 U	1 U	5 U
Acetone	ug/L	NA	5 U	5 U	5 U	7 U	5 U	5 U
Benzene	ug/L	1	1 U	1 U	1 U	1 U	0.4 U	1 U
Bromodichloromethane	ug/L	1	1 U	1 U	1 U	1 U	0.3 U	1 U
Bromoform	ug/L	4	1 U	1 U	1 U	1 U	1 U	1 U
Bromomethane	ug/L	NA	1 U	1 U	1 U	1 U	1 U	1 U
Carbon disulfide	ug/L	NA	1 U	1 U	1 U	1 U	1 U	1 U
Carbon tetrachloride	ug/L	2	1 U	1 U	1 U	1 U	1 U	1 U
Chlorobenzene	ug/L	4	1 U	1 U	1 U	1 U	1 U	1 U
Chloroethane	ug/L	NA	1 U	1 U	1 U	1 U	1 U	1 U
Chloroform	ug/L	6	1 U	1 U	1 U	2 U	1 U	1 U
Chloromethane	ug/L	NA	1 U	1 U	1 U	1 U	1 U	1 U
cis-1,3-Dichloropropene	ug/L	NA	0.2 U	0.2 U	0.2 U	0.2 U	0.4 U	0.2 U
Dibromochloromethane	ug/L	10	1 U	1 U	1 U	1 U	1 U	1 U
Ethylbenzene	ug/L	700	1 U	1 U	1 U	1 U	1 U	1 U
Methylene chloride	ug/L	3(4)	1 B	2 U	1 U	3 B	1 U	1 U
Styrene	ug/L	100	1 U	1 U	1 U	1 U	1 U	1 U
Tetrachloroethene	ug/L	1	1 U	1 U	1 U	1 U	0.5 U	1 U
Toluene	ug/L	1000	1 U	1 U	1 U	1 U	1 U	1 U
trans-1,3-Dichloropropene	ug/L	0.02	0.2 U	0.2 U	0.2 U	0.2 U	0.3 U	0.2 U
Trichloroethene	ug/L	1	1 U	1 U	1 U	1 U	0.4 U	1 U
Vinyl chloride	ug/L	5	1 U	1 U	1 U	1 U	1 U	1 U
Xylenes, total	ug/L	1000(2)	1 U	1 U	1 U	1 U	1 U	1 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812410 TRIP BLANK 10/7/98	9812524 TRIP BLANK 10/8/98	9812566 TRIPBLANK 10/9/98	9812566RE TRIP BLANK 10/9/98	9812587 TRIP BLANK 10/12/98	9812677 TRIP BLANK 10/13/98
1,1,1-Trichloroethane	ug/L	30	1 U	1 U	1 U	1 U	1 U	1 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	1 U	1 U	1 U	1 U	1 U	1 U
1,1,2-Trichloroethane	ug/L	3	1 U	1 U	1 U	1 U	1 U	1 U
1,1-Dichloroethane	ug/L	50(3)	1 U	1 U	1 U	1 U	1 U	1 U
1,1-Dichloroethene	ug/L	2	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloroethane	ug/L	2	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloroethene, cis-	ug/L	70	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloroethene, trans-	ug/L	100	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloropropane	ug/L	1	1 U	1 U	1 U	1 U	1 U	1 U
2-Butanone	ug/L	300	5 U	5 U	5 U	5 U	5 U	5 U
2-Hexanone	ug/L	NA	5 U	5 U	5 U	5 U	5 U	5 U
4-Methyl-2-pentanone	ug/L	400	5 U	1 U	5 U	5 U	5 U	5 U
Acetone	ug/L	NA	5 U	5 U	5 U	5 U	5 U	5 U
Benzene	ug/L	1	1 U	1 U	1 U	1 U	1 U	1 U
Bromodichloromethane	ug/L	1	1 U	1 U	1 U	1 U	1 U	1 U
Bromoform	ug/L	4	1 U	1 U	1 U	1 U	1 U	1 U
Bromomethane	ug/L	NA	1 U	1 U	1 U	1 U	1 U	1 U
Carbon disulfide	ug/L	NA	1 U	1 U	1 U	1 U	1 U	1 U
Carbon tetrachloride	ug/L	2	1 U	1 U	1 U	1 U	1 U	1 U
Chlorobenzene	ug/L	4	1 U	1 U	1 U	1 U	1 U	1 U
Chloroethane	ug/L	NA	1 U	1 U	1 U	1 U	1 U	1 U
Chloroform	ug/L	6	1 U	1 U	1 U	1 U	1 U	1 U
Chloromethane	ug/L	NA	1 U	1 U	1 U	1 U	1 U	1 U
cis-1,3-Dichloropropene	ug/L	NA	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
Dibromochloromethane	ug/L	10	1 U	1 U	1 U	1 U	1 U	1 U
Ethylbenzene	ug/L	700	1 U	1 U	1 U	1 U	1 U	1 U
Methylene chloride	ug/L	3(4)	0.8 J	1 U	1 U	1 U	1 U	1 U
Styrene	ug/L	100	1 U	1 U	1 U	1 U	1 U	1 U
Tetrachloroethene	ug/L	1	1 U	1 U	1 U	1 U	1 U	1 U
Toluene	ug/L	1000	0.1 J	1 U	1 U	1 U	1 U	1 U
trans-1,3-Dichloropropene	ug/L	0.02	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
Trichloroethene	ug/L	1	0.8 J	1 U	1 U	1 U	1 U	1 U
Vinyl chloride	ug/L	5	1 U	1 U	1 U	1 U	1 U	1 U
Xylenes, total	ug/L	1000(2)	1 U	1 U	1 U	1 U	1 U	1 U

TABLE 1A (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812752 TRIP BLANK 10/14/98	9812828 TRIP BLANK 10/15/98	9812857 TRIP BLANK 10/16/98
1,1,1-Trichloroethane	ug/L	30	1 U	1 U	1 U
1,1,2,2-Tetrachloroethane	ug/L	1(6)	1 U	1 U	1 U
1,1,2-Trichloroethane	ug/L	3	1 U	1 U	1 U
1,1-Dichloroethane	ug/L	50(3)	1 U	1 U	1 U
1,1-Dichloroethene	ug/L	2	1 U	1 U	1 U
1,2-Dichloroethane	ug/L	2	1 U	1 U	1 U
1,2-Dichloroethene, cis-	ug/L	70	1 U	1 U	1 U
1,2-Dichloroethene, trans-	ug/L	100	1 U	1 U	1 U
1,2-Dichloropropane	ug/L	1	1 U	1 U	1 U
2-Butanone	ug/L	300	5 U	5 U	5 U
2-Hexanone	ug/L	NA	5 U	5 U	5 U
4-Methyl-2-pentanone	ug/L	400	5 U	5 U	5 U
Acetone	ug/L	NA	5 U	5 U	5 U
Benzene	ug/L	1	1 U	1 U	1 U
Bromodichloromethane	ug/L	1	1 U	1 U	1 U
Bromoform	ug/L	4	1 U	1 U	1 U
Bromomethane	ug/L	NA	1 U	1 U	1 U
Carbon disulfide	ug/L	NA	1 U	1 U	1 U
Carbon tetrachloride	ug/L	2	1 U	1 U	1 U
Chlorobenzene	ug/L	4	1 U	1 U	1 U
Chloroethane	ug/L	NA	1 U	1 U	1 U
Chloroform	ug/L	6	1 U	1 U	1 U
Chloromethane	ug/L	NA	1 U	1 U	1 U
cis-1,3-Dichloropropene	ug/L	NA	0.2 U	0.2 U	0.2 U
Dibromochloromethane	ug/L	10	1 U	1 U	1 U
Ethylbenzene	ug/L	700	1 U	1 U	1 U
Methylene chloride	ug/L	3(4)	1 U	1 U	1 U
Styrene	ug/L	100	1 U	1 U	1 U
Tetrachloroethene	ug/L	1	1 U	1 U	1 U
Toluene	ug/L	1000	1 U	1 U	1 U
trans-1,3-Dichloropropene	ug/L	0.02	0.2 U	0.2 U	0.2 U
Trichloroethene	ug/L	1	1 U	1 U	1 U
Vinyl chloride	ug/L	5	1 U	1 U	1 U
Xylenes, total	ug/L	1000(2)	1 U	1 U	1 U

TABLE 1B
SUMMARY OF STORM DRAIN WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Surface Water Quality Criteria	9812824 OF22-101598 10/15/98	9812824DL OF22-101598 10/15/98	9812825 OF22-101598DUP5 10/15/98	9812825DL OF22-101598DUP5DL 10/15/98	9812826 OF23-101598 10/15/98	9812823 OF24-101598 10/15/98
1,1,1-Trichloroethane	ug/L	127	1 U	5 U	1 U	5 U	1 U	1 U
1,1,2,2-Tetrachloroethane	ug/L	1.72	1 U	5 U	1 U	5 U	1 U	1 U
1,1,2-Trichloroethane	ug/L	13.5	1 U	5 U	1 U	5 U	1 U	1 U
1,1-Dichloroethane	ug/L	NA	1 U	5 U	1 U	5 U	1 U	1 U
1,1-Dichloroethene	ug/L	4.81	1 U	5 U	1 U	5 U	1 U	1 U
1,2-Dichloroethane	ug/L	0.291	1 U	5 U	1 U	5 U	1 U	1 U
1,2-Dichloroethene, cis-	ug/L	NA	130 E	110 D	130 E	110 D	1 U	1 U
1,2-Dichloroethene, trans-	ug/L	592	1 U	5 U	1 U	5 U	1 U	1 U
1,2-Dichloropropane	ug/L	NA	1 U	5 U	1 U	5 U	1 U	1 U
2-Butanone	ug/L	NA	5 U	25 U	5 U	25 U	5 U	5 U
2-Hexanone	ug/L	NA	5 U	25 U	5 U	25 U	5 U	5 U
4-Methyl-2-pentanone	ug/L	NA	5 U	25 U	5 U	25 U	5 U	5 U
Acetone	ug/L	NA	5 U	6 JD	5 U	25 U	6 U	5 U
Benzene	ug/L	0.15	1 U	5 U	1 U	5 U	1 U	1 U
Bromodichloromethane	ug/L	0.266	1 U	5 U	1 U	5 U	1 U	1 U
Bromoform	ug/L	4.38	1 U	5 U	1 U	5 U	1 U	1 U
Bromomethane	ug/L	NA	1 U	5 U	1 U	5 U	1 U	1 U
Carbon disulfide	ug/L	NA	1 U	5 U	1 U	5 U	1 U	1 U
Carbon tetrachloride	ug/L	0.363	1 U	5 U	1 U	5 U	1 U	1 U
Chlorobenzene	ug/L	22.0	1 U	5 U	1 U	5 U	1 U	1 U
Chloroethane	ug/L	NA	1 U	5 U	1 U	5 U	1 U	1 U
Chloroform	ug/L	NA	1 U	5 U	1 U	5 U	1 U	1 U
Chloromethane	ug/L	NA	1 U	5 U	1 U	5 U	1 U	1 U
cis-1,3-Dichloropropene	ug/L	0.193 (7)	0.2 U	1 U	0.2 U	1 U	0.2 U	0.2 U
Dibromochloromethane	ug/L	72.6	1 U	5 U	1 U	5 U	1 U	1 U
Ethylbenzene	ug/L	3,030	1 U	5 U	1 U	5 U	1 U	1 U
Methylene chloride	ug/L	2.49	1 U	5 U	1 U	5 U	1 U	1 U
Styrene	ug/L	NA	1 U	5 U	1 U	5 U	1 U	1 U
Tetrachloroethene	ug/L	0.388	1 U	5 U	1 U	5 U	1 U	1 U
Toluene	ug/L	7,440	1 U	5 U	1 U	5 U	1 U	1 U
trans-1,3-Dichloropropene	ug/L	0.193 (7)	0.2 U	1 U	0.2 U	1 U	0.2 U	0.2 U
Trichloroethene	ug/L	1.09	160 E	150 D	150 E	140 D	1 U	1 U
Vinyl chloride	ug/L	0.0830	24	18 D	24	17 D	1 U	1 U
Xylenes, total	ug/L	NA	1 U	5 U	1 U	5 U	1 U	1 U

TABLE 1B (continued)
SUMMARY OF STORM DRAIN WATER ANALYSES FOR VOLATILES
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Surface Water Quality Criteria	9812822 OF25-101598 10/15/98	9812821 ST26-101598 10/15/98	9812820 ST27-101598 10/15/98
1,1,1-Trichloroethane	ug/L	127	1 U	1 U	1 U
1,1,2,2-Tetrachloroethane	ug/L	1.72	1 U	1 U	1 U
1,1,2-Trichloroethane	ug/L	13.5	1 U	1 U	1 U
1,1-Dichloroethane	ug/L	NA	1 U	1 U	1 U
1,1-Dichloroethene	ug/L	4.81	1 U	1 U	1 U
1,2-Dichloroethane	ug/L	0.291	1 U	1 U	1 U
1,2-Dichloroethene, cis-	ug/L	NA	1 U	1 U	1 U
1,2-Dichloroethene, trans-	ug/L	592	1 U	1 U	1 U
1,2-Dichloropropane	ug/L	NA	1 U	1 U	1 U
2-Butanone	ug/L	NA	5 U	5 U	5 U
2-Hexanone	ug/L	NA	5 U	5 U	5 U
4-Methyl-2-pentanone	ug/L	NA	5 U	5 U	5 U
Acetone	ug/L	NA	5 U	5 U	5 U
Benzene	ug/L	0.15	1 U	1 U	1 U
Bromodichloromethane	ug/L	0.266	1 U	1 U	1 U
Bromoform	ug/L	4.38	1 U	1 U	1 U
Bromomethane	ug/L	NA	1 U	1 U	1 U
Carbon disulfide	ug/L	NA	1 U	1 U	1 U
Carbon tetrachloride	ug/L	0.363	1 U	1 U	1 U
Chlorobenzene	ug/L	22.0	1 U	1 U	1 U
Chloroethane	ug/L	NA	1 U	1 U	1 U
Chloroform	ug/L	NA	1 U	1 U	1 U
Chloromethane	ug/L	NA	1 U	1 U	1 U
cis-1,3-Dichloropropene	ug/L	0.193	0.2 U	0.2 U	0.2 U
Dibromochloromethane	ug/L	72.6	1 U	1 U	1 U
Ethylbenzene	ug/L	3,030	1 U	1 U	1 U
Methylene chloride	ug/L	2.49	1 U	1 U	1 U
Styrene	ug/L	NA	1 U	1 U	1 U
Tetrachloroethene	ug/L	0.388	1 U	1 U	1 U
Toluene	ug/L	7,440	1 U	1 U	1 U
trans-1,3-Dichloropropene	ug/L	0.193	0.2 U	0.2 U	0.2 U
Trichloroethene	ug/L	1.09	1 U	1 U	1 U
Vinyl chloride	ug/L	0.0830	1 U	1 U	1 U
Xylenes, total	ug/L	NA	1 U	1 U	1 U

TABLE 2
SUMMARY OF GROUND-WATER ANALYSES FOR METALS
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812414 02BR-100798 10/7/98	9812312 03BR-100598 10/5/98	9812571 04BR-100998 10/9/98	9812757 5BR-101498 10/14/98	9812419 MW6BR-100798 10/7/98	9812530 07BR-100898 10/8/98
Barium	ug/L	2000	8.9 B	18.3 B	158 B	73.3 B	134 B	265
Calcium	ug/L	NA	26500	29400	45200 N	58800	39000	65400 N
Iron	ug/L	300	12700	13.0 U	1090	39.5 B	33.7 B	2740
Magnesium	ug/L	NA	10200	10400	11900	17300	13200	20400
Potassium	ug/L	NA	1320 B	1130 B	2320	1180 B	1380 B	2430
Sodium	ug/L	50,000	13100	9080	23000	10900	9190	18900

Analyte	Units	NJDEP Groundwater Quality Criteria	9812569 08BR-100998 10/9/98	9812416 9BR-100798 10/7/98	9812360 11BR-100698 10/6/98	9812413 12BR-100798 10/7/98	9812564 15BR-100998 10/9/98	9812565 15BR-100998 10/9/98
Barium	ug/L	2000	26.6 B	8.5 B	7.0 U	23.2 B	387	118 B
Calcium	ug/L	NA	32500 N	31700	17900	32100	61300 N	47800 N
Iron	ug/L	300	106	2110	13.0 U	13.0 U	648	13.0 U
Magnesium	ug/L	NA	12900	10500	6280	11100	22300	15900
Potassium	ug/L	NA	1710	1470 B	884 B	1210 B	2320	1550
Sodium	ug/L	50,000	22200	12200	10100	9560	15700	17400

Analyte	Units	NJDEP Groundwater Quality Criteria	9812756 16BR-101498 10/14/98	9812357 19BR-100698 10/6/98	9812755 20BR-101498 10/14/98	9812356 21BR-100698 10/6/98	9812568 22BR-100998 10/9/98	9812526 27BR-100898 10/8/98
Barium	ug/L	2000	122 B	13.5 B	84.2 B	19.1 B	21.0 B	120 B
Calcium	ug/L	NA	50800	27600	57200	34700	51400 N	29500 N
Iron	ug/L	300	37.8 B	13.0 U	1360	484	18.2 B	182
Magnesium	ug/L	NA	16600	12000	18900	10200	13400	10900
Potassium	ug/L	NA	1720 B	2150 B	1770 B	2010 B	877 B	3480
Sodium	ug/L	50,000	18200	15900	17600	17100	12600	11300

TABLE 2 (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR METALS
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812358 28BR-100698 10/6/98	9812567 29BR-100998 10/9/98	9812681 30BR-101398 10/13/98	9812523 31BR-100898 10/8/98	9812679 33BR-101398 10/13/98	9812412 MW34BR-100798 10/7/98
Barium	ug/L	2000	35.5 B	166 B	513	8.2 B	179 B	7.0 U
Calcium	ug/L	NA	47200	29700 N	38200	31000 N	53100	49100
Iron	ug/L	300	26.7 B	53.4 B	554	13.0 U	564	200
Magnesium	ug/L	NA	16200	12000	17000	13100	19900	10600
Potassium	ug/L	NA	949 B	2130	2550 B	2220	2280 B	865 B
Sodium	ug/L	50,000	9770	17200	34300	15100	21400	11000

Analyte	Units	NJDEP Groundwater Quality Criteria	9812819 35BR-101598 10/15/98	9812759 36BR-101498 10/14/98	9812359 37BR-100698 10/6/98	9812682 38BR-101398 10/13/98	9812527 39BR-100898 10/8/98	9812532 40BR-100898 10/8/98
Barium	ug/L	2000	7.4 U	315	200	644	114 B	84.0 B
Calcium	ug/L	NA	24900	34000	22500	43500	24800 N	28700 N
Iron	ug/L	300	70.8 B	1120	508	436	368	167
Magnesium	ug/L	NA	8460	14700	8570	19200	9960	11300
Potassium	ug/L	NA	10300	2110 B	1890 B	2500 B	2230	1990
Sodium	ug/L	50,000	8350	12900	10700	20800	15400	10300

Analyte	Units	NJDEP Groundwater Quality Criteria	9812565 41BR-100998 10/09/98	9812528 42BR-100898 10/8/98	9812591 43BR-101298 10/12/98	9812592 44BR-101298 10/12/98	9812760 45BR-101498 10/14/98	9812761 45BR-101498DUP3 10/14/98
Barium	ug/L	2000	118 B	27.7 B	7.4 U	7.4 U	194 B	193 B
Calcium	ug/L	NA	47800	2190 N	1760 B	1400 B	33700	33200
Iron	ug/L	300	13.0 U	13.0 U	139	68.4 B	346	258
Magnesium	ug/L	NA	15900	729 B	32.9 U	35.2 B	11900	11800
Potassium	ug/L	NA	1550	5000	64000	21300	1640 B	1450 B
Sodium	ug/L	50,000	17400	63000	197000	90100	12700	13100

TABLE 2 (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR METALS
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812594 46BR-101298 10/12/98	9812529 47BR-100898 10/8/98	9812562 48BR-100998 10/9/98	9812595 49BR-101298 10/12/98	9812754 50BR-101498 10/14/98	9812758 50BR-101498DUP4 10/14/98
Barium	ug/L	2000	176 B	31.3 B	20.3 B	12.3 B	7.4 U	7.4 U
Calcium	ug/L	NA	8130	38000 N	35700 N	23600	35700	35900
Iron	ug/L	300	291	2430	13.0 U	561	131	122
Magnesium	ug/L	NA	32.9 U	16200	12100	9220	11200	11300
Potassium	ug/L	NA	22500	1830	1190	1570 B	1180 B	1280 B
Sodium	ug/L	50,000	97000	28900	10600	15600	9210	9100

Analyte	Units	NJDEP Groundwater Quality Criteria	9812417 51BR-100798 10/7/98	9812418 51BR-100798DUP1 10/07/98	9812313 11MW1-100598 10/5/98	9812589 35MW1-101298 10/12/98	9812590 35MW2-101298 10/12/98	9812531 BRP1-100898 10/8/98
Barium	ug/L	2000	7.0 U	7.0 U	39.0 B	40.3 B	164 B	96.0 B
Calcium	ug/L	NA	32500	30600	7400	11000	12900	48500 N
Iron	ug/L	300	13.0 U	13.0 U	35.8 B	28.0 B	19.9 B	1700
Magnesium	ug/L	NA	8890	8810	4660 B	10100	9120	20700
Potassium	ug/L	NA	2950 B	3490 B	1460 B	2670 B	2410 B	3440
Sodium	ug/L	50,000	11700	12100	7900	28700	18000	18300

Analyte	Units	NJDEP Groundwater Quality Criteria	9812563 BRP2-100998 10/8/98	9812683 BRP1-101398 10/13/98	9812531 BRP-3-100898 10/08/98	9812856 WD-101698 10/16/98	9812415 12S-100798 10/7/98	9812570 31S-100998 10/9/98
Barium	ug/L	2000	309	49.8 B	96.0 B	118 B	36.4 B	20.7 B
Calcium	ug/L	NA	78000 N	51900	48500 N	59800	35800	20000 N
Iron	ug/L	300	4260	2720	1700	3050	2660	1780
Magnesium	ug/L	NA	27000	17500	20700	20300	19600	6860
Potassium	ug/L	NA	2820	1860 B	3440	2520 B	3310 B	2360
Sodium	ug/L	50,000	48600	31100	18300	20900	21700	25500

TABLE 2 (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR METALS
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812680 32S-101398 10/13/98	9812684 32S-101398DUP2 10/13/98	9812311 37S-10/5/98 10/5/98	9812309 FB-1 10/5/98	9812355 FB2-100698 10/6/98	9812411 FB3-100798 10/7/98
Barium	ug/L	2000	90.0 B	88.9 B	658	7.0 U	7.0 U	7.0 U
Calcium	ug/L	NA	37900	38200	118000	149 B	84.8 B	37.0 U
Iron	ug/L	300	29.8 B	13.0 U	13.0 U	13.0 U	13.0 U	13.0 U
Magnesium	ug/L	NA	14300	14400	57000	78.3 B	82.5 B	33.0 U
Potassium	ug/L	NA	2180 B	2110 B	5660	84.0 U	84.0 U	84.0 U
Sodium	ug/L	50,000	28100	28200	35700	220 B	204 B	28.0 U

Analyte	Units	NJDEP Groundwater Quality Criteria	9812525 FB4-100898 10/8/98	9812588 FB5-101298 10/12/98	9812678 FB7-101398 10/13/98	9812753 FB8-101498 10/14/98	9812827 FD9101598 10/15/98
Barium	ug/L	2000	5.1 U	7.4 U	7.4 U	7.4 U	7.4 U
Calcium	ug/L	NA	72.3 BN	31.8 B	41.0 B	51.1 B	21.8 B
Iron	ug/L	300	13.0 U	13.0 U	13.0 U	13.0 U	13.0 U
Magnesium	ug/L	NA	39.0 U	32.9 U	32.9 U	32.9 U	32.9 U
Potassium	ug/L	NA	84.2 U	84.2 U	84.2 U	84.2 U	84.2 U
Sodium	ug/L	50,000	331 B	28.1 U	55.6 B	28.1 U	28.1 U

TABLE 3
SUMMARY OF GROUND-WATER ANALYSES FOR GENERAL CHEMISTRY PARAMETERS
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812414 02BR-100798 10/07/98	9812312 03BR-100598 10/05/98	9812571 04BR-100998 10/09/98	9812757 5BR-101498 10/14/98	9812419 MW6BR-100798 10/07/98	9812530 07BR-100898 10/08/98
TDS	mg/L	NA	131	134	288	280	249	341
Ammonia, dissolved	mg/L	NA	0.11	0.10 U	0.46	0.11	0.21	0.12
DOC	mg/L	NA	1.7	0.20	2.7	0.42	0.47	7.7

Analyte	Units	NJDEP Groundwater Quality Criteria	9812569 08BR-100998 10/09/98	9812416 9BR-100798 10/07/98	9812360 11BR-100698 10/06/98	9812413 12BR-100798 10/07/98	9812564 15BR-100998 10/09/98	9812756 16BR-101498 10/14/98
TDS	mg/L	NA	291	173	78.0	196	336	273
Ammonia, dissolved	mg/L	NA	0.10 U	0.14	0.10 U	0.11	0.11	0.10 U
DOC	mg/L	NA	0.88	1.5	0.36	0.61	4.3	1.3

Analyte	Units	NJDEP Groundwater Quality Criteria	9812357 19BR-100698 10/06/98	9812755 20BR-101498 10/14/98	9812356 21BR-100698 10/06/98	9812568 22BR-100998 10/09/98	9812526 27BR-100898 10/08/98	9812358 28BR-100698 10/06/98
TDS	mg/L	NA	219	437	256	274	10.0 U	173
Ammonia, dissolved	mg/L	NA	0.15	0.28	0.35	0.10 U	0.10 U	0.17
DOC	mg/L	NA	0.41	2.2	0.54	0.82	1.0	0.49

Analyte	Units	NJDEP Groundwater Quality Criteria	9812567 29BR-100998 10/09/98	9812681 30BR-101398 10/13/98	9812523 31BR-100898 10/08/98	9812679 33BR-101398 10/13/98	9812412 MW34BR-100798 10/07/98	9812819 35BR101598 10/15/98
TDS	mg/L	NA	218	287	448	288	200	1.8
Ammonia, dissolved	mg/L	NA	0.10 U	0.21	0.10	0.11	0.12	0.26
DOC	mg/L	NA	0.72	2.2	0.77	1.3	0.62	10.0 U

TABLE 3 (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR GENERAL CHEMISTRY PARAMETERS
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812759 36BR-101498 10/14/98	9812359 37BR-100698 10/06/98	9812682 38BR-101398 10/13/98	9812527 39BR-100898 10/08/98	9812532 40BR-100898 10/08/98	9812565 41BR-100998 10/09/98
TDS	mg/L	NA	233	141	290	92.0	169	242
Ammonia, dissolved	mg/L	NA	0.11	0.17	0.25	0.10 U	0.11	0.10 U
DOC	mg/L	NA	1.4	0.20	1.4	0.79		0.98

Analyte	Units	NJDEP Groundwater Quality Criteria	9812528 42BR-100898 10/08/98	9812591 43BR-101298 10/12/98	9812592 44BR-101298 10/12/98	9812760 45BR-101498 10/14/98	9812761 45BR-101498DUP3 10/14/98	9812594 46BR-101298 10/12/98
TDS	mg/L	NA	166	1510	330	219	221	313
Ammonia, dissolved	mg/L	NA	0.12	0.37	0.39	0.18	0.11	0.67
DOC	mg/L	NA	0.71	3.7	2.1	0.65	0.66	2.1

Analyte	Units	NJDEP Groundwater Quality Criteria	9812529 47BR-100898 10/08/98	9812562 48BR-100998 10/09/98	9812595 49BR-101298 10/12/98	9812754 50BR-101498 10/14/98	9812758 50BR-101498DUP4 10/14/98	9812417 51BR-100798 10/07/98
TDS	mg/L	NA	310	200	182	210	181	190
Ammonia, dissolved	mg/L	NA	0.15	0.10	0.17	0.10 U	0.10 U	0.11
DOC	mg/L	NA	3.9	0.60	0.66	0.57	0.39	0.72

Analyte	Units	NJDEP Groundwater Quality Criteria	9812418 51BR-100798DUP1 10/07/98	9812313 11MW1-100598 10/05/98	9812589 35MW1-101298 10/12/98	9812590 35MW2-101298 10/12/98	9812683 BRP1-101398 10/13/98	9812563 BRP2-100998 10/09/98
TDS	mg/L	NA	185		257	182	325	522
Ammonia, dissolved	mg/L	NA	0.26	0.17	0.21	0.10	0.19	0.18
DOC	mg/L	NA	0.71		0.98	0.65	2.8	7.4

TABLE 3 (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR GENERAL CHEMISTRY PARAMETERS
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812531 BRP-3-100898 10/08/98	9812415 12S-100798 10/07/98	9812570 31S-100998 10/09/98	9812680 32S-101398 10/13/98	9812684 32S-101398DUP2 10/13/98	9812311 37S-10/5/98 10/05/98
TDS	mg/L	NA	350	210	114	290	290	1020
Ammonia, dissolved	mg/L	NA	0.14	0.21	0.35	0.12	0.25	0.10 U
DOC	mg/L	NA	3.4	3.2	2.8	2.8	2.7	0.24

Analyte	Units	NJDEP Groundwater Quality Criteria	9812856 WD-101698 10/16/98	9812309 FB-1 10/05/98	9812355 FB2-100698 10/06/98	9812411 FB3-100798 10/07/98	9812525 FB4-100898 10/08/98	9812588 FB5-101298 10/12/98
TDS	mg/L	NA	364	10.0	29.0	30.0	287	41.0
Ammonia, dissolved	mg/L	NA	0.28	0.28	0.16	0.11	0.10 U	0.21
DOC	mg/L	NA	2.8	0.81	0.20 U	0.20 U	0.86	0.20 U

Analyte	Units	NJDEP Groundwater Quality Criteria	9812678 FB7-101398 10/13/98	9812753 FB8-101498 10/14/98	9812827 FD9101598 10/15/98
TDS	mg/L	NA	10.0 U	13.0	0.51
Ammonia, dissolved	mg/L	NA	0.13	0.20	0.11
DOC	mg/L	NA	0.24	0.43	10.0 U

TABLE 4
SUMMARY OF GROUND-WATER ANALYSES FOR THE ANIONS
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812414 02BR-100798 10/7/98	9812312 03BR-100598 10/5/98	9812312DL 03BR-100598 10/6/98	9812571 04BR-100998 10/09/98	9812571DL 04BR-100998DL 10/09/98	9812757 5BR-101498 10/14/98	9812757DL 5BR-101498DL 10/14/98
Chloride	mg/L	250	7.6	64	6.7 D	42 E	40 D	25 E	24 D
Nitrogen, nitrate	mg/L	10	0.10 U	0.27	0.27 D	0.10 U	0.50 U	2.5	2.3 D
Sulfate	mg/L	250	3.3	27 E	25 D	91 E	86 D	56 E	52 D

Analyte	Units	NJDEP Groundwater Quality Criteria	9812419 MW6BR-100798 10/7/98	9812419DL MW6BR-100798 10/7/98	9812530 07BR-100898 10/08/98	9812530DL 07BR-100898DL 10/08/98	9812569 08BR-100998 10/09/98	9812569DL 08BR-100998DL 10/09/98	9812416 9BR-100798 10/7/98
Chloride	mg/L	250	8.9	9.1 D	85 E	84 D	11	11 D	21 E
Nitrogen, nitrate	mg/L	10	0.10 U	0.20 U	0.10 U	0.50 U	0.10 U	0.20 U	0.10 U
Sulfate	mg/L	250	36 E	34 D	9.2	8.7 D	21 E	20 D	0.46

Analyte	Units	NJDEP Groundwater Quality Criteria	9812416DL 9BR-100798DL 10/7/98	9812360 11BR-100698 10/6/98	9812360DL 11BR-100698DL 10/6/98	9812413 12BR-100798 10/7/98	9812564 15BR-100998 10/09/98	9812564DL 15BR-100998DL 10/09/98	9812756 16BR-101498 10/14/98
Chloride	mg/L	250	21 D	7.2	7.1 D	4.2	63 E	61 D	37 E
Nitrogen, nitrate	mg/L	10	0.20 U	1.7	1.5 D	0.80	0.10 U	0.50 U	0.10 U
Sulfate	mg/L	250	0.53 D	21 E	19 D	17	21 E	19 D	29 E

Analyte	Units	NJDEP Groundwater Quality Criteria	9812756DL 16BR-101498DL 10/14/98	9812357 19BR-100698 10/6/98	9812755 20BR-101498 10/14/98	9812755DL 20BR-101498DL 10/14/98	9812356 21BR-100698 10/6/98	9812356DL 21BR-100698 10/6/98	9812568 22BR-100998 10/09/98
Chloride	mg/L	250	39 D	2.9	71 E	70 D	54 E	50 D	33 E
Nitrogen, nitrate	mg/L	10	0.20 U	0.29	0.10 U	0.50 U	2.3	2.1 D	2.2
Sulfate	mg/L	250	29 D	19	13	12 D	19	17 D	49 E

TABLE 4 (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR THE ANIONS
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812568DL 22BR-100998DL 10/09/98	9812526 27BR-100898 10/08/98	9812358 28BR-100698 10/6/98	9812358DL 28BR-100698DL 10/6/98	9812567 29BR-100998 10/09/98	9812681 30BR-101398 10/13/98	9812681DL 30BR-101398DL 10/13/98
Chloride	mg/L	250	32 D	8.4	14	14 D	6.9	50 E	49 D
Nitrogen, nitrate	mg/L	10	2.1 D	0.10 U	2.9	2.7 D	0.10 U	0.10 U	0.50 U
Sulfate	mg/L	250	45 D	19	43 E	41 D	18	12	12 D

Analyte	Units	NJDEP Groundwater Quality Criteria	9812523 31BR-100898 10/8/98	9812679 33BR-101398 10/13/98	9812679DL 33BR-101398DL 10/13/98	9812412 MW34BR-100798 10/0/798	9812412DL MW34BR-100798DL 10/7/98	9812819 35BR-101598 10/15/98	9812759 36BR-101498 10/14/98
Chloride	mg/L	250	8.7	19	19 D	13	13 D	6.1	15
Nitrogen, nitrate	mg/L	10	0.10 U	0.10 U	0.20 U	3.5	3.2 D	1.9	0.10 U
Sulfate	mg/L	250	18	26 E	25 D	54 E	50 D	15	28 E

Analyte	Units	NJDEP Groundwater Quality Criteria	9812759DL 36BR-101498DL 10/14/98	9812359 37BR-100698 10/6/98	9812359DL 37BR-100698DL 10/6/98	9812682 38BR-101398 10/13/98	9812682DL 38BR-101398DL 10/13/98	9812527 39BR-100898 10/08/98	9812532 40BR-100898 10/08/98
Chloride	mg/L	250	14 D	4.1	4.5 D	45 E	46 D	4.6	9.9
Nitrogen, nitrate	mg/L	10	0.20 U	0.10 U	0.20 U	0.10 U	0.50 U	0.10 U	0.10 U
Sulfate	mg/L	250	26 D	28 E	27 D	20	19 D	8.8	23 E

Analyte	Units	NJDEP Groundwater Quality Criteria	9812532DL 40BR-100898DL 10/08/98	9812565 41BR-100998 10/09/98	9812565DL 41BR-100998DL 10/09/98	9812528 42BR-100898 10/08/98	9812591 43BR-101298 10/12/98	9812591DL 43BR-101298DL 10/12/98	9812592 44BR-101298 10/12/98
Chloride	mg/L	250	10 D	31 E	32 D	2.9	70 E	72	7.1
Nitrogen, nitrate	mg/L	10	0.20 U	0.11	0.20 U	0.10 U	0.20 U	0.50 U	0.20 U
Sulfate	mg/L	250	22 D	28 E	27 D	6.4	1.7	1.6	38

TABLE 4 (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR THE ANIONS
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812760 45BR-101498 10/14/98	9812760DL 45BR-101498DL 10/14/98	9812761 45BR-101498DUP3 10/14/98	9812761DL 45BR-101498DUP3DL 10/14/98	9812594 46BR-101298 10/12/98	9812529 47BR-100898 10/08/98	9812529DL 47BR-100898DL 10/08/98
Chloride	mg/L	250	12	12 D	12	12 D	9.0	22 E	23 D
Nitrogen, nitrate	mg/L	10	0.10 U	0.20 U	0.10 U	0.20 U	0.20 U	0.10 U	0.20 U
Sulfate	mg/L	250	29 E	28 D	29 E	28 D	7.1	7.1	7.2 D

Analyte	Units	NJDEP Groundwater Quality Criteria	9812562 48BR-100998 10/09/98	9812595 49BR-101298 10/12/98	9812754 50BR-101498 10/14/98	9812754DL 50BR-101498DL 10/14/98	9812758 50BR-101498DUP4 10/14/98	9812758DL 50BR-101498DUP4DL 10/14/98	9812417 51BR-100798 10/7/98
Chloride	mg/L	250	6.6	5.8	6.2	7.1 D	6.2	6.7 D	6.2
Nitrogen, nitrate	mg/L	10	0.10 U	0.10 U	0.19	0.20 U	0.18	0.20 U	0.52
Sulfate	mg/L	250	17	14	31 E	30 D	31 E	30 D	22 E

Analyte	Units	NJDEP Groundwater Quality Criteria	9812417DL 51BR-100798DL 10/7/98	9812418 51BR-100798DUP1 10/7/98	9812418DL 51BR-100798DUP1DL 10/7/98	9812313 11MW1-100598 10/5/98	9812313DL 11MW1-100598 10/6/98	9812589 35MW1-101298 10/12/98	9812589DL 35MW1-101298DL 10/12/98
Chloride	mg/L	250	6.4 D	6.1	6.5 D	7.0	7.3 D	59 E	57 D
Nitrogen, nitrate	mg/L	10	0.52 D	0.56	0.53 D	2.1	2.0 D	2.3	2.3 D
Sulfate	mg/L	250	21 D	22 E	21 D	22 E	20 D	55 E	50 D

Analyte	Units	NJDEP Groundwater Quality Criteria	9812590 35MW2-101298 10/12/98	9812590DL 35MW2-101298DL 10/12/98	9812683 BRP1-101398 10/13/98	9812683DL BRP1-101398DL 10/13/98	9812563 BRP2-100998 10/09/98	9812563DL BRP2-100998DL 10/09/98	9812531 BRP-3-100898 10/08/98
Chloride	mg/L	250	62 E	61 D	34 E	35 D	150 E	150 D	27 E
Nitrogen, nitrate	mg/L	10	1.6	1.6 D	0.10 U	0.20 U	0.10 U	1.0 U	3.4
Sulfate	mg/L	250	23 E	22 D	31 E	30 D	2.1	3.0 D	77 E

TABLE 4 (continued)
SUMMARY OF GROUND-WATER ANALYSES FOR THE ANIONS
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

Analyte	Units	NJDEP Groundwater Quality Criteria	9812531DL BRP-3-100898DL 10/08/98	9812856 WD-101698 10/16/98	9812856DL WD-101698DL 10/16/98	9812415 12S-100798 10/7/98	9812570 31S-100998 10/09/98	9812570DL 31S-100998DL 10/09/98	9812680 32S-101398 10/13/98
Chloride	mg/L	250	26 D	52 E	54 D	17	14	14 D	20 E
Nitrogen, nitrate	mg/L	10	3.1 D	0.23	1.0 U	0.10 U	0.10 U	0.20 U	0.18
Sulfate	mg/L	250	71 D	120 E	110 D	5.7	21 E	20 D	30 E

Analyte	Units	NJDEP Groundwater Quality Criteria	9812680DL 32S-101398DL 10/13/98	9812684 32S-101398DUP2 10/13/98	9812684DL 32S-101398DUP2DL 10/13/98	9812311 37S-10/5/98 10/5/98	9812311DL 37S-10/5/98 10/6/98	9812309 FB-1 10/5/98	9812355 FB2-100698 10/6/98
Chloride	mg/L	250	20 D	18	18 D	490 E	440 D	0.10 U	0.10 U
Nitrogen, nitrate	mg/L	10	0.20 U	0.10 U	0.20 U	2.7	2.5 U	0.10 U	0.10 U
Sulfate	mg/L	250	27 D	31 E	30 D	14	16 D	0.10 U	0.10 U

Analyte	Units	NJDEP Groundwater Quality Criteria	9812411 FB3-100798 10/7/98	9812525 FB4-100898 10/08/98	9812588 FB5-101298 10/12/98	9812678 FB7-101398 10/13/98	9812753 FB8-101498 10/14/98	9812827 FB9-101598 10/15/98
Chloride	mg/L	250	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U
Nitrogen, nitrate	mg/L	10	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U
Sulfate	mg/L	250	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U

TABLE 5
FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING
OCTOBER 1998 MONITORING WELL SAMPLING
NAWC, TRENTON

WELL I.D.	DATE AND TIME		pH	TEMPERATURE (C)	CONDUCTIVITY (umhos/cm)	DISSOLVED OXYGEN (mg/L)	TURBIDITY (NTU)	Eh (mv)
2BR	10/07/98	1136	6.48	14.7	0.290	0.41	0.0	-46.2
3BR	10/05/98	1740	7.19	15.5	0.236	0.43	1.0	-7.0
4BR	10/09/98	1229	7.45	18.8	0.460	1.01	2.0	7.2
5BR	10/14/98	1324	6.77	15.3	0.389	0.57	1.0	-112.9
6BR	10/07/98	1630	7.50	14.7	0.250	0.68	0.0	23.0
7BR	10/08/98	1405	6.65	17.3	0.494	0.05	0.0	-131.9
8BR	10/09/98	1004	7.43	16.1	0.359	0.85	2.0	-19.6
9BR	10/07/98	1500	7.75	17.6	0.325	0.05	8.0	-161.4
11BR	10/06/98	1643	6.05	13.5	0.150	4.86	2.0	167.8
12BR	10/07/98	1435	7.05	13.9	0.207	0.79	3.0	39.9
15BR	10/09/98	1102	6.80	15.8	0.504	1.93	0.0	NS
16BR	10/14/98	1356	7.50	17.8	0.490	1.51	5.0	-6.8
19BR	10/06/98	1040	7.13	13.5	0.216	0.47	5.0	101.9
20BR	10/14/98	1019	6.58	16.5	0.461	-0.06	0.0	-107.3
21BR	10/06/98	1343	5.84	15.7	0.294	-0.08	1.0	78.6
22BR	10/09/98	1234	6.85	15.7	0.457	1.37	0.0	61.8
24BR	10/13/98		NS	NS	NS	NS	NS	NS
25BR	10/13/98		NS	NS	NS	NS	NS	NS
27BR	10/08/98	1055	7.55	17.6	0.242	0.04	0.0	195.5
28BR	10/05/98	1113	7.20	16.4	0.377	1.64	0.0	48.0
29BR	10/09/98	1114	7.75	16.1	0.330	0.82	2.0	7.4
30BR	10/13/98	1205	6.70	17.9	0.485	0.56	4.0	-116.2
31BR	10/08/98	0913	6.39	16.9	0.318	0.36	1.0	5.1
33BR	10/13/98	1058	7.43	15.0	0.467	2.02	1.0	-61.7
34BR	10/07/98	1435	7.05	13.9	0.207	0.79	3.0	39.9
35BR	10/15/98	1153	6.89	14.6	0.199	1.53	12.0	-16.3
36BR	10/14/98	1450	7.13	17.8	0.278	1.43	0.0	-115.4
37BR	10/06/98	1455	6.87	14.9	0.230	0.06	0.0	14.0
38BR	10/13/98	1600	7.09	16.3	0.482	-0.07	-9.0	-173.8
39BR	10/08/98	1102	7.88	17.4	0.279	0.27	0.0	-169.1
40BR	10/08/98	1700	7.49	15.3	0.299	0.51	115.0	-121.6
41BR	10/09/98	1007	6.81	16.4	0.382	3.45	0.0	NS
42BR	10/08/98	1118	9.22	16.8	0.346	0.05	0.0	-122.0
43BR	10/12/98	0945	10.88	14.7	1.520	10.98	125.0	-107.2
44BR	10/12/98	1125	10.12	16.4	0.575	11.29	2.0	-50.2
45BR	10/14/98	1555	7.57	14.2	0.331	1.18	-8.0	-46.0
46BR	10/12/98	1650	11.60	16.6	1.210	0.83	16.0	-51.6
47BR	10/08/98	1230	6.38	20.4	0.482	0.42	2.0	-115.4
48BR	10/09/98	0912	6.04	14.9	0.293	2.30	0.0	NS
49BR	10/12/98	1723	7.19	19.0	0.243	0.19	9.0	-39.9
50BR	10/14/98	1021	7.30	13.9	0.300	0.46	-4.0	-124.8
51BR	10/07/98	1528	7.80	16.7	0.262	0.86	6.0	36.6
11-MW-1	10/05/98	1410	5.07	21.7	0.123	2.86	16.0	125.8
35-MW-1	10/12/98	1329	5.41	16.8	0.345	1.23	91.0	243.1
35-MW-2	10/12/98	1116	5.54	15.0	0.284	2.09	36.0	224.7
BRP1	10/13/98	1430	6.18	18.6	0.567	0.87	3.0	-117.8
BRP2	10/09/98	1220	6.45	15.2	0.792	0.10	-10.0	NS

TABLE 5 (continued)
 FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING
 OCTOBER 1998 MONITORING WELL SAMPLING
 NAWC, TRENTON

WELL I.D.	DATE AND TIME	pH	TEMPERATURE (C)	CONDUCTIVITY (umhos/cm)	DISSOLVED OXYGEN (mg/L)	TURBIDITY (NTU)	Eh (mv)
BRP3	10/08/98 1539	7.77	16.4	0.475	0.11	48.0	-86.1
W DITCH WELL	10/16/98 1050	6.72	15.7	0.566	2.07	9.0	-54.2
2S	ABANDONED	NS	NS	NS	NS	NS	NS
12S	10/07/98 1100	6.03	19.2	0.439	2.92	1.0	19.8
31S	10/09/98 1110	6.29	18.5	0.305	1.57	121.0	27.2
32S	10/13/98 1246	6.30	17.8	0.429	1.79	2.0	145.8
37S	10/05/98 1740	5.02	19.5	1.510	2.24	3.0	234.8
41S	WELL DRY	NS	NS	NS	NS	NS	NS

TABLE 6
SUMMARY OF DATA QUALIFIERS FOR THE ANALYTICAL SUMMARY TABLE

DUP	Duplicate field sample.
(1)	Higher of PQLs and Ground Water Quality Criteria for 1,2-dichloroethene (trans-) is 100 ug/l. Criterion for 1,2-dichloroethene (cis-) is NJ Maximum Contaminant Level (MCL) as of 5 February 1997 of 70 ug/l.
(2)	Criterion for xylenes (total) is NJ MCL as of 5 February 1997 of 1,000 ug/l.
(3)	Criterion for 1,1-dichloroethane is NJ MCL as of 5 February 1997 of 50 ug/l.
(4)	Criterion for methylene chloride is NJ MCL as of 5 February 1997 of 3 ug/l.
(5)	Criterion for naphthalene is NJ MCL as of 5 February 1997 of 300 ug/l.
(6)	Criterion for 1,1,2,2-tetrachloroethane is NJ MCL as of 5 February 1997 of 1 ug/l.
(7)	NJDEP Surface Water Criterion for 1,3-dichloropropene (total), since no criterion is available for individual isomers.
NA	No available NJ criteria.
ND	Not Detected.
NS	Not Sampled.
TIC	Tentatively Identified Compounds.

Organic Data Qualifiers


D	Compounds identified at a secondary dilution factor
DL	Identifies a sample which has been reanalyzed at a higher dilution factor
E	Compounds whose concentrations exceed the calibration range of the GC/MS for that specific analysis; if one or more compounds have a response greater than the calibration range, the sample or extract is diluted and reanalyzed
J	Estimated value
U	Compound analyzed for but not detected

Inorganic Data Qualifiers

B	Reported value is less than the CRDL, but greater than the IDL
E	Reported value is estimated because of presence of interference
U	Compound analyzed for but not detected (concentration is less than the IDL)

Notes

1. Ground-Water Quality Criteria is from NJDEP Ground-Water Quality Criteria for Class II-A Ground Water (N.J.A.C. 7:9-6). Unless otherwise noted, the criteria used are the Higher of Practical Quantitation Levels (PQLs) and Ground-Water Quality Criteria.
2. Analytes with concentrations greater than NJDEP Ground-Water Quality Criteria are highlighted in bold.




LEGEND

- OVERBURDEN MONITORING WELL
- BEDROCK MONITORING WELL
- △ BEDROCK MONITORING WELL INSTALLED BETWEEN NOVEMBER 1996 AND MAY 1997 FOR FOCUSED FEASIBILITY STUDY

15BR MONITORING WELL SAMPLED

DESIGNED BY RAH	DRAWN BY SMD	DATE 7-23-98	PROJECT NO. 29600.43	FILE NAME FIG1
CHECKED BY RAH	PROJECT MGR. SGF	SCALE 1"=250'	DRAWING NO. -	FIGURE 1



EA® EA ENGINEERING,
SCIENCE, AND
TECHNOLOGY

NAWC - TRENTON
TRENTON, NEW JERSEY

**SITE LOCATION MAP FOR
OUTFALL AND STORM DRAIN
SAMPLE LOCATIONS**

DESIGNED BY RAH	DRAWN BY FDV	DATE 7-24-98	PROJECT NO. 29600.43
CHECKED BY RAH	PROJECT MGR. SGF	SCALE AS SHOWN	FIGURE 2

APPENDIX A

FIELD RECORDS OF WELL GAUGING, PURGING AND SAMPLING

1998/1997

Sherri Allar
Brian Andersen

Page 1 of 2



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
 WELL I.D.: 020R WELL LOCK STATUS: LOCKED
 WELL CONDITION: GOOD WEATHER: OVERCAST 65°
 GAUGE DATE: 10-7/98 GAUGE TIME: 830
 SOUNDING METHOD: SLOPE INDICATOR MEASUREMENT REF: TOC
 STICK UP DOWN (ft): 6"
 PURGE DATE: 10/7/98 PURGE TIME: 846
 PURGE METHOD: LOW FLOW FIELD PERSONNEL: SAP BA
 AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm) Start: 0.9 End: 0.5

A. TOTAL WELL DEPTH (ft): 59 E. CASING VOLUME/FT (GAL): 1.5
 B. OPEN INTERVAL (ft): 19 F. CASING VOLUME (GAL) (D*E): 40.35
 C. DEPTH TO WATER (ft): 14.9 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 60.53
 D. H₂O COLUMN(ft) (A-B-C): 26.9

Parameter	Beginning	1	2	3	4	5
Time (min)	846	950 1005	1010	1015	1020	
Depth to Water (ft)	14.9	22.75	21.50	20.59	19.34	18.59
Purge Rate (L/min)	2 gpm	0.3	0.3	0.4	0.4	0.4
Volume Purged (L)		—	1.5	3.5	5.5	7.5
pH		6.37	6.41	6.43	6.42	6.44
Temperature (°C)	Fast	14.4	14.5	14.5	14.5	14.6
Conductivity (µmhos/cm)	Purge	0.303	0.299	0.292	0.292	0.290
Dissolved Oxygen (mg/L)	0.2 gpm	0.19	0.51	0.42	0.42	0.50
Turbidity (NTU)	est 38 min	1	1	1	1	1
Eh (mv)		-73.9	-95.1	-108.3	-116.3	-130.3

TOTAL VOLUME WATER PURGED: 60 GAL + (37.5 LITERS * 0.264 GAL/LITER) = 69.9 GAL
 SAMPLERS: SAP BA SAMPLING TIME (START/END): 1106 -> 1136
 SAMPLING DATE: 10/7/98 DECONTAMINATION FLUIDS USED: DI H₂O, methanol
 SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: HCL, HNO₃, H₂SO₄, HgCl
 SAMPLE BOTTLE IDs: 02BR-100798 SUCFIDE, METHANE
 SAMPLE PARAMETERS: VOC+10, TDS, DOC, Dissolved Alkalinity, dissolved metals, dissolved ammonia
 COMMENTS AND OBSERVATIONS: Contaminated purge water used disposed of at treatment plant.

PUMP #: A9607.0084 - PUMP E
 ODOR: Yes, Hydrocarbon
 LEVEL: 30 FT

**FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING
(OVERFLOW PAGE)**

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/7/98
Well ID: 02BR	Field Personnel: STP/BA	

Parameter	6	7	8	9	10	11
Time (min.)	1025	1030	1035	1040	1045	1050
Depth to Water (ft)	18.45	17.98	17.30	17.12	17.00	16.95
Purge Rate (L/min)	0.4	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)	9.5	11.5	13.5	15.5	17.5	19.5
pH	6.45	6.44	6.43	6.44	6.43	6.41
Temperature (°C)	14.5	14.5	14.6	14.6	14.6	14.6
Conductivity (μmhos/cm)	0.286	0.283	0.276	0.274	0.273	0.278
Dissolved Oxygen (mg/L)	0.48	0.48	0.48	0.41	0.46	0.46
Turbidity (NTU)	1	0	0	0	0	0
Eh (mv)	-133.4	-134.9	-174.9	-231.5	-408	-185.1

Parameter	12	13	14	15	16	17
Time (min)	1055	1100	1105	1106	1136	
Depth to Water (ft)	16.82	16.80	16.78		17.45	
Purge Rate (L/min)	0.4	0.4	0.4		0.4	
Volume Purged (L)	21.5	23.5	25.5		37.5	
pH	6.45	6.45	6.45		6.48	
Temperature (°C)	14.5	14.5	14.5		14.7	
Conductivity (μmhos/cm)	0.276	0.275	0.274		0.290	
Dissolved Oxygen (mg/L)	0.43	0.41	0.40		0.40	
Turbidity (NTU)	0	0	0		0	
Eh (mv)	-170.7	-162.8	-163.7		-46.2	

Sampled @ 1106
End @ 1136

COMMENTS AND OBSERVATIONS



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
 WELL I.D.: 03 BR WELL LOCK STATUS: Not Locked
 WELL CONDITION: Good WEATHER: Sunny, 75°
 GAUGE DATE: 10/5/98 GAUGE TIME: 1534
 SOUNDING METHOD: Interphase probe MEASUREMENT REF: TOC
 STICK UP/DOWN (ft): 2.3 WELL DIAMETER (in.): 6"
 PURGE DATE: 10/5/98 PURGE TIME: 1550
 PURGE METHOD: Low Flow FIELD PERSONNEL: BA/SAP
 AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm) Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 45 E. CASING VOLUME/FT (GAL): 1.5
 B. OPEN INTERVAL (ft): 10 F. CASING VOLUME (GAL) (D*E): 25.74
 C. DEPTH TO WATER (ft): 17.84 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 38.61
 D. H₂O COLUMN(ft) (A-B-C): 17.16

Parameter	Beginning	1	2	3	4	5
Time (min)	1550	1620	1625	1630	1635	1640
Depth to Water (ft)	17.84	18.80	18.30	18.28	18.23	18.28
Purge Rate (L/min)	26.00	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)	X	30X	2.0	4.0	6.0	8.0
pH	Fast	6.36	6.46	6.36	6.34	6.45
Temperature (°C)	Purge	15.8	16.1	16.2	16.5	16.5
Conductivity (µmhos/cm)		0.232	0.226	0.223	0.222	0.226
Dissolved Oxygen (mg/L)		0.40	0.41	0.42	0.37	0.37
Turbidity (NTU)		45	3	2	2	1
Eh (mv)		44.0	13.3	7.4	-9.2	-9.2

TOTAL VOLUME WATER PURGED: 72 GAL + (LITERS * 0.264 GAL/LITER) = GAL

SAMPLERS: BA/SAP SAMPLING TIME (START/END): 1718 → 1740
 SAMPLING DATE: 10/5/98 DECONTAMINATION FLUIDS USED: Methanol/DI/alconox
 SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: 14.50% HCL / 16.00% AGCl
 SAMPLE BOTTLE IDs: 03BR-100598

SAMPLE PARAMETERS: TDS, trace metals, dissolved ammonia, dissolved organic carbon

COMMENTS AND OBSERVATIONS:

PUMP: 96490133 C
 ODOR: NONE

PUMP LEVEL: 23ft

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/5/98
Well ID: 03AR	Field Personnel: BA/SAP	

Parameter	6	7	8	9	10	11
Time (min.)	16.45	16.50	16.55	17.00	17.05	17.08
Depth to Water (ft)	18.28	18.28	18.28	18.28	18.28	18.28
Purge Rate (L/min)	0.4	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)	10.0	12.0	14.0	16.0	18.0	19.2
pH	6.55	6.61	6.64	6.67	6.69	6.68
Temperature (°C)	16.4	16.3	16.1	16.1	16.0	16.2
Conductivity (µmhos/cm)	0.230	0.231	0.232	0.232	0.232	0.231
Dissolved Oxygen (mg/L)	0.39	0.44	0.38	0.40	0.38	0.36
Turbidity (NTU)	1	1	1	1	1	1
Eh (mv)	-10.8	-17.0	-17.2	-20.8	-26.8	-26.8

Parameter	12	13	14	15	16	17
Time (min)	17.4	17.14	17.17		17.40	
Depth to Water (ft)	18.28	18.28	18.28		18.40	
Purge Rate (L/min)	0.4	0.4	0.4		0.4	
Volume Purged (L)	20.4	21.6	22.8		32	
pH	6.69	6.67	6.69		7.19	
Temperature (°C)	16.3	16.3	16.3		15.5	
Conductivity (µmhos/cm)	0.229	0.229	0.229		0.236	
Dissolved Oxygen (mg/L)	0.40	0.40	0.40		0.43	
Turbidity (NTU)	1	1	1		1	
Eh (mv)	-31.2	-31.4	-32.6		-7.0	

COMMENTS AND OBSERVATIONS _____

4530/4650

Me. Liss-B. Page 1 of 2
Bethany Allen



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 04 BR WELL LOCK STATUS: unlocked
WELL CONDITION: good extraction well WEATHER: raining 60-65°
GAUGE DATE: 100998 GAUGE TIME: 1221
SOUNDING METHOD: water level meter MEASUREMENT REF: LOC.
STICK UP/DOWN (ft): extraction well. sticks up is below grade. WELL DIAMETER (in.): 6"
PURGE DATE: 100998 PURGE TIME: 1231
PURGE METHOD: fast purge flow FIELD PERSONNEL: B. Allen / M. Bader
AMBIENT AIR VOCs (ppm) Start: 8.6 End: 32.0 then 0ppm WELL MOUTH VOCs (ppm): Start: 0 End: 0

- A. TOTAL WELL DEPTH (ft): 39
 - B. OPEN INTERVAL (ft): 15
 - C. DEPTH TO WATER (ft): 7.4
 - D. H₂O COLUMN(ft) (A-B-C): 16.6
 - E. CASING VOLUME/FT (GAL): 1.5
 - F. CASING VOLUME (GAL) (D*E): 24.90
 - G. 1.5 CASING VOLUMES (GAL) (F*1.5): 37.35
- ≈ 38 gal

Parameter	Beginning	1	2	3	4	5
Time (min)	1231	1307	1346	1351	1356	1401
Depth to Water (ft)	7.4	lost	7.4	7.4	7.4	7.4
Purge Rate (L/min)	4 liters/min	flow	0.5	.5	.5	.5
Volume Purged (L)	0-1 gal/min		2.5	5.0	7.5	10
pH	38 gal		7.51	7.51	7.48	7.48
Temperature (°C)	or 40 gal		18.0	17.9	18.0	18.0
Conductivity (µmhos/cm)	total		4146	451	451	451
Dissolved Oxygen (mg/L)	purged		1.47	1.45	1.49	1.81
Turbidity (NTU)	1	1	17	9	9	9
Eh (mv)			79.6	8.10	8.11	8.01

TOTAL VOLUME WATER PURGED: 38 GAL + (24 LITERS * 0.264 GAL/LITER) = 44.33 GAL
SAMPLERS: BDA / MB SAMPLING TIME (START/END): 1414 / 1429
SAMPLING DATE: 100998 DECONTAMINATION FLUIDS USED: Methanol + DI H₂O
SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: HgCl₂, H₂SO₄, HCl, HNO₃, Zn Ac, NAC
SAMPLE BOTTLE IDs: 04BR-100998
SAMPLE PARAMETERS: voc, rds, methane, DOC, Diss. Metals, Inorganic Anions, Alkalinity, Sul Fide, Diss. Ammon
COMMENTS AND OBSERVATIONS: When vault was cracked open, got readings of 32.0, so we "aired" vault out, stood upwind for 5-10 min. until readings read 0ppm. Last flow at around 1307, so will purge to 60 for a total of ≈ 40 gal.

PUMP #: Extraction well ODOR: NONE
LEVEL: _____

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 100998
Well ID: 04BR-100998	Field Personnel: B. Allen / M. Bader	

*Post
Sample*

Parameter	6	7	8	9	10	11
Time (min.)	1406	1411	1229			
Depth to Water (ft)	7.41	7.41	7.41			
Purge Rate (L/min)	.5	.5	.5			
Volume Purged (L)	12.5	15.0	24.0			
pH	7.50	7.48	7.45			
Temperature (°C)	18.0	18.0	18.8			
Conductivity (μmhos/cm)	.452	.452	.460			
Dissolved Oxygen (mg/L)	1.79	1.82	1.01			
Turbidity (NTU)	9	9	2			
Eh (mv)	8.10	8.12	7.2			

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____

27 / 8

Extraction
Well

Page 1 of 2



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON
WELL I.D.: 05BR
WELL CONDITION: on 10/13/98 - leaky connection
on 10/14/98 - leak fixed

PROJECT NUMBER: 29600.43
WELL LOCK STATUS: extraction well
WEATHER: cloudy 60°

GAUGE DATE: 10/4/98
SOUNDING METHOD: water level meter
STICK UP/DOWN (ft): extraction well

GAUGE TIME: 1145
MEASUREMENT REF: TOC
WELL DIAMETER (in.): 6"

PURGE DATE: 10/4/98
PURGE METHOD: fast + purge / low flow
AMBIENT AIR VOCs (ppm) Start: 0 End: 0

PURGE TIME: 1200
FIELD PERSONNEL: B. Allen / M. Goldberg
WELL MOUTH VOCs (ppm) Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 86.3
B. OPEN INTERVAL (ft): 15
C. DEPTH TO WATER (ft) (B-A): 64.26.56
D. H₂O COLUMN (ft) (A-B-C): 64.88 64.74
E. CASING VOLUME/FT (GAL): 1.5
F. CASING VOLUME (GAL) (D*E): 97.22 97.11
G. 1.5 CASING VOLUMES (GAL) (F*1.5): 145.98 145.66
2146 gal

Parameter	Beginning	1	2	3	4	5
Time (min)	1200	1230	1240	1245	1250	1255
Depth to Water (ft)	6.56	6.88	6.89	6.89	6.90	6.90
Purge Rate (L/min)	40 l/min or	5 gpm	0.3 (min)	0.3	0.3	0.3
Volume Purged (L)	5 gpm	150 gpm	3.0 (min)	4.5	6.0	7.5
pH		total	6.71	6.72	6.72	6.75
Temperature (°C)			14.8	14.8	15.3	15.3
Conductivity (µmhos/cm)			0.386	0.386	0.386	0.386
Dissolved Oxygen (mg/L)			0.98	1.13	1.07	1.03
Turbidity (NTU)			8	8	5	5
Eh (mv)			-215.6	-198.4	-172.1	-182.0

TOTAL VOLUME WATER PURGED: 150 GAL + (10.5 LITERS * 0.264 GAL/LITER) = 152.77 GAL

SAMPLERS: BDA / mg SAMPLING TIME (START/END): 1307-1324
SAMPLING DATE: 10/4/98 DECONTAMINATION FLUIDS USED: Methanol Dil Water
SAMPLE TYPE: GBA B SAMPLE PRESERVATIVES: HgCl₂ / HCl, HNO₃, H₂SO₄
SAMPLE BOTTLE IDs: 05BR-101498

SAMPLE PARAMETERS voc, TDS, Methane, Sulfide, Alkalinity, Diss Ammonia, Diss Metals, Inorganic Anions, DO
COMMENTS AND OBSERVATIONS: Connection is leaking, Foster Wheeler to fix on 10/14/98. Connection fixed by Chuck Jones on 10/14/98. no readings on PID. Purged for 30 minutes at 5 gpm for a total of 150 gallons.

PUMP #: EW
LEVEL: EW

ODOR: NONE

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/4/98
Well ID: 05 BR	Field Personnel: Ballen m Goldberg	

Parameter	6	7 ^{Post sample} ↓	8	9	10	11
Time (min.)	1300 (M60) 6.67	1324 6.67				
Depth to Water (ft)	6.67	6.67				
Purge Rate (L/min)	0.3	0.3				
Volume Purged (L)	9.0	10.5				
pH	6.76	6.77				
Temperature (°C)	15.5	15.3				
Conductivity (μmhos/cm)	.386	0.389				
Dissolved Oxygen (mg/L)	1.09	0.57				
Turbidity (NTU)	5	1				
Eh (mv)	-172.1	-112.9				

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

010

Call of Action
Melissa Gable
Amy Wacker

Page 1 of 2

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43

WELL I.D.: 06BR WELL LOCK STATUS: WGS WATER LEVEL RECORD

WELL CONDITION: GOOD WEATHER: COOL, CLOUDY, GOOD

GAUGE DATE: 10/7/98 GAUGE TIME: 15:20

SOUNDING METHOD: WLI MEASUREMENT REF: TOP OF OUTER CASING

STICK UP/DOWN (ft): UP WELL DIAMETER (in.): 6"

PURGE DATE: 10/7/98 PURGE TIME: 15:30 -

PURGE METHOD: FAST/Low PWD FIELD PERSONNEL: MRB/ATW

AMBIENT AIR VOCs (ppm) Start: PID BROKEN End: PID BROKEN WELL MOUTH VOCs (ppm) Start: PID BROKEN End: PID BROKEN

A. TOTAL WELL DEPTH (ft): 77.52 E. CASING VOLUME/FT (GAL): 1.5

B. OPEN INTERVAL (ft): 25 F. CASING VOLUME (GAL) (D*E): 65.7

C. DEPTH TO WATER (ft): 8.20 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 98.55

D. H₂O COLUMN(ft) (A-B-C): 43.80

Parameter	Beginning	1	2	3	4	5
Time (min)	15:30	15:50	16:55	16:00	16:05	16:10
Depth to Water (ft)	8.20		12.20	11.36	10.85	10.27
Purge Rate (L/min) <u>gpm</u>	5	1	1	1	1	0.5
Volume Purged (L) <u>gal</u>		100	105	110	115	117.5
pH		7.35	7.38	7.41	7.45	7.46
Temperature (°C)		15.2	14.5	14.4	14.5	14.8
Conductivity (µmhos/cm)		0.354	0.250	0.250	0.250	0.251
Dissolved Oxygen (mg/L)		0.30	0.37	0.35	0.159	0.59
Turbidity (NTU)		3	3	1	1	1
Eh (mv)		49.0	34.6	32.8	49.2	18.9

TOTAL VOLUME WATER PURGED: _____ GAL + (_____ LITERS * 0.264 GAL/LITER) = 122.5 GAL

SAMPLERS: MRB/ATW SAMPLING TIME (START/END): 1620/1630

SAMPLING DATE: 10/7/98 DECONTAMINATION FLUIDS USED: DI

SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: Zn, Ac, HgCl₂, HNO₃, H₂SO₄, HCl

SAMPLE BOTTLE IDs: 06BR-100798

SAMPLE PARAMETERS: VOC, DOC, dissolved ammonia, dissolved metals, inorganic, TDS, methane

COMMENTS AND OBSERVATIONS: _____

PUMP: C
ODOR: NONE

PUMP LEVEL: 49'

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/7/98
Well ID: 06BR	Field Personnel: A1W/MB	

AFTER SAMP.

Parameter	6	7	8	9	10	11
Time (min.)	16:15	16:20		16:30		
Depth to Water (ft)	10.02	9.89				
Purge Rate (L/min) <i>gpm</i>	0.5	0.5				
Volume Purged (L) <i>g</i>	120	122.5				
pH	7.45	7.42		7.50		
Temperature (°C)	14.8	14.7		14.7		
Conductivity (μmhos/cm)	0.251	0.251		0.250		
Dissolved Oxygen (mg/L)	0.55	0.54		0.68		
Turbidity (NTU)	1	0		0		
Eh (mv)	19.2	19.2		23.0		

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____



EA Engineering,
Science, and
Technology

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 07BR WELL LOCK STATUS:
WELL CONDITION: GOOD WEATHER: RAIN, 60'S
GAUGE DATE: 10/8/98 GAUGE TIME:
SOUNDING METHOD: 1 FP MEASUREMENT REF: 710.0
STICK UP DOWN (ft): 0.5 WELL DIAMETER (in.): 6"
PURGE DATE: 10/8/98 PURGE TIME: 1300
PURGE METHOD: SLOW PURGE FIELD PERSONNEL: AM/K.S.
AMBIENT AIR VOCs (ppm) Start: 00 End: 00 WELL MOUTH VOCs (ppm) Start: End:

A. TOTAL WELL DEPTH (ft): 53.5 E. CASING VOLUME/FT (GAL): 1.5
B. OPEN INTERVAL (ft): 15 F. CASING VOLUME (GAL) (D*E): 44.0
C. DEPTH TO WATER (ft): 9.17 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 66.0
D. H₂O COLUMN(ft) (A-B-C): 29.33

Parameter	Beginning	1	2	3	4	5
Time (min)	1300	1322	1327	1336		
Depth to Water (ft)	9.17	9.60	9.25	9.21		
Purge Rate (L/min)	3.06 gpm	0.42 gpm	0.4	0.4		
Volume Purged (L)	66.0	0	2.0	0.6		
pH		5.71	6.77	6.76		
Temperature (°C)		17.9	18.2	18.3		
Conductivity (µmhos/cm)		0.474	0.473	0.473		
Dissolved Oxygen (mg/L)		0.61	0.43	0.25		
Turbidity (NTU)		0	0	0		
Eh (mv)		108.8				

TOTAL VOLUME WATER PURGED: 66 GAL + (14 LITERS * 0.264 GAL/LITER) = 69.7 GAL
SAMPLERS: AM/KS SAMPLING TIME (START/END): 1405 - 1415
SAMPLING DATE: 10/8/98 DECONTAMINATION FLUIDS USED: METHANOL/DI H₂O
SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES:
SAMPLE BOTTLE IDs: 07BR-100898
SAMPLE PARAMETERS: VOC, TDS, METALS, DISSOLVED METALS, DISSOLVED AMMONIA, INORGANIC AMMONIUM, METAMORPHIC
COMMENTS AND OBSERVATIONS: FAST PURGE @ 3.0 GPM / SLOW PURGE @ 0.42 GPM Surfing D.

PUMP # : A
LEVEL: 16ft

ODOR: None

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/8/98
Well ID: 07BR	Field Personnel: AM/KS	

Parameter	6	7	8	9	10	11
Time (min.)	1341	1348	1351	1356	1401	Post Sample
Depth to Water (ft)	9.59	9.57	9.45	9.46	9.40	9.48
Purge Rate (L/min)	0.4	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)	6.0	8.0	10.0	12	14	-
pH	6.67	6.69	6.66	6.64	6.62	6.65
Temperature (°C)	18.7	17.6	17.5	17.4	17.4	17.3
Conductivity (μmhos/cm)	0.472	0.487	0.490	0.492	0.495	0.498
Dissolved Oxygen (mg/L)	1.52	0.11	0.09	0.07	0.08	0.05
Turbidity (NTU)	0	0	0	0	0	0
Eh (mv)	-100.4	-122.2	-124.6	-126.9	-127.5	-131.9

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 08BR WELL LOCK STATUS: LOCKED
WELL CONDITION: GOOD WEATHER: OVERCAST, MISTING
GAUGE DATE: 10/9/98 GAUGE TIME: 822
SOUNDING METHOD: Slope Indicator MEASUREMENT REF: TOP OF COVER
STICK UP/DOWN (ft): DOWN WELL DIAMETER (in.): 6"
PURGE DATE: 10/9/98 PURGE TIME: 840
PURGE METHOD: LOW FLOW FIELD PERSONNEL: SAP/BA
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm): Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 57 E. CASING VOLUME/FT (GAL): 1.5
B. OPEN INTERVAL (ft): 25 F. CASING VOLUME (GAL) (D*E): 41.48
C. DEPTH TO WATER (ft): 4.35 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 62.22
D. H₂O COLUMN(ft) (A-B-C): 27.65

Parameter	Beginning	1	2	3	4	5
Time (min)	840	900	905 ⁹¹⁰	915	920	925
Depth to Water (ft)	4.35	6.72	5.40	5.25	5.25	5.25
Purge Rate (L/min)	1.6 gpm	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)		—	2.0	4.0	6.0	8.0
pH	Fast	6.07	6.09	6.57	6.87	7.00
Temperature (°C)	15.3	15.3	15.7	15.8	16.0	16.1
Conductivity (μmhos/cm)	Purge	0.376	0.371	0.358	0.357	0.358
Dissolved Oxygen (mg/L)		0.46	0.45	0.45	0.40	0.42
Turbidity (NTU)		1	1	1	0	0
Eh (mv)	28.0	28.0	-13.8	-18.2	-28.6	-33.0

TOTAL VOLUME WATER PURGED: 65 GAL + (23.6 LITERS * 0.264 GAL/LITER) = 71.2 GAL
SAMPLERS: BA/SAP SAMPLING TIME (START/END): 956 →
SAMPLING DATE: 10/9/98 DECONTAMINATION FLUIDS USED: DE H₂O, Methanol
SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: HCl, HNO₃, H₂SO₄
SAMPLE BOTTLE IDs: 08BR-100993
SAMPLE PARAMETERS: VOC+10, TO3, DOC, DISSOLVED AMMONIA, METHANE, SULFIDE, DISSOLVED METALS
COMMENTS AND OBSERVATIONS: Problem with turbidity had to clean probe.

Purged water was contained and disposed of at Treatment plant

PUMP #: —

ODOR: BSB

LEVEL: —

855

**FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING
(OVERFLOW PAGE)**

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 927 10/9/98
Well ID: 08BR	Field Personnel: STP/BA	

Parameter	6	7	8	9	10	11
Time (min.)	930	935	940	945	950	955
Depth to Water (ft)	5.20	^{5.10} 5.08	5.00	5.00	4.98	4.96
Purge Rate (L/min)	0.4	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)	10.0	12.0	14.0	16.0	18.0	20.0
pH	7.08	7.15	7.20	7.24	7.26	7.28
Temperature (°C)	16.1	16.1	16.1	16.1	16.1	16.1
Conductivity (μmhos/cm)	0.359	0.358	0.358	0.358	0.358	0.359
Dissolved Oxygen (mg/L)	0.40	0.44	0.46	0.40	0.38	0.37
Turbidity (NTU)	0	0	0	0	0	0
Eh (mv)	-37.8	-42.2	-46.0	-50.8	-53.4	-55.6

Parameter	12	13	14	15	16	17
Time (min)	956	1004				
Depth to Water (ft)	4.96	4.96				
Purge Rate (L/min)	0.4	0.4				
Volume Purged (L)		23.4				
pH		7.43				
Temperature (°C)		16.1				
Conductivity (μmhos/cm)		0.359				
Dissolved Oxygen (mg/L)		0.85				
Turbidity (NTU)		2				
Eh (mv)		-19.4				

COMMENTS AND OBSERVATIONS

35/37

Andy McBride
line skuffs

Page 1 of 2



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
 WELL I.D.: 09 DR WELL LOCK STATUS: O.K.
 WELL CONDITION: Good WEATHER: Cloudy, 60's
 GAUGE DATE: 10/7/98 GAUGE TIME: 1315
 SOUNDING METHOD: WATER LINE MEASUREMENT REF: T.O.C.
 STICK UP/DOWN (ft): 2.5 ft. WELL DIAMETER (in.): 6"
 PURGE DATE: 10/7/98 PURGE TIME: 60 min
 PURGE METHOD: FAST PURGE / SLOW PURGE FIELD PERSONNEL: AM/KS
 AMBIENT AIR VOCs (ppm) Start: 0.0 End: 0.0 WELL MOUTH VOCs (ppm): Start: 0.0 End: 0.0

A. TOTAL WELL DEPTH (ft): 44 E. CASING VOLUME/FT (GAL): 1.5
 B. OPEN INTERVAL (ft): 25 F. CASING VOLUME (GAL) (D*E): 14.175
 C. DEPTH TO WATER (ft): 9.55 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 21.2625
 D. H₂O COLUMN(ft) (A-B-C): 9.45

Parameter	Beginning	1	2	3	4	5
Time (min)	1329	1334	1339	1344	1349	1354
Depth to Water (ft)	7.25 (?)	7.33	7.41	7.54	7.76	7.83
Purge Rate (L/min)	0.4	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)	0	2.0	4.0	6.0	8.0	10.0
pH	7.21	7.42	7.57	7.61	7.66	7.69
Temperature (°C)	17.0	16.8	16.9	17.3	17.3	17.3
Conductivity (µmhos/cm)	0.317	0.328	0.329	0.324	0.324	0.324
Dissolved Oxygen (mg/L)	0.98	0.54	0.62	0.27	0.06	0.00
Turbidity (NTU)	15	14	10	8	8	8
Eh (mv)	-215.8	-219.8	-222.1	-228.7	-239.4	-240.6

TOTAL VOLUME WATER PURGED: 21 GAL + (36 LITERS * 0.264 GAL/LITER) = 30.5 GAL
 SAMPLERS: AM/KS SAMPLING TIME (START/END): 1440 - 1500
 SAMPLING DATE: 10/7/98 DECONTAMINATION FLUIDS USED: DI / METHANOL
 SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: HNO₃ / H₂SO₄ / HCL / HgCl₂ / Ar
 SAMPLE BOTTLE IDs: 9BR-100798
 SAMPLE PARAMETERS: VOC, INORGANIC ANIONS, TDS, DIS. AMMONIA, DISS. METALS, ALKALINITY, METHANE, SULFIDE, etc
 COMMENTS AND OBSERVATIONS: Set Pump @ 14 ft. / Quick Purge @ 26 gpm for 10 + min
Slow Purge @ 0.4 LPM

PUMP #: A
 LEVEL: 14 ft

ODOR: NONE

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/7/98
Well ID: 09 BR	Field Personnel: AM/KS	

Parameter	6	7	8	9	10	11
Time (min.)	1359	1404	1409	1414	1419	1424
Depth to Water (ft)	7.83	7.98	8.03	7.98	7.96	7.90
Purge Rate (L/min)	0.4	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)	12.0	14.0	16.0	18.0	20.0	22.0
pH	7.70	7.73	7.73	7.75	7.75	7.77
Temperature (°C)	17.4	17.5	17.5	17.5	17.5	17.5
Conductivity (μmhos/cm)	0.325	0.325	0.325	0.326	0.327	0.327
Dissolved Oxygen (mg/L)	0.08	0.04	0.01	0.01	0.01	0.01
Turbidity (NTU)	9	9	9	9	9	9
Eh (mv)	-244.0	-242.0	-238.6	-238.3	-239.6	-240.8

Parameter	12	13	14	15	16	17
Time (min)	1429	1500				
Depth to Water (ft)	7.91	8.53				
Purge Rate (L/min)	0.4	0.4				
Volume Purged (L)	24.0	36.0				
pH	7.77	7.75				
Temperature (°C)	17.7	17.6				
Conductivity (μmhos/cm)	0.327	0.325				
Dissolved Oxygen (mg/L)	0.01	0.05				
Turbidity (NTU)	8	8				
Eh (mv)	-241.3	-161.4				

COMMENTS AND OBSERVATIONS

33 / 33

Melissa
Bader
Bethany Allen

Page 1 of 2



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME:

NAWC TRENTON

PROJECT NUMBER:

29600.43

WELL I.D.:

11BR

WELL LOCK STATUS:

locked

WELL CONDITION:

good

WEATHER:

70° sunny breezy

GAUGE DATE:

100698

GAUGE TIME:

1515

SOUNDING METHOD:

interface probe

MEASUREMENT REF:

top of PVC casing

STICK UP/DOWN (ft):

stick up

WELL DIAMETER (in.):

4"

PURGE DATE:

10/6/98

PURGE TIME:

1529 - fast purged

PURGE METHOD:

fast purge / low flow

FIELD PERSONNEL:

MB/BA

AMBIENT AIR VOCs (ppm)

Start: 9 AM End: 0 PM

WELL MOUTH VOCs (ppm):

Start: 3:17 PM End: 2:7 PM

A. TOTAL WELL DEPTH (ft):

75

E. CASING VOLUME/FT (GAL):

0.65

B. OPEN INTERVAL (ft):

20

F. CASING VOLUME (GAL) (D*E):

20.77

C. DEPTH TO WATER (ft):

23.04

G. 1.5 CASING VOLUMES (GAL) (F*1.5):

31.16

D. H₂O COLUMN(ft) (A-B-C):

31.96

≈ 27 gal

Parameter	Beginning	1	2	3	4	5
Time (min)	1529	1543	1548	1553	1558	1603
Depth to Water (ft)	23.04	23.66	23.40	23.36	23.39	23.70
Purge Rate (L/min)	2 gpm	0.3	0.3	0.3	0.3	0.3
Volume Purged (L)	28 gpm		1.5	3.0	4.5	6.0
pH			5.72	5.74	5.74	5.72
Temperature (°C)			14.6	14.8	14.9	15.0
Conductivity (µmhos/cm)			0.149	0.149	0.150	0.150
Dissolved Oxygen (mg/L)			4.93	5.03	5.06	4.99
Turbidity (NTU)			1	2	1	1
Eh (mv)			147.0	144.4	145.0	147.6

TOTAL VOLUME WATER PURGED: 28 GAL + (18 LITERS * 0.264 GAL/LITER) = 32.75 GAL

SAMPLERS:

BA/MB

SAMPLING TIME (START/END):

1614 - 1643

SAMPLING DATE:

10/6/98

DECONTAMINATION FLUIDS USED:

Di Water / Methanol

SAMPLE TYPE:

Grab

SAMPLE PRESERVATIVES:

1:1 HCl, HNO₃, H₂SO₄

SAMPLE BOTTLE IDs:

11BR-100698

SAMPLE PARAMETERS:

VOCs + 10, TDS, DOC, Inorganic Anions, Dissolved Ammonia, H₂CH₂

COMMENTS AND OBSERVATIONS:

Set pump at 28 feet for fast purge. Set pump at 40 to 42 feet for low flow. At 1543, low flow at 0.3 liters per minute. Readings were stabilized after 15 minutes, we took 2 more readings.

PUMP # A

ODOR: None

LEVEL:

28 feet for fast purge - 40 feet for low flow H₂O qual. readings.

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 100698
Well ID: 11BR	Field Personnel: Gotham Allen, Melissa Bader	

Parameter	6	7	8	9	10	11
Time (min.)	1608	1643				
Depth to Water (ft)	23.38	23.46				
Purge Rate (L/min)	0.3	0.3				
Volume Purged (L)	7.5	18.0				
pH	5.69	6.05				
Temperature (°C)	15.4	13.5				
Conductivity (µmhos/cm)	0.149	0.150				
Dissolved Oxygen (mg/L)	4.89	4.86				
Turbidity (NTU)	1	2				
Eh (mv)	151.3	167.8				

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (µmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____

15 / 12

Melissa Bader
Amy Winkler



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 12 BR WELL LOCK STATUS: LOCKED
WELL CONDITION: Good WEATHER: COOL, CLOUDY, 60's
GAUGE DATE: 10/7/98 GAUGE TIME: 13:50
SOUNDING METHOD: WLI MEASUREMENT REF: TOP OF INNER CASING
STICK UP/DOWN (ft): FLUSH WELL DIAMETER (in.): 6"
PURGE DATE: 10/7/98 PURGE TIME: 13:00 - 14:35
PURGE METHOD: FAST FIELD PERSONNEL: MRB/AIW
AMBIENT AIR VOCs (ppm) Start: PID NOT WORKING End: PID NOT WORKING WELL MOUTH VOCs (ppm): Start: NOT WORKING End: NOT WORKING

- A. TOTAL WELL DEPTH (ft): 71.5 ~~66.5~~ E. CASING VOLUME/FT (GAL): 1.5
B. OPEN INTERVAL (ft): 15.0 F. CASING VOLUME (GAL) (D*E): 70.5
C. DEPTH TO WATER (ft): 19.53 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 105.75
D. H₂O COLUMN(ft) (A-B-C): 46.97

Parameter	Beginning	1	2	3	4	5
Time (min)	13:00	13:00	14:05	14:10	14:15	14:20
Depth to Water (ft)	19.53		28.59	27.86	27.06	26.85
Purge Rate (L/min) <u>gpm</u>	2 gpm	0.5 <u>0.5</u> gpm	0.5 gpm	0.5	0.5	0.5
Volume Purged (gal)		106	108.5	111	113.5	116
pH	7.08	7.08	7.08	7.10	7.07	7.04
Temperature (°C)		14.4	14.5	14.0	13.9	13.8
Conductivity (µmhos/cm)		0.210	0.208	0.209	0.209	0.209
Dissolved Oxygen (mg/L)		0.40	0.21	0.19	0.19	0.20
Turbidity (NTU)		9	9	7	7	5
Eh (mv)		11.0	6.0	3.8	5.0	5.0

TOTAL VOLUME WATER PURGED: 123.5 GAL + () LITERS * 0.264 GAL/LITER = () GAL

SAMPLERS: MRB/AIW SAMPLING TIME (START/END): 14:25
SAMPLING DATE: 10/7/98 DECONTAMINATION FLUIDS USED: DI/METHANOL
SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: HCl, Zn Ac, HAN O3, H2SO4, NaOH, HgCl2
SAMPLE BOTTLE IDs: 12 BR - 100798
SAMPLE PARAMETERS: Kat10, DOC, Dissolved ammonia, dissolved metals, inorganic anions, alkalinity, TDS, methane, sulfide
COMMENTS AND OBSERVATIONS: _____

PUMP #: B
LEVEL: 38'

ODOR: NONE

**FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING
(OVERFLOW PAGE)**

Site Name: NAWC TRENTON	Project No.: 29600.43	Date:
Well ID:	Field Personnel:	

Parameter	6	7	8	9	10	11
Time (min.)	14:35					
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH	7.05					
Temperature (°C)	13.9					
Conductivity (µmhos/cm)	0.207					
Dissolved Oxygen (mg/L)	0.79					
Turbidity (NTU)	3					
Eh (mv)	399 670					

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (µmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
 WELL I.D.: 15 BR WELL LOCK STATUS: UNLOCKED
 WELL CONDITION: _____ WEATHER: CLOUDY, 60'S
 GAUGE DATE: _____ GAUGE TIME: N/A
 SOUNDING METHOD: _____ MEASUREMENT REF: _____
 STICK UP/DOWN (ft): _____ WELL DIAMETER (in.): 6"
 PURGE DATE: _____ PURGE TIME: _____
 PURGE METHOD: N/A FIELD PERSONNEL: AM/KS
 AMBIENT AIR VOCs (ppm) Start: 0.0 End: 0.0 WELL MOUTH VOCs (ppm): Start: _____ End: _____

A. TOTAL WELL DEPTH (ft): 41.0 E. CASING VOLUME/FT (GAL): 1.5
 B. OPEN INTERVAL (ft): 15 F. CASING VOLUME (GAL) (D*E): N/A
 C. DEPTH TO WATER (ft): N/A G. 1.5 CASING VOLUMES (GAL) (F*1.5): N/A
 D. H₂O COLUMN(ft) (A-B-C): _____

Parameter	Beginning	1	2	3	4	5
Time (min)	<u>0945</u>	<u>1102</u>				
Depth to Water (ft)	<u>N/A</u>	<u>N/A</u>				
Purge Rate (L/min)						
Volume Purged (L)	<u>↓</u>	<u>↓</u>				
pH	<u>6.80</u>	<u>6.80</u>				
Temperature (°C)	<u>15.9</u>	<u>15.8</u>				
Conductivity (μmhos/cm)	<u>0.496</u>	<u>0.509</u>				
Dissolved Oxygen (mg/L)	<u>1.91</u>	<u>1.93</u>				
Turbidity (NTU)	<u>0</u>	<u>0</u>				
Eh (mv)	<u>N/A</u>	<u>N/A</u>				

TOTAL VOLUME WATER PURGED: N/A GAL + (N/A LITERS * 0.264 GAL/LITER) = N/A GAL
 SAMPLERS: AM/KS SAMPLING TIME (START/END): 1050-1100
 SAMPLING DATE: 10/9/98 DECONTAMINATION FLUIDS USED: DI / METHANE
 SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: HCL, HNO₃, H₂SO₄ / HgCl₂
 SAMPLE BOTTLE IDs: 15BR-100998
 SAMPLE PARAMETERS: VOC, TDS, MINERAL, DOC/DISS. AMMONIA, DISS. METALS, INORGANIC ANIONS, SULFIDE
 COMMENTS AND OBSERVATIONS: EXTRACTION WELL

PUMP #:
LEVEL:

ODOR:

*A. Winkler
M. Bader*

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 16 BR WELL LOCK STATUS: locked
WELL CONDITION: Good WEATHER: Sunny 64-70's, c.l.o.
GAUGE DATE: 101498 GAUGE TIME: 1155
SOUNDING METHOD: water level meter MEASUREMENT REF: + op. + well casing
STICK UP/DOWN (ft): 3 feet WELL DIAMETER (in.): 6"
PURGE DATE: 101498 PURGE TIME: 1200
PURGE METHOD: foot pump / low flow FIELD PERSONNEL: A. Winkler - M. Bader
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm) Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 65 E. CASING VOLUME/FT (GAL): 1.5
B. OPEN INTERVAL (ft): 25 F. CASING VOLUME (GAL) (D*E): 48.23
C. DEPTH TO WATER (ft): 7.85 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 72.35
D. H₂O COLUMN (ft) (A-B-C): 32.15 ~ 73

Parameter	Beginning	1	2	1248	4	5
Time (min)	1200	1238	1243	1258	1253	1258
Depth to Water (ft)	7.85	33.15	31.0	26.84	25.20	21.40
Purge Rate (L/min)	2.758/m	0.52/m	0.5	0.5	0.5	0.5
Volume Purged (L)	736.16	2.52	5.0	7.5	10.0	12.5
pH		7.23	7.31	7.35	7.36	7.37
Temperature (°C)		17.4	17.4	17.5	17.5	17.7
Conductivity (μmhos/cm)		.450	.450	.449	.450	.450
Dissolved Oxygen (mg/L)		2.50	2.52	2.09	1.82	1.55
Turbidity (NTU)		20	20	20	20	19
Eh (mv)		6.25	6.67	8.2	8.4	-24.8

TOTAL VOLUME WATER PURGED: 73 GAL + (41.5 LITERS * 0.264 GAL/LITER) 83.96 GAL
SAMPLERS: AW/MB A. Winkler - M. Bader SAMPLING TIME (START/END): 1330/1356
SAMPLING DATE: 101498 DECONTAMINATION FLUIDS USED: D.I. Water - 1/2 m. H₂O
SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: HCl, HNO₃, 4.50% HgCl₂
SAMPLE BOTTLE IDs: 16BR-101498 N.D.H. 7.1.10
SAMPLE PARAMETERS: VOL, TDS, Methane Sulfide, DO, Dissolved Metals, Dissolved Ammonia, Alk
COMMENTS AND OBSERVATIONS: 1224 - Well stopped Purging - Started flowing 1225

PUMP #: Extraction Well ODOR: None
LEVEL:

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/14/98
Well ID: 16BR-101498	Field Personnel: A. Winkler - M. Bader	

Parameter	6	7	8	9	10	11
Time (min.)	1303	1308	1313	1318	1323	1328
Depth to Water (ft)	20.5	19.8 19.86	18.6	16.0	14.4	13.25
Purge Rate (L/min)	15.0 0.5	0.5	0.5	0.5	0.5	0.5
Volume Purged (L)	15.0	17.5	20.0	22.5	25.0	27.5
pH	7.34	7.34	7.35	7.37	7.38	7.38
Temperature (°C)	17.5	17.5	17.6	17.9	17.9	18.0
Conductivity (µmhos/cm)	.458	.481	.483	.475	.476	.477
Dissolved Oxygen (mg/L)	1.49	1.15	1.02	.93	.94	.92
Turbidity (NTU)	11	8	2	0	0	0
Eh (mv)	-20.6	-20.4	-21.2	-39.8	-44.2	-45

post-sample

Parameter	12	13	14	15	16	17
Time (min)	1356					
Depth to Water (ft)	11.86					
Purge Rate (L/min)	0.5					
Volume Purged (L)	16.4 16.45					
pH	7.50					
Temperature (°C)	17.8					
Conductivity (µmhos/cm)	.490					
Dissolved Oxygen (mg/L)	1.51					
Turbidity (NTU)	5					
Eh (mv)	-6.8					

COMMENTS AND OBSERVATIONS _____

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 19BR WELL LOCK STATUS: locked
WELL CONDITION: good WEATHER: cloud ≈ 55°

GAUGE DATE: 100698 GAUGE TIME: 0820
SOUNDING METHOD: water level meter MEASUREMENT REF: TOC Well (outside casing)
STICK UP/DOWN (ft): up WELL DIAMETER (in.): 6"

PURGE DATE: 100698 PURGE TIME: 0835 (purged 52 min)
PURGE METHOD: low blow FIELD PERSONNEL: Allen + M. Baden
AMBIENT AIR VOCs (ppm) Start: 0.9 ppm End: 1.0 ppm WELL MOUTH VOCs (ppm): Start: 0.9 ppm End: 2.5 ppm

A. TOTAL WELL DEPTH (ft): 58.0 E. CASING VOLUME/FT (GAL): 1.5
B. OPEN INTERVAL (ft): 15.0 F. CASING VOLUME (GAL) (D*E): 34.65 ~~36.15~~
C. DEPTH TO WATER (ft): 18.90 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 51.98 ~~54.23~~
D. H₂O COLUMN(ft) (A-B-C): 24.10 ~~23.10~~ ≈ 52 gal

Parameter	Beginning	1	2	3	4	5
Time (min)	0835	0927	0945	0950	0955	0900
Depth to Water (ft)	18.90	*	* —	19.75	19.79	19.71
Purge Rate (L/min)	24m	0.5	0.5	0.5	0.5	0.5
Volume Purged (L)		52 gal total	4.0	6.5	9.0	11.5
pH			5.94	6.69	6.86	6.83
Temperature (°C)			13.5	13.8	13.8	13.8
Conductivity (μmhos/cm)			0.229	0.217	0.215	0.216
Dissolved Oxygen (mg/L)			0.91	0.49	0.47	0.70
Turbidity (NTU)			12	10	10	10
Eh (mv)			96.5	85.1	83.6	89.2

TOTAL VOLUME WATER PURGED: 52 GAL + (31.5 LITERS * 0.264 GAL/LITER) = 60.32 GAL
SAMPLERS: BA + MB SAMPLING TIME (START/END): 1020 / 1040
SAMPLING DATE: 100698 DECONTAMINATION FLUIDS USED: Methanol DI
SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: HCl, H₂SO₄, HVO₃
SAMPLE BOTTLE IDs: 19BR-100698

SAMPLE PARAMETERS: VOC, methane, sulfide, alkalinity, DOC, Diss Metals, Dissolved Ammonia, TDS, Anions
COMMENTS AND OBSERVATIONS: At 0835 purged at 2 liters/min or 1 gal per minute. Purged for 52 minutes. Slowed rate to 0.5 L per minute at 0927.

* Water level meter broke.

PUMP: E

ODOR: none

PUMP LEVEL: ≈ 28 feet initially
53 feet at low flow.

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/06/98
Well ID: 19BR	Field Personnel: Bethany Allen/Melissa Bader	

Parameter	6	7	8	9	10	11
Time (min.)	1005	1010	1015	1040		
Depth to Water (ft)	19.72	19.71	19.72	19.79		
Purge Rate (L/min)	0.5	0.5	0.5	0.5		
Volume Purged (L)	14.0	16.5	19.0	31.5		
pH	7.05	7.11	7.14	7.13		
Temperature (°C)	13.8	13.8	13.8	13.5		
Conductivity (μ mhos/cm)	0.214	0.214	0.212	0.216		
Dissolved Oxygen (mg/L)	0.37	0.37	0.36	0.47		
Turbidity (NTU)	10	9	9	5		
Eh (mv)	84.8	82.1	79.8	101.9		

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μ mhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____

1015 Horiba Calibration
#00110 TDS 0
pH 3.97
DO 3.40
cond 4.50
temp 19.7



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON
WELL I.D.: 20BR
WELL CONDITION: good

PROJECT NUMBER: 29600.43
WELL LOCK STATUS: bottled down
WEATHER: sunny 65°

GAUGE DATE: 10/14/98
SOUNDING METHOD: water level meter
STICK UP/DOWN (ft): attraction well
(pumping)

GAUGE TIME: N/A
MEASUREMENT REF: N/A
WEI L. DIAMETER (in.): 6"

PURGE DATE: 10/14/98
PURGE METHOD: Low flow
AMBIENT AIR VOCs (ppm) Start: 2.0 End: 0.0

PURGE TIME: 1019
FIELD PERSONNEL: B. Allen / M. Goldberg
WELL MOUTH VOCs (ppm): Start: 0.0 End: 0.0

A. TOTAL WELL DEPTH (ft):	<u>43</u>	E. CASING VOLUME/FT (GAL):	<u>1.5</u>
B. OPEN INTERVAL (ft):	<u>15</u>	F. CASING VOLUME (GAL) (D*E):	<u>—</u>
C. DEPTH TO WATER (ft):	<u>N/A</u>	G. 1.5 CASING VOLUMES (GAL) (F*1.5):	<u>—</u>
D. H ₂ O COLUMN(ft) (A-B-C):	<u>*Depth to water could not be obtained w/o slope indicator.</u>		

Parameter	Beginning	1	2	3	4	5
Time (min)	1019	1055				
Depth to Water (ft)	—	Sample taken				
Purge Rate (L/min)	—					
Volume Purged (L)	—					
pH	6.58					
Temperature (°C)	16.5					
Conductivity (μmhos/cm)	0.461					
Dissolved Oxygen (mg/L)	-0.06					
Turbidity (NTU)	0					
Eh (mv)	-107.3					

TOTAL VOLUME WATER PURGED: GAL + (LITERS * 0.264 GAL/LITER) = 23 GAL

SAMPLERS: BDA/mg SAMPLING TIME (START/END): 1055-1104
 SAMPLING DATE: 101498 DECONTAMINATION FLUIDS USED: H₂SO₄, H₂SO₄, HNO₃, HCl, NaOH, Zn
 SAMPLE TYPE: GAB SAMPLE PRESERVATIVES: methanol / DI water

SAMPLE TYPE: WATER SAMPLE PRESERVATIVES: _____

SAMPLE BOTTLE IDs: 206R-101498

SAMPLE PARAMETERS: VOC, TDS, Methane, DOC, Diss Ammonia, Diss. Metals, Incrg. Anions, Alkalinity, Sulfide

SAMPLE PARAMETERS: vol, TDS, Methane, DOC, Diss Ammonia, Diss. Metals, Inorg. Anions, Alkalinity, Sulfide

COMMENTS AND OBSERVATIONS: H_2S odors when water filled up drum.
 H_2O level meter did not work.

PUMP #: — EW
LEVEL: — FW

ODOR: H_2S odors

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

10/9

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43

WELL I.D.: 210R WELL LOCK STATUS: locked

WELL CONDITION: good WEATHER: Sunny 65° windy

GAUGE DATE: 100698 GAUGE TIME: 1145

SOUNDING METHOD: water level meter MEASUREMENT REF: top of out. well casing

STICK UP/DOWN (ft): stick up WELL DIAMETER (in.): 6"

PURGE DATE: 100698 PURGE TIME: 1155 ^{Purge started 8 or 10 min.}

PURGE METHOD: fast purge / low flow FIELD PERSONNEL: B. Allen M. Bader

AMBIENT AIR VOCs (ppm) Start: 0 ppm End: 0 ppm WELL MOUTH VOCs (ppm) Start: 5.4 ppm End: 5.4 ppm

A. TOTAL WELL DEPTH (ft): 65 E. CASING VOLUME/FT (GAL): 1.5

B. OPEN INTERVAL (ft): 15 F. CASING VOLUME (GAL) (D*E): 49.17

C. DEPTH TO WATER (ft): 17.22 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 73.75

D. H₂O COLUMN(ft) (A-B-C): 32.78 ≈ 74 gal

Parameter	Beginning	1	2	3	4	5
Time (min)	1155	1235	1245	1250	1255	1300
Depth to Water (ft)	17.22	17.36	17.77	17.84	17.87	17.87
Purge Rate (L/min)	8 L/min or 2 gpm	0.5	0.5	0.5	0.5	0.5
Volume Purged (L)			5.0	7.5	10.0	12.5
pH	40 min x 2 gpm =		6.22	5.99	6.03	5.65
Temperature (°C)	80 gal		16.5	16.1	16.0	15.9
Conductivity (µmhos/cm)	total		0.280	0.279	0.279	0.306
Dissolved Oxygen (mg/L)			0.81	0.19	-0.1	-0.05
Turbidity (NTU)			3	5	5	3
Eh (mv)			89.4	84.0	76.0	74.5

TOTAL VOLUME WATER PURGED: 80 GAL + (34 LITERS * 0.264 GAL/LITER) = 88.97 GAL

SAMPLERS: BA / MB SAMPLING TIME (START/END): 1322 / 1343

SAMPLING DATE: 100698 DECONTAMINATION FLUIDS USED: Methanol + DI H₂O

SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: H₂SO₄, HNO₃, HCl, HCL

SAMPLE BOTTLE IDs: 21BR-100698

SAMPLE PARAMETERS: VOC, TDS, Methane, Sulfide, DOC, Heavy Anions, Dissolved Metals, Alkalinity, Dissolved Ammonia

COMMENTS AND OBSERVATIONS: Purge at 8 liters / minute or 2 gallons / minute.
At 1235, changed flow to 0.5 liters / minute.

NOTE: negative DO readings, some recalibrated.

PUMP #: C

LEVEL: 25 feet initially to purge - Level - 35 feet for the quality readings.

ODOR: NO ODORS

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 100698
Well ID: 21BR	Field Personnel: <i>Bethany Allen M. Baden</i>	

Parameter	6	7	8	9	10	11
Time (min.)	1305	1310	1315	1343		
Depth to Water (ft)	17.85	17.87	17.8	18.43		
Purge Rate (L/min)	0.5	0.5	0.5	.5		
Volume Purged (L)	15.0	17.5	20.0	34.0		
pH	5.89	5.93	5.92	5.84		
Temperature (°C)	15.9	15.9	15.9	15.7		
Conductivity (μ mhos/cm)	0.292	0.292	0.293	.294		
Dissolved Oxygen (mg/L)	-0.16	-0.17	-0.19	-0.08		
Turbidity (NTU)	2	1	1	1		
Eh (mv)	72.4	68.1	61.7	78.6		

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μ mhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 22BR WELL LOCK STATUS: LOCKED
WELL CONDITION: GOOD WEATHER: OVERCAST 65°
GAUGE DATE: 10/9/98 GAUGE TIME: 1140
SOUNDING METHOD: SLOPE INDICATOR MEASUREMENT REF: TOP OF COVER
STICK UP/DOWN (ft): DOWN WELL DIAMETER (in.): 6"
PURGE DATE: 10/9/98 PURGE TIME: 1143
PURGE METHOD: LOW FLOW FIELD PERSONNEL: SAP/BA
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm): Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 49 E. CASING VOLUME/FT (GAL): 1.5
B. OPEN INTERVAL (ft): 25 F. CASING VOLUME (GAL) (D*E): 25.55
C. DEPTH TO WATER (ft): 6.97 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 38.3
D. H₂O COLUMN(ft) (A-B-C): 17.03

Parameter	Beginning	1	2	3	4	5	
Time (min)	1143	1214	1219	1224	1229	1234	1246
Depth to Water (ft)	6.97	7.32	7.30	7.25	7.20	7.15	7.15
Purge Rate (L/min)	1.5	0.4	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)		—	2.0	4.0	6.0	8.0	16.8
pH		7.19	7.01	6.91	6.87	6.85	6.85
Temperature (°C)		15.6	15.6	15.7	15.8	15.7	16.0
Conductivity (µmhos/cm)		0.455	0.456	0.457	0.457	0.457	0.45
Dissolved Oxygen (mg/L)		1.74	1.19	1.14	1.18	1.37	1.54
Turbidity (NTU)		3	1	1	0	0	1
Eh (mv)		73.0	62.2	59.6	60.2	61.8	57.4

TOTAL VOLUME WATER PURGED: 38 GAL + (16.8 LITERS * 0.264 GAL/LITER) = 42.4 GAL
SAMPLERS: SAP/BA SAMPLING TIME (START/END): 1235 → 1256
SAMPLING DATE: 10/9/98 DECONTAMINATION FLUIDS USED: DI H₂O, Methanol
SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: HCL, HNO₃, H₂SO₄
SAMPLE BOTTLE IDs: 22BR-100998
SAMPLE PARAMETERS: VOLUME, TDS, DOC, DISSOLVED METALS, DISSOLVED AMMONIA, ALKALINITY,
COMMENTS AND OBSERVATIONS: * 1157 flow stopped - flow started back up at 1204

PUMP #: —
LEVEL: —

ODOR: —

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 24 BR WELL LOCK STATUS: LOCKED
WELL CONDITION: Good WEATHER: Cloudy 65°F

GAUGE DATE: 10/13/98 GAUGE TIME: 1254
SOUNDING METHOD: IFP MEASUREMENT REF: TOP OF CASING
STICK UP/DOWN (ft): 3 WELL DIAMETER (in.): 8"

PURGE DATE: 10/13/98 PURGE TIME: 08:00/09:00
PURGE METHOD: Fast Purge/Low Flow FIELD PERSONNEL: DA/RH/AM
AMBIENT AIR VOCs (ppm) Start: End: WELL MOUTH VOCs (ppm) Start: End:

A. TOTAL WELL DEPTH (ft): 95 E. CASING VOLUME/FT (GAL): 2.6
B. OPEN INTERVAL (ft): 15 F. CASING VOLUME (GAL) (D*E): 189.07
C. DEPTH TO WATER (ft): 7.28 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 283.61
D. H₂O COLUMN(ft) (A-B-C): 72.72

Parameter	Beginning	1	2	3	4	5
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

TOTAL VOLUME WATER PURGED: GAL + (LITERS * 0.264 GAL/LITER) = GAL

SAMPLERS: SAMPLING TIME (START/END):
SAMPLING DATE: DECONTAMINATION FLUIDS USED:
SAMPLE TYPE: SAMPLE PRESERVATIVES:
SAMPLE BOTTLE IDs:
SAMPLE PARAMETERS:

COMMENTS AND OBSERVATIONS: Well Not Sampled -> Blocked
@ ~ 8' bgs -> Hard bottom (concrete or metal) w/
~ 1' of water @ bottom

PUMP #:
LEVEL:

ODOR:



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON
WELL I.D.: 25BR
WELL CONDITION: good

PROJECT NUMBER: 29600.43
WELL LOCK STATUS: locked-good
WEATHER: cloudy, gray, 60s

GAUGE DATE: 10/3/98
SOUNDING METHOD: intertidal probe
STICK UP/DOWN (ft): flush

GAUGE TIME: 858
MEASUREMENT REF: top of PYZ
WELL DIAMETER (in.): 8"

PURGE DATE: 101398
PURGE METHOD: Fast purge/low flow
AMBIENT AIR VOCs (ppm) Start: 0 End: 0.8

PURGE TIME: _____
FIELD PERSONNEL: A. Winkler + M. Bader
WELL MOUTH VOCs (ppm): Start: 108 End: _____

A. TOTAL WELL DEPTH (ft):	<u>100</u>
B. OPEN INTERVAL (ft):	<u>25</u>
C. DEPTH TO WATER (ft):	<u>5.57</u>
D. H ₂ O COLUMN(ft) (A-B-C):	<u>74.34 mb</u>
	69.43

E. CASING VOLUME/FT (GAL): 2.6
 F. CASING VOLUME (GAL) (D*E): 180.518
 G. 1.5 CASING VOLUMES (GAL) (F*1.5): ~270

Parameter	Beginning	1	2	3	4	5
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

TOTAL VOLUME WATER PURGED: _____ GAL + (_____ LITERS * 0.264 GAL/LITER) = _____ GAL

SAMPLERS: _____ SAMPLING TIME (START/END) : _____

SAMPLING DATE: _____ DECONTAMINATION FLUIDS USED: _____

SAMPLE TYPE: _____ SAMPLE PRESERVATIVES: _____

SAMPLE BOTTLE IDs: _____

SAMPLE PARAMETERS: _____

COMMENTS AND OBSERVATIONS: _____

Well Could Not be Completed, due to Silt at 9.8 Feet
Blocked Well

pump #: A

ODOR: None

LEVEL: Attempted level
of object

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON **PROJECT NUMBER:** 29600.43
WELL I.D.: 270R **WELL LOCK STATUS:** O.K.
WELL CONDITION: Good **WEATHER:** SHOWERS, 60's
GAUGE DATE: 10/8/98 **GAUGE TIME:** 0745
SOUNDING METHOD: WATER LEVEL INDICATOR **MEASUREMENT REF:** T.O.C.
STICK UP/DOWN (ft): 2.5 ft **WELL DIAMETER (in.):** 6"
PURGE DATE: 10/8/98 **PURGE TIME:** 0755
PURGE METHOD: Slow Purge **FIELD PERSONNEL:** AM/KS
AMBIENT AIR VOCs (ppm) Start: 0.0 End: 0.0 **WELL MOUTH VOCs (ppm):** Start: 0.0 End: 0.0

A. TOTAL WELL DEPTH (ft): 80 **E. CASING VOLUME/FT (GAL):** 1.5
B. OPEN INTERVAL (ft): 15 **F. CASING VOLUME (GAL) (D*E):** 81.87
C. DEPTH TO WATER (ft): 10.42 **G. 1.5 CASING VOLUMES (GAL) (F*1.5):** 122.81
D. H₂O COLUMN(ft) (A-B-C): 54.58

Parameter	Beginning	1	2	3	4	5
Time (min)	0755	0800	0805	0810	0840	1005
Depth to Water (ft)	10.42	28.56	41.40	47.50	54.95	59.29
Purge Rate (L/min)	5 GPM	4 GPM	3.6 GPM	4.0 GPM	0.56 GPM	0.56 GPM
Volume Purged (L)	0.06 GAL	25.6 GAL	45.6 GAL	60.6 GAL	80.6 GAL	124.6 GAL
pH	↓	↓	↓	↓	↓	↓
Temperature (°C)	↓	↓	↓	↓	↓	↓
Conductivity (μmhos/cm)	↓	↓	↓	↓	↓	↓
Dissolved Oxygen (mg/L)	↓	↓	↓	↓	↓	↓
Turbidity (NTU)	↓	↓	↓	↓	↓	↓
Eh (mv)	↓	↓	↓	↓	↓	↓

TOTAL VOLUME WATER PURGED: 124 GAL + (8 LITERS * 0.264 GAL/LITER) = 126.1 GAL
SAMPLERS: AM/KS **SAMPLING TIME (START/END):** 0755
SAMPLING DATE: 10/8/98 **DECONTAMINATION FLUIDS USED:** DI/METHANOL
SAMPLE TYPE: GRAB **SAMPLE PRESERVATIVES:** ACL, HNO₃, H₂SO₄, HgCl₂
SAMPLE BOTTLE IDs: 270R-100898
SAMPLE PARAMETERS: VOC's, TDS, DOC, DISSOLVED METALS, INORGANIC AMMONIA, SULFIDE, METHANE, DISINTEGRITY
COMMENTS AND OBSERVATIONS: Quick Purged 124 GAL / Slow Purged (2)

PUMP #: A
LEVEL: 60 ft

ODOR: NONE

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/8/18
Well ID: 27BR	Field Personnel: AM/KS	

Parameter	6	7	8	9	10	11
Time (min.)	1010	1015	1020	1025	1030	1035
Depth to Water (ft)	57.94	59.34	59.32	59.29	59.28	59.27
Purge Rate (L/min)	0.2	0.2	0.2	0.2	0.2	0.2
Volume Purged (L)	0	1.0	2.0	3.0	4.0	5.8
pH	6.87	7.26	7.28	7.34	7.45	7.49
Temperature (°C)	16.2	16.2	17.1	17.2	17.2	17.3
Conductivity (μmhos/cm)	0.275	0.253	0.253	0.247	0.244	0.243
Dissolved Oxygen (mg/L)	0.54	0.02	0.01	0.11	0.11	0.12
Turbidity (NTU)	0	0	0	0	0	0
Eh (mv)	-164.0	-159.0	-170.5	-163.8	-177.7	-185.5

Parameter	12	13	14	15	16	17
Time (min)	1040	1045	1050	Post Sample		
Depth to Water (ft)	59.30	59.29	59.30	59.45		
Purge Rate (L/min)	0.2	0.2	0.2	0.2		
Volume Purged (L)	6.0	7.0	8.0	-		
pH	7.50	7.53	7.54	7.55		
Temperature (°C)	17.4	17.4	17.4	17.6		
Conductivity (μmhos/cm)	0.243	0.242	0.242	0.242		
Dissolved Oxygen (mg/L)	0.17	0.17	0.13	0.04		
Turbidity (NTU)	0	0	0	0		
Eh (mv)	-186.9	189.7	196.7	195.5		

COMMENTS AND OBSERVATIONS _____

0/0

Sherrill A. Pullar
Brian D. Andersen

Page 1 of 2

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 28BR WELL LOCK STATUS: LOCKED
WELL CONDITION: GOOD WEATHER: Sunny 60°
GAUGE DATE: 10/6/98 GAUGE TIME: 816
SOUNDING METHOD: Interphase Probe MEASUREMENT REF: TOC
STICK UP/DOWN (ft): 2.60 WELL DIAMETER (in.): 6"
PURGE DATE: 10/6/98 PURGE TIME: 835
PURGE METHOD: LOW FLOW FIELD PERSONNEL: DA/SAP
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm): Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 91 E. CASING VOLUME/FT (GAL): 1.5
B. OPEN INTERVAL (ft): 15 F. CASING VOLUME (GAL) (D*E): 97.85
C. DEPTH TO WATER (ft): 10.77 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 146.78
D. H₂O COLUMN(ft) (A-B-C): 65.23

Parameter	Beginning	1	2	3	4	5
Time (min)	835	950	955	1000	1005	1010
Depth to Water (ft)	10.77	34.52	34.52	33.75	31.03	27.95
Purge Rate (L/min)	2 gpm	0.4	0.1	0.4	0.4	0.4
Volume Purged (L)		—	2.0	4.0	6.0	8.0
pH		6.33	6.50	6.57	6.65	6.71
Temperature (°C)		14.2	14.2	14.1	14.1	14.2
Conductivity (µmhos/cm)	Fast	0.379	0.375	0.374	0.371	0.367
Dissolved Oxygen (mg/L)	Purge	1.71	1.74	1.53	1.65	1.80
Turbidity (NTU)		-10	-10	-10	-10	-10
Eh (mv)		6.05	6.55	54.2	44.8	35.6

TOTAL VOLUME WATER PURGED: 150 GAL + (33.2 LITERS * 0.264 GAL/LITER) = 158.8 GAL

SAMPLERS: SAP/3A SAMPLING TIME (START/END): 1056 → 1113
SAMPLING DATE: 10/6/98 DECONTAMINATION FLUIDS USED: DE H₂O, Methanol
SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: HNO₃, 14.50%, HCL
SAMPLE BOTTLE IDs: 28BR-100698

SAMPLE PARAMETERS: 1565 Alkalinity, Sulfide, Inorganic Arsenic, Dissolved Metals, DOC, Dissolved

COMMENTS AND OBSERVATIONS: Started at 5 g/3 min then increased to 2.5 g/min, started pump at 20 ft then lower to 30 ft, then to 50 ft

PUMP #: 106093
ODOR: NOVE

PUMP LEVEL: 50 FT

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/15
Well ID: BR 28BR	Field Personnel: BA / SAP	

Parameter	6	7	8	9	10	11
Time (min.)	1015	1020	1025	1030*	1035	1040
Depth to Water (ft)	25.95	24.40	22.00	21.18	20.20	19.28
Purge Rate (L/min)	0.4	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)	10.0	12.0	14.0	16.0	18.0	20.0
pH	6.75	6.82	6.86	6.84	6.68	6.85
Temperature (°C)	14.8	14.7	15.3	15.4	15.5	15.7
Conductivity (µmhos/cm)	0.358	0.359	0.357	0.389	0.383	0.378
Dissolved Oxygen (mg/L)	1.76	1.96	1.66	1.80	1.67	1.48
Turbidity (NTU)	-10	-10	-10	0	0	0
Eh (mv)	31.4	28.2	29.4	30.0	29.2	28.2

Parameter	12	13	14	15	16	17
Time (min)	1045	1050	1055		1113	
Depth to Water (ft)	18.68	18.18	17.70		16.45	
Purge Rate (L/min)	0.4	0.4	0.4		0.4	
Volume Purged (L)	22.0	24.0	26.0		33.2	
pH	6.97	7.02	7.03		7.20	
Temperature (°C)	15.8	15.9	15.9		16.1	
Conductivity (µmhos/cm)	0.377	0.379	0.378		0.377	
Dissolved Oxygen (mg/L)	1.61	1.62	1.56		1.64	
Turbidity (NTU)	0	0	0		0	
Eh (mv)	26.6	26.0	26.2		26.48.0	

COMMENTS AND OBSERVATIONS * Changed baristas due to turbidity readings

455/734

Sherrill Pullar
Brian Andersen



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43

WELL I.D.: 29BR WELL LOCK STATUS: LOCKED

WELL CONDITION: GOOD WEATHER: OVERCAST, MISTY

GAUGE DATE: 10/9/98 GAUGE TIME: 824

SOUNDING METHOD: SLOPE INDICATOR MEASUREMENT REF: TOP OF COVER

STICK UP/DOWN (ft): DOWN WELL DIAMETER (in.): 6"

PURGE DATE: 10/9/98 PURGE TIME: 840

PURGE METHOD: LOW FLOW FIELD PERSONNEL: BA/SAP

AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm) Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 100 E. CASING VOLUME/FT (GAL): 1.5

B. OPEN INTERVAL (ft): 15 F. CASING VOLUME (GAL) (D*E): 118.52

C. DEPTH TO WATER (ft): 5.99 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 177.78

D. H₂O COLUMN(ft) (A-B-C): 79.01

Parameter	Beginning	1	2	3	4	5
Time (min)	840	1019	1024	1029	1034	1039
Depth to Water (ft)	5.99	6.80	6.70	6.50	6.75	6.55
Purge Rate (L/min)	2.4 gpm	0.3	0.3	0.3	0.3	0.3
Volume Purged (L)		—	1.5	3.0	4.5	6.0
pH		7.61	7.66	7.69	7.71	7.72
Temperature (°C)		16.0	16.0	16.0	16.0	16.0
Conductivity (µmhos/cm)	634	0.341	0.340	0.337	0.335	0.333
Dissolved Oxygen (mg/L)		0.42	0.38	0.38	0.37	0.36
Turbidity (NTU)		2	1	1	1	1
Eh (mv)		-42.2	-57.6	-69.8	-74.2	-78.8

TOTAL VOLUME WATER PURGED: 178 GAL + (16.2 LITERS * 0.264 GAL/LITER) = 182.3 GAL

SAMPLERS: BA/SAP SAMPLING TIME (START/END): 1055 → 1114

SAMPLING DATE: 10/9/98 DECONTAMINATION FLUIDS USED: DEH₂O, Methanol

SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: HCL, HNO₃, H₂SO₄

SAMPLE BOTTLE IDs: 29BR - 100998

SAMPLE PARAMETERS: KO₂, TDS, DO, DISSOLVED AMMONIA, METHANE, SULFIDE, DISSOLVED METALS

COMMENTS AND OBSERVATIONS: Purged till 1005 then turned off for power turn off -
Turned back on @ 1018

PUMP #1 —
LEVEL: —

ODOR: —

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/9/98
Well ID: 29BR	Field Personnel: SAP/BA	

Parameter	6	7	8	9	10	11
Time (min.)	1049	1049	1054	1055	1114	
Depth to Water (ft)	6.55	6.55	6.55	6.55	6.55	
Purge Rate (L/min)	0.3	0.3	0.3	0.3	0.3	
Volume Purged (L)	7.5	9.0	10.5	11.1	14.2	
pH	7.73	7.74	7.75	7.75	7.75	
Temperature (°C)	16.0	16.0	16.0	16.1	16.1	
Conductivity (μmhos/cm)	0.332	0.332	0.331	0.330	0.330	
Dissolved Oxygen (mg/L)	0.37	0.36	0.37	0.37	0.82	
Turbidity (NTU)	1	1	1		2	
Eh (mv)	-82.2	-85.0	-87.5		7.40	

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____

133,300 / 55,000

Page 1 of 2

EA Engineering,
Science, and
TechnologyBrian Andersen
Andrew McBrideFIELD RECORD OF WELL GAUGING,
PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
 WELL I.D.: 30 BR WELL LOCK STATUS: Good
 WELL CONDITION: Good WEATHER: cloudy, cool
 GAUGE DATE: 10/13/98 GAUGE TIME: 0815
 SOUNDING METHOD: Interface Probe MEASUREMENT REF: TOC (Butter Steel pipe)
 STICK UP/DOWN (ft): _____ WELL DIAMETER (in.): 6"
 PURGE DATE: 10/13/98 PURGE TIME: 0845
 PURGE METHOD: Fast/low flow FIELD PERSONNEL: BA, AM
 AMBIENT AIR VOCs (ppm) Start: 0.0 End: 0.0 WELL MOUTH VOCs (ppm): Start: 1.2 End: 0.0

A. TOTAL WELL DEPTH (ft): 111.5 E. CASING VOLUME/FT (GAL): 1.5
 B. OPEN INTERVAL (ft): 25 F. CASING VOLUME (GAL) (D*E): 115.86
 C. DEPTH TO WATER (ft): 9.26 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 173.79
 D. H₂O COLUMN (ft) (A-B-C): 77.24

Parameter	Beginning	1	2	3	4	5
Time (min)	0845	1115	1120	1125	1130	1135
Depth to Water (ft)		77.10	76.25	75.87	74.42	73.82
Purge Rate (L/min)	FAST 2.5-1/2 min	.2	.2	.4	.2	.2
Volume Purged (L)		.4	1.4	3.4	4.4	5.4
pH		5.87	6.15	6.27	6.40	6.40
Temperature (°C)		16.3	16.1	16.2	16.5	16.6
Conductivity (µmhos/cm)		.532	.510	.505	.498	.495
Dissolved Oxygen (mg/L)		1.60	1.08	0.91	0.64	0.64
Turbidity (NTU)		0	3	3	3	3
Eh (mv)		-89.4	-112.6	-124.2	-127.2	-123.6

TOTAL VOLUME WATER PURGED: 174 GAL + (6.4 LITERS * 0.264 GAL/LITER) = 175.7 GAL
 SAMPLERS: AM, BA SAMPLING TIME (START/END): 1143 - 1205
 SAMPLING DATE: 10/13/98 DECONTAMINATION FLUIDS USED: methanol/DI
 SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: HCL, HgCL, H₂SO₄, H₂O₂
 SAMPLE BOTTLE IDs: 30BR-101398

SAMPLE PARAMETERS: VOC, BTEX, methane, DOC, Dissolved Ammonia, Dissolved Nitrate, Inorganic Arsenic, Alkalinity, Sulfide
 COMMENTS AND OBSERVATIONS: Start fast purge 2.5 gal/min - 0855 move pump to 50' (water depth 36' + drop) - ~ 90 gal out; 0905 - water at 50' drop pump to 60' slow purge to 1 gal/min (80 gal purged so far). 0920 water level - 58' move pump to 70'; 1015 drop pump to 75' DTW - 67' (Rate 1.5 gal/min). Reach 80' @ 1050 - need 10 gal to finish fast
PUMP #: E ODOR: Slight petroleum purge. 1110 - pump at 10 gal - start low purge.
LEVEL: 80'

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/13/98
Well ID: 30BR	Field Personnel: BA, AM	

Post

Parameter	6	7	8	9	10	11
Time (min.)	1140	1205				
Depth to Water (ft)	73.04	69.85				
Purge Rate (L/min)	.2	.				
Volume Purged (L)	6.4					
pH	6.41	6.70				
Temperature (°C)	16.6	17.9				
Conductivity (µmhos/cm)	.495	.485				
Dissolved Oxygen (mg/L)	0.60	0.56				
Turbidity (NTU)	3	4				
Eh (mv)	-122.8	-116.2				

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (µmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 31BR WELL LOCK STATUS: LOCKED
WELL CONDITION: GOOD WEATHER: OVERCAST, 70°
GAUGE DATE: 10/8/98 GAUGE TIME: 800
SOUNDING METHOD: Slope Indicator MEASUREMENT REF: TOP of Inner casing
STICK UP/DOWN (ft): 4" WELL DIAMETER (in.): 4"
PURGE DATE: 10/8/98 PURGE TIME: 807
PURGE METHOD: Low Flow FIELD PERSONNEL: SAP/BA
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm) Start: 0.3 End: 0

A. TOTAL WELL DEPTH (ft): 46 E. CASING VOLUME/FT (GAL): 0.65
B. OPEN INTERVAL (ft): 10 F. CASING VOLUME (GAL) (D*E): 13.95
C. DEPTH TO WATER (ft): 14.54 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 20.92
D. H₂O COLUMN(ft) (A-B-C): 21.46

Parameter	Beginning	1	2	3	4	5
Time (min)	807	819	824	829	834	839
Depth to Water (ft)	14.54	15.15	15.15	14.76	14.73	14.79
Purge Rate (L/min)	1.5	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)		—	2.0	4.0	6.0	8.0
pH		5.93	6.09	6.13	6.57	6.18
Temperature (°C)	Fast	15.4	15.8	16.3	16.7	16.7
Conductivity (µmhos/cm)	Purge	0.332	0.319	0.310	0.307	0.306
Dissolved Oxygen (mg/L)		0.45	0.42	0.45	0.42	0.42
Turbidity (NTU)		0	0	0	0	0
Eh (mv)		84.4	97.0	101.0	101.4	101.6

TOTAL VOLUME WATER PURGED: 20 GAL + (LITERS * 0.264 GAL/LITER) = GAL
SAMPLERS: SAP/BA SAMPLING TIME (START/END): 841 → 913
SAMPLING DATE: 10/8/98 DECONTAMINATION FLUIDS USED: DI H₂O, Methanol
SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: HCL, HNO₃, H₂SO₄, HgZAAC
SAMPLE BOTTLE IDS: 31BR-100898
SAMPLE PARAMETERS: VOC+10, DISSOLVED ALKALINITY, METHANE, SULFIDE, DISSOLVED METALS, DISSOLVED AMMONIA, TD3, DOC, INORGANIC AMIC
COMMENTS AND OBSERVATIONS:

PUMP #: F

ODOR: None

LEVEL: 20 ft

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/2/98
Well ID: 31BR	Field Personnel: STA/BA	

Parameter	6	7	8	9	10	11
Time (min.)	913					
Depth to Water (ft)	14.76					
Purge Rate (L/min)	0.3					
Volume Purged (L)						
pH	6.39					
Temperature (°C)	15.9					
Conductivity (μmhos/cm)	0.318					
Dissolved Oxygen (mg/L)	0.36					
Turbidity (NTU)	1					
Eh (mv)	5.13					

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____

**FIELD RECORD OF WELL GAUGING,
PURGING, AND SAMPLING**

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 33BR WELL LOCK STATUS: locked
WELL CONDITION: USGS BOX recorder good WEATHER: cloudy 60°F
GAUGE DATE: 101398 GAUGE TIME: 0850
SOUNDING METHOD: water level meter MEASUREMENT REF: TOF casing
STICK UP/DOWN (ft): up 2 feet 3 inches WELL DIAMETER (in.): 6"
PURGE DATE: 101398 PURGE TIME: 0906 (for 42 minutes)
PURGE METHOD: fast purge / low flow FIELD PERSONNEL: M. Golberg, B. Allen
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm) Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 45 E. CASING VOLUME/FT (GAL): 1.5
B. OPEN INTERVAL (ft): 15 F. CASING VOLUME (GAL) (D*E): 27.76
C. DEPTH TO WATER (ft): 11.49 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 41.65
D. H₂O COLUMN(ft) (A-B-C): 18.51 ≈ 42 gal.

Parameter	Beginning	1	2	3	4	5
Time (min)	0906	0948	1000	1005	1010	1015
Depth to Water (ft)	11.49	11.76	11.76	11.75	11.74	11.71
Purge Rate (L/min)	→ 4 Liters / min	0.4 l/min	0.4	0.4	0.4	0.4
Volume Purged (L)	or 1.5 gal / min	42 gal total	4.8	6.8	8.8	10.8
pH			7.19	7.24	7.26	7.27
Temperature (°C)			14.4	14.4	14.5	14.5
Conductivity (μmhos/cm)			0.473	0.470	0.469	0.469
Dissolved Oxygen (mg/L)			0.46	0.52	0.52	0.33
Turbidity (NTU)			1	0	0	0
Eh (mv)			-59.3	-69.8	-74.7	-77.8

TOTAL VOLUME WATER PURGED: 42.0 GAL + (28.0 LITERS * 0.264 GAL/LITER) = 49.39 GAL
SAMPLERS: BDA/mg SAMPLING TIME (START/END): 1035-1058
SAMPLING DATE: 101398 DECONTAMINATION FLUIDS USED: Methanol / DI H₂O
SAMPLE TYPE: GRAB 33BR-101398 SAMPLE PRESERVATIVES: HgCl₂, HNO₃, NaOH, ZnAc, H₂SO₄, HCl
SAMPLE BOTTLE IDS: voc 101398, Sulfides, Methane, Diss. Metals, Diss. Ammonia, Inorg. Arsenic, DOC, TDS, + Alkalinity
SAMPLE PARAMETERS: 7
COMMENTS AND OBSERVATIONS: Used Pump C. Lowered Pump to ≈ 35 feet. NO ODORS, NO PID Reading. Has USGS meter on top of well.

PUMP #: C
ODOR: NONE

PUMP LEVEL: 35 feet

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/3/98
Well ID: 33 BR	Field Personnel: Michael Goldberg/B. Allen	

Parameter	6	7	8	9	10	11
Time (min.)	1020	1025	1030	1035	1058	
Depth to Water (ft)	11.70	11.70	11.69	sample	11.68	
Purge Rate (L/min)	0.4	0.4	0.4	taken	0.4	
Volume Purged (L)	12.8	14.8	16.8		28.0	
pH	7.28	7.30	7.33		7.43	
Temperature (°C)	14.6	14.6	14.7		15.0	
Conductivity (μmhos/cm)	0.468	0.467	0.467		0.467	
Dissolved Oxygen (mg/L)	0.17	0.23	0.21		2.02	
Turbidity (NTU)	0	0	0		1	
Eh (mv)	-80.9	-82.2	-84.5		-61.7	

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS Sample taken at 1035.



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

Rmy Winkler
Melissa Baden

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
 WELL I.D.: 34BR WELL LOCK STATUS: LOCKED
 WELL CONDITION: GOOD WEATHER: COOL, CLOUDY, 60's
 GAUGE DATE: 10/7/98 GAUGE TIME: 09:07
 SOUNDING METHOD: WLI MEASUREMENT REF: TOP OF INNER CASING
 STICK UP/DOWN (ft): FLUSH WELL DIAMETER (in.): 6"
 PURGE DATE: 10/7/98 PURGE TIME: 09:20 -
 PURGE METHOD: FAST FIELD PERSONNEL: MRB/AIW
 AMBIENT AIR VOCs (ppm) Start: 2.4 End: WELL MOUTH VOCs (ppm) Start: 5.7 End:

A. TOTAL WELL DEPTH (ft): 47 > 30.00 E. CASING VOLUME/FT (GAL): 1.5
 B. OPEN INTERVAL (ft): 17 F. CASING VOLUME (GAL) (D*E): 32.2
 C. DEPTH TO WATER (ft): 8.51 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 48.3
 D. H₂O COLUMN(ft) (A-B-C): 28.49

generally accepted

Parameter	Beginning	1	2	3	4	5
Time (min)	09:20	09:48	10:10	10:15	10:20	10:25
Depth to Water (ft)	8.51	8.88	8.90	8.95	8.93	8.97
Purge Rate (L/min)	29 gpm	.5	.5	.5	.5	.5
Volume Purged (L)	56 gal	55	57.5	60	62.5	65
pH		5.88	6.29	6.34	6.37	6.32
Temperature (°C)		13.3	13.4	13.3	13.3	13.3
Conductivity (µmhos/cm)		.314	.265	.274	.280	.282
Dissolved Oxygen (mg/L)		1.5	1.83	1.40	1.40	1.42
Turbidity (NTU)		24	74	48	37	35
Eh (mv)		113.8	56.7	63.6	77	81.5

TOTAL VOLUME WATER PURGED: 56 GAL + (LITERS * 0.264 GAL/LITER) = 82.5 GAL
 SAMPLERS: MRB/AIW SAMPLING TIME (START/END): 1105 / 1123
 SAMPLING DATE: 10/7/98 DECONTAMINATION FLUIDS USED: DI Methanol
 SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: H₂SO₄, HCl, HNO₃, HgCl₂
 SAMPLE BOTTLE IDs: 34BR-100798 ZnAc, NaOH
 SAMPLE PARAMETERS: VOC+10, TDS, DOC, dissolved ammonia, inorg. anions, diss. metals,
 COMMENTS AND OBSERVATIONS: methane, sulfide, alkalinity,

PUMP #: 200 D
 LEVEL: 28'

ODOR: NO ODO

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date:
Well ID:	Field Personnel:	

Parameter	6	7	8	9	10	11
Time (min.)	14:35					
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH	7.05					
Temperature (°C)	13.9					
Conductivity (µmhos/cm)	0.207					
Dissolved Oxygen (mg/L)	0.79					
Turbidity (NTU)	3					
Eh (mv)	399 670					

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (µmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
 WELL I.D.: 35BR WELL LOCK STATUS: Locked - Threaded Manhole
 WELL CONDITION: Good WEATHER: Sunny, 60's
 GAUGE DATE: 101598 GAUGE TIME: 935
 SOUNDING METHOD: water level man MEASUREMENT REF: top of inner casing
 STICK UP/DOWN (ft): flush 1 foot down WELL DIAMETER (in.): 6"
 PURGE DATE: 101598 PURGE TIME: 940
 PURGE METHOD: fast purge 1 foot down FIELD PERSONNEL: A. Winkler / M. Baker
 AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm): Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 48.2 E. CASING VOLUME/FT (GAL): 1.5
 B. OPEN INTERVAL (ft): 15.2 F. CASING VOLUME (GAL) (D*E): 28.05
 C. DEPTH TO WATER (ft): 14.3 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 42.1
 D. H₂O COLUMN (ft) (A-B-C): 18.7 ~43

Parameter	Beginning	1022	2	3	4	5
Time (min)	940	955	1027	1032	1037	1041
Depth to Water (ft)	14.3	20.6	20.69	20.65	20.62	20.59
Purge Rate (L/min)	3 gallons/min	0.1 L/min	0.1	0.4	0.4	0.4
Volume Purged (L)	<u>~43</u> gallons	0.5 L	8.0	3.0	5.0	7.0
pH		6.45	6.63	6.70	6.78	6.83
Temperature (°C)		13.1	13.0	13.0	13.1	13.2
Conductivity (µmhos/cm)		.188	.185	.181	.183	.182
Dissolved Oxygen (mg/L)		.48	.19	.34	0	-.01
Turbidity (NTU)		23	22	22	23	21
Eh (mv)		-191.8	-212.6	-224.6	-20.1	-229.7

TOTAL VOLUME WATER PURGED: 43 GAL + (31 LITERS * 0.264 GAL/LITER) = 51.2 GAL
 SAMPLERS: A. Winkler / M. Baker SAMPLING TIME (START/END): 1145/1153
 SAMPLING DATE: 101598 DECONTAMINATION FLUIDS USED: Dist Water / Methanol
 SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: HCl, H₂SO₄, HNO₃, ZnAc₂, NaOH, H₂O₂, Cl₂
 SAMPLE BOTTLE IDs: 35BR-101598 Inorganic Arsenic
 SAMPLE PARAMETERS: VOC, TDS, Methane, DOC, Alkalinity, Dissolved Metals, Dissolved Ammonia
 COMMENTS AND OBSERVATIONS: Well Cover Must be removed with a large Well Wrench. At 954 the Well was Dry. Purging was Completed. Started by flow at 1022



Pump: B Odor: None
 Level: 25 feet

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/5/8
Well ID: 35BR-101598	Field Personnel: M R B / A L W	

Parameter	6	7	8	9	10	11
Time (min.)	1045	1049	1054	1059	1104	1109
Depth to Water (ft)	20.59	20.5		20.7	20.6	20.45
Purge Rate (L/min)	0.4	0.4	flow	0.4	0.4	0.4
Volume Purged (L)	9.0	11.0	through	15.0	17.0	19.0
pH	6.88	6.94	cell	6.95	7.11	7.14
Temperature (°C)	13.3	13.4	cleaned	14.6	14.7	15.0
Conductivity (µmhos/cm)	.181	.180		.180	.179	.176
Dissolved Oxygen (mg/L)	-0.03	-0.05		0.5	.23	.30
Turbidity (NTU)	21	21		21	20	20
Eh (mv)	-226.5	-222		-146.1	-143.1	-132.1

Parameter	12	13	14	15	16	17
Time (min)	1114	1119	1124	1128	1134	1139
Depth to Water (ft)	20.35	20.28	20.2	20.13	20.04	20.02
Purge Rate (L/min)	0.4	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)	21.0	23.0	25.0	27.0	29.0	31.0
pH	7.08	7.05	7.02	6.99	6.97	6.96
Temperature (°C)	15.1	15.1	15.1	15.1	15.0	15.0
Conductivity (µmhos/cm)	.176	.178	.179	.179	.178	.180
Dissolved Oxygen (mg/L)	.34	.26	.35	.66	1.08	.96
Turbidity (NTU)	18	16	16	17	17	17
Eh (mv)	-117.0	-103.1	-88.1	-73	-54.0	-46.8

COMMENTS AND OBSERVATIONS 1054 flow through cell checked
Sample collected 1145 - 2 hours since beginning purge



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/5/88
Well ID: 35BR-101588	Field Personnel: M. B. A. L.	

Post Sample

Parameter	18	19	20	21	22	23
Time (min.)	1153					
Depth to Water (ft)	20.0					
Purge Rate (L/min)	0.4					
Volume Purged (L)						
pH	6.89	7.19				
Temperature (°C)	14.6					
Conductivity (μmhos/cm)	199					
Dissolved Oxygen (mg/L)	1.53					
Turbidity (NTU)	12					
Eh (mv)	-163					

Parameter	24	25	26	27	28	29
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____

149,000 / 25,500.

Page 1 of 1



Well in treatment system building.

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
 WELL I.D.: 36BR WELL LOCK STATUS: N/A
 WELL CONDITION: Good - sample port in treatment building. WEATHER: Sunny 60 to 70°
 GAUGE DATE: N/A GAUGE TIME: N/A
 SOUNDING METHOD: N/A MEASUREMENT REF: N/A
 STICK UP/DOWN (ft): Valve WELL DIAMETER (in.): 6"

PURGE DATE: 101498 PURGE TIME: 1448
 PURGE METHOD: low flow FIELD PERSONNEL: B. Allen M. Goldberg
 AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm): Start: 0 End: 0
0 on Draeger tube 0 on Draeger tube

A. TOTAL WELL DEPTH (ft): 125 E. CASING VOLUME/FT (GAL): 1.5
 B. OPEN INTERVAL (ft): 23 F. CASING VOLUME (GAL) (D*E): N/A
 C. DEPTH TO WATER (ft): N/A G. 1.5 CASING VOLUMES (GAL) (F*1.5): N/A
 D. H₂O COLUMN(ft) (A-B-C): N/A

Sample taken at 1450

Parameter	Beginning	1	2	3	4	5
Time (min)	1448	1448 BDA				
Depth to Water (ft)	N/A					
Purge Rate (L/min)						
Volume Purged (L)	3 gallons total					
pH		7.13				
Temperature (°C)		17.8				
Conductivity (μmhos/cm)		0.278				
Dissolved Oxygen (mg/L)		1.43				
Turbidity (NTU)		0				
Eh (mv)		-115.4				

TOTAL VOLUME WATER PURGED: _____ GAL + (_____ LITERS * 0.264 GAL/LITER) = ≈ 3.0 GAL
 SAMPLERS: BDA / MG SAMPLING TIME (START/END): 1450 to 1503
 SAMPLING DATE: 101498 DECONTAMINATION FLUIDS USED: Methanol / DTHO
 SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: HgCl₂, HNO₃, HCL, NaOH, ZnAc, H₂SO₄
 SAMPLE BOTTLE IDs: 36BR-101498
 SAMPLE PARAMETERS: VOC, TDS, DOX, Diss. Ammonia, Alkalinity, Diss. Metals, Inorg. Phosphorus, Methane, Surfactants
 COMMENTS AND OBSERVATIONS: No readings on Draeger tube + PID. Used fan and stood upwind. Sample taken at 1450. Water quality readings taken at 1448.

PUMP #: N/A
 LEVEL: N/A

ODOR: NONE
(Used Fan)

2/3

Sherri Pullar
Brian Andersen

Page 1 of 2



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
 WELL I.D.: 37 BR WELL LOCK STATUS: LOCKED
 WELL CONDITION: GOOD WEATHER: Sunny 65° Light breeze
 GAUGE DATE: 10/6/98 GAUGE TIME: 1254
 SOUNDING METHOD: Interphase Probe MEASUREMENT REF: 702
 STICK UP/DOWN (ft): 3.7 WELL DIAMETER (in.): 6"
 PURGE DATE: 10/6/98 PURGE TIME: 1304 - 1420
 PURGE METHOD: LOW FLOW FIELD PERSONNEL: BA/SAP
 AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm) Start: 9 End: 0

A. TOTAL WELL DEPTH (ft): 75 E. CASING VOLUME/FT (GAL): 1.5
 B. OPEN INTERVAL (ft): 15 F. CASING VOLUME (GAL) (D*E): 73.83
 C. DEPTH TO WATER (ft): 10.78 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 110.75
 D. H₂O COLUMN(ft) (A-B-C): 49.22

Parameter	Beginning	1	2	3	4	5
Time (min)	<u>1304</u>	<u>1350</u>	<u>1405</u>	<u>1410</u>	<u>1415</u>	<u>1420</u>
Depth to Water (ft)	<u>10.78</u>	<u>34.50</u>	<u>32.71</u>	<u>30.68</u>	<u>29.05</u>	<u>28.00</u>
Purge Rate (L/min) *	<u>2.5 gpm</u>	<u>.6</u>	<u>.4</u>	<u>.4</u>	<u>.4</u>	<u>.4</u>
Volume Purged (L)		<u>1.2</u>	<u>4.2</u>	<u>6.2</u>	<u>8.2</u>	<u>10.2</u>
pH		<u>6.55</u>	<u>6.40</u>	<u>6.35</u>	<u>6.32</u>	<u>6.31</u>
Temperature (°C)	<u>Fast</u>	<u>14.7</u>	<u>14.9</u>	<u>15.0</u>	<u>15.0</u>	<u>14.9</u>
Conductivity (μmhos/cm)		<u>.226</u>	<u>.228</u>	<u>.228</u>	<u>.228</u>	<u>.229</u>
Dissolved Oxygen (mg/L)	<u>Purge</u>	<u>0.04</u>	<u>0.09</u>	<u>0.08</u>	<u>0.08</u>	<u>0.08</u>
Turbidity (NTU)		<u>9</u>	<u>2</u>	<u>0</u>	<u>0</u>	<u>0</u>
Eh (mv)		<u>-45.2</u>	<u>-34.0</u>	<u>-38.6</u>	<u>-39.8</u>	<u>-40.0</u>

TOTAL VOLUME WATER PURGED: 115 GAL + (10.2 LITERS * 0.264 GAL/LITER) = 117.7 GAL
 SAMPLERS: BA/SAP SAMPLING TIME (START/END): (1425) → 1455
 SAMPLING DATE: 10/6/98 DECONTAMINATION FLUIDS USED: DI, neutral
 SAMPLE TYPE: grab SAMPLE PRESERVATIVES: Argon, HCL, HNO₃, H₂SO₄, Hg Cl₂
 SAMPLE BOTTLE IDs: 37BR-100698
 SAMPLE PARAMETERS: VOC, Dissolved Metals, Inorganics, Anions, DOC, Methane, TOC, Alkalinity, Dissolved ammonia
 COMMENTS AND OBSERVATIONS: Fast Purge started at 20 ft and 2.5 gal/min then to 30 ft and 2.5 gal/min eventually to 50 ft to finish.
Flow adjust necessary due to rising water in well during slow, low flow.

PUMP #: 9717070 ODOR: NONE observed.
 LEVEL: 50 ft.

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10 06 98
Well ID: 37BR	Field Personnel: SAP / BFA	

post sample

Parameter	6	7	8	9	10	11
Time (min.)	1455	1455				
Depth to Water (ft)	23.97					
Purge Rate (L/min)						
Volume Purged (L)						
pH	6.87					
Temperature (°C)	14.9					
Conductivity (µmhos/cm)	0.230					
Dissolved Oxygen (mg/L)	0.06					
Turbidity (NTU)	0					
Eh (mv)	14.0					

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (µmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____

27-20-46,900



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 38BR WELL LOCK STATUS: Locked
WELL CONDITION: Good WEATHER: Gray, Cloudy, Rainy
GAUGE DATE: 101398 GAUGE TIME: 1115
SOUNDING METHOD: water level meter MEASUREMENT REF: Topo + Well Cas'g
STICK UP/DOWN (ft): 5' 11" 5' 1" WELL DIAMETER (in.): 8"
PURGE DATE: 101398 PURGE TIME: 11:19
PURGE METHOD: fast purge low flow FIELD PERSONNEL: A. Winkler + M. Bader
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm): Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 115' E. CASING VOLUME/FT (GAL): 2.6
B. OPEN INTERVAL (ft): 15' F. CASING VOLUME (GAL) (D*E): 226.616
C. DEPTH TO WATER (ft): 12.84 G. 1.5 CASING VOLUMES (GAL) (F*1.5): ~ 339 Gallons
D. H₂O COLUMN(ft) (A-B-C): 87.16

Parameter	Beginning	1	2	3	4	5
Time (min)	1119	1227	1534	1538	1542	1546
Depth to Water (ft)	12.84	75.6	72.28	71.50	71.50	71.40
Purge Rate (L/min)	5 gull/min	0.5L	0.5L	0.5L	0.5	0.5
Volume Purged (L)		2.5L	5.0L	7.5L	10.0	12.5
pH		6.74	6.79	6.86	6.88	6.93
Temperature (°C)		15.9	15.9	15.9	16.8	16.6
Conductivity (µmhos/cm)		0.476	0.476	0.460	0.465	0.476
Dissolved Oxygen (mg/L)		0.87	0.28	0.19	0.18	0.08
Turbidity (NTU)		-8	-8	-8	-9	-9
Eh (mv)		-144.6	-151.4	-164.0	-167.2	-161.6

TOTAL VOLUME WATER PURGED: 339 GAL + (20) LITERS * 0.264 GAL/LITER = 344.28 GAL

SAMPLERS: MGBIAW SAMPLING TIME (START/END): 1602-1
SAMPLING DATE: 101398 DECONTAMINATION FLUIDS USED: DI Water/Methanol
SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: HCl, HNO₃, H₂SO₄, HgCl₂, ZnAc, NaOH
SAMPLE BOTTLE IDs: 38BR-101398 Alkalinity

SAMPLE PARAMETERS: VOC, Methane, TDS, Sulfides, Dissolved Metals, Inorganic Anions, DO, Dissolved
COMMENTS AND OBSERVATIONS: At 1235' Well Vent 2 Dr. Started purging again
+ 2407 - Depth to water has only recharged to 60 feet - Pumped Well
to Dryness at 1445, Completed Purging ~ 340 Gallons. Turbidity is reading - Number
but sample is clear

PUMP #: F
LEVEL: 80 feet
ODOR: Sulfur

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/3/98
Well ID: 38BR-101328	Field Personnel: A. Winkler, H. B. Jr.	

Post-purge

Parameter	6	7	8	9	10	11
Time (min.)	1550	1555	1600			
Depth to Water (ft)	70.41	70.25	69.71			
Purge Rate (L/min)	0.5	0.5	0.5			
Volume Purged (L)	15.0	17.5	20.0			
pH	6.97	7.04	7.09			
Temperature (°C)	16.5	16.4	16.3			
Conductivity (µmhos/cm)	.480	.481	.482			
Dissolved Oxygen (mg/L)	0	-0.03	-0.07			
Turbidity (NTU)	-9	-9	-9			
Eh (mv)	-173.2	-179.1	-173.8			

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (µmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

Melissa Badler
Bethany Allen

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 39 BR WELL LOCK STATUS: Locked
WELL CONDITION: Good WEATHER: 65°-70°F drizzling cloudy
GAUGE DATE: 100898 GAUGE TIME: 0845
SOUNDING METHOD: water level meter MEASUREMENT REF: top of casing
STICK UP/DOWN (ft): up WELL DIAMETER (in.): 4"

PURGE DATE: 100898 PURGE TIME: 0904
PURGE METHOD: fast purge low flow FIELD PERSONNEL: B. Allen M. Badler
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm): Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 88 E. CASING VOLUME/FT (GAL): 0.65
B. OPEN INTERVAL (ft): 20 F. CASING VOLUME (GAL) (D*E): 35.07
C. DEPTH TO WATER (ft): 14.05 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 52.61
D. H₂O COLUMN(ft) (A-B-C): 53.95 253 gal.

Parameter	Beginning	1	2	3	4	5
Time (min)	0904	0919	0952	0957	1002	1007
Depth to Water (ft)	14.05	19.71	19.75	14.75	14.65	14.66
Purge Rate (L/min)	2 gpm	1 gpm	0.5 L/min	0.5 L/min	0.5	0.5
Volume Purged (L)	30 gal	33 gal	33 gal	2.5 L	5.0	7.5
pH				7.12	7.21	7.29
Temperature (°C)			63 total	17.4	17.6	17.8
Conductivity (µmhos/cm)			gallons	0.280	0.276	0.274
Dissolved Oxygen (mg/L)			purged	0.28	0.22	0.29
Turbidity (NTU)				0	0	0
Eh (mv)				-163.7	-168.4	-182.2

TOTAL VOLUME WATER PURGED: 53 GAL + (27.5 LITERS * 0.264 GAL/LITER) = 72.6 GAL = 60.2
SAMPLERS: BDA mb SAMPLING TIME (START/END): 1044/1102
SAMPLING DATE: 100898 DECONTAMINATION FLUIDS USED: DI Water
SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: HCl, HNO₃, TAA, NaOH, H₂Cl₂, H₂SO₄
SAMPLE BOTTLE IDS: 39 BR-100896
SAMPLE PARAMETERS: VOC, 105, Nitrate, DOC, Dissolved Alkalinity, Dissolved Metals, Inorganic Arsenic & S
COMMENTS AND OBSERVATIONS: WGS boxes on well. Decreased flow to 1 gpm at 0919 and purged at that rate until 0952. Decreased purge rate from 2 gpm to 1 gpm b/c water level was decreasing too quick.

PUMP #: C
ODOR: NONE.

PUMP LEVEL: 20 feet initially at 0904 then 30 to 35 feet at 0919.

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 100898
Well ID: 396R	Field Personnel: B. Allen / M. Baden	

Parameter	6	7	8	9	10	11
Time (min.)	1012	1017	1022	1027	1032	1037
Depth to Water (ft)	14.66	14.66	14.65	14.61	14.62	14.58
Purge Rate (L/min)	0.5	0.5	0.5	0.5	0.5	0.5
Volume Purged (L)	10.0	12.5	15.0	17.5	20.0	22.5
pH	7.35	7.41	7.50	7.59	7.61	7.68
Temperature (°C)	17.9	18.2	18.4	18.6	18.6	18.7
Conductivity (μmhos/cm)	0.273	0.272	0.271	0.271	0.271	0.270
Dissolved Oxygen (mg/L)	0.38	0.23	0.32	0.30	0.30	0.29
Turbidity (NTU)	0	0	0	0	0	0
Eh (mv)	-187.2	-183.8	-186.8	-185.1	-186.9	-186.9

Post Sample

Parameter	12	13 ↓	14	15	16	17
Time (min)	1042	1102				
Depth to Water (ft)	14.57	14.25				
Purge Rate (L/min)	0.5	0.5				
Volume Purged (L)	25.0	27.5				
pH	7.67	7.88				
Temperature (°C)	18.9	17.4				
Conductivity (μmhos/cm)	0.270	0.279				
Dissolved Oxygen (mg/L)	0.29	0.27				
Turbidity (NTU)	0	0				
Eh (mv)	-195.7	-169.1				

COMMENTS AND OBSERVATIONS _____



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
 WELL I.D.: 40 BR WELL LOCK STATUS: Not locked
 WELL CONDITION: good WEATHER: Raining, 75°
 GAUGE DATE: 10/3/98 GAUGE TIME: 1430
 SOUNDING METHOD: Interphase probe MEASUREMENT REF: TOC
 STICK UP (DOWN) (ft): 4" WELL DIAMETER (in.): 4"

PURGE DATE: 10/3/98 PURGE TIME: 1437
 PURGE METHOD: LOW FLOW FIELD PERSONNEL: SAF/BA
 AMBIENT AIR VOCs (ppm) Start: RAW End: RAIN WELL MOUTH VOCs (ppm) Start: Trap End: Don

A. TOTAL WELL DEPTH (ft): 129 E. CASING VOLUME/FT (GAL): 0.65 DO
 B. OPEN INTERVAL (ft): 25 F. CASING VOLUME (GAL) (D*E): 59.48 Turb
 C. DEPTH TO WATER (ft): 12.50 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 89.22 EH
 D. H₂O COLUMN(ft) (A-B-C): 91.50
 Handwritten notes: Read 5.1 temp, DO 0.44, Ex - 141.6, 11 ph 7.27, CO 0.295, turb 114

Parameter	Beginning	1	2	3	4	5
Time (min)	1440	1640	1645	1650	1655	1705
Depth to Water (ft)	12.50					
Purge Rate (L/min)	1 gpm	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)		0.40	0.42	4.0	6.0	8.0
pH		7.45	7.42	7.49	7.44	7.49
Temperature (°C)	Fast	15.6	15.7	15.5	15.2	15.3
Conductivity (µmhos/cm)		0.261	0.270	0.281	0.283	0.299
Dissolved Oxygen (mg/L)	Purge	1.31	1.11	0.99	0.92	0.51
Turbidity (NTU)		491	225	206	173	115
Eh (mv)	10	-34.2	-101.2	-137.6	-139.6	-121.6

TOTAL VOLUME WATER PURGED: 1701 GAL + (1735 LITERS * 0.264 GAL/LITER) = 1735 GAL

SAMPLERS: SAF/BA SAMPLING TIME (START/END): 1701 → 1735

SAMPLING DATE: 10/3/98 DECONTAMINATION FLUIDS USED: DE 4, 2, Methanol

SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: HCL, HNO₃, H₂SO₄

SAMPLE BOTTLE IDs: 40 BR - 1003 98

SAMPLE PARAMETERS: VOC + 10, Methane, sulfide, alkalinity, dissolved anions, dissolved metals

COMMENTS AND OBSERVATIONS: Water running into well very muddy before low flow started

PUMP #: E
 LEVEL: 70'

ODOR: 5.1

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 41 BR WELL LOCK STATUS: UNLOCKED
WELL CONDITION: OK WEATHER: CLOUDY, 60'S

GAUGE DATE: N/A GAUGE TIME: N/A
SOUNDING METHOD: N/A MEASUREMENT REF: N/A
STICK UP/DOWN (ft): N/A WELL DIAMETER (in.): 4"

PURGE DATE: N/A PURGE TIME: N/A
PURGE METHOD: Am/KS FIELD PERSONNEL: Am/KS
AMBIENT AIR VOCs (ppm) Start: 0.0 End: 0.0 WELL MOUTH VOCs (ppm) Start: 1.58 End: 17.3

A. TOTAL WELL DEPTH (ft): 110 E. CASING VOLUME/FT (GAL): 0.65
B. OPEN INTERVAL (ft): 25 F. CASING VOLUME (GAL) (D*E): N/A
C. DEPTH TO WATER (ft): N/A G. 1.5 CASING VOLUMES (GAL) (F*1.5): N/A
D. H₂O COLUMN(ft) (A-B-C): N/A

Parameter	Beginning	1	2	3	4	5
Time (min)	<u>0945</u>	<u>1007</u>				
Depth to Water (ft)	<u>N/A</u>	<u>N/A</u>				
Purge Rate (L/min)	<u>↓</u>	<u>↓</u>				
Volume Purged (L)	<u>↓</u>	<u>↓</u>				
pH	<u>6.79</u>	<u>6.81</u>				
Temperature (°C)	<u>16.1</u>	<u>16.4</u>				
Conductivity (μmhos/cm)	<u>0.374</u>	<u>0.382</u>				
Dissolved Oxygen (mg/L)	<u>3.78</u>	<u>3.45</u>				
Turbidity (NTU)	<u>0</u>	<u>0</u>				
Eh (mv)	<u>N/A</u>	<u>N/A</u>				

TOTAL VOLUME WATER PURGED: N/A GAL + (N/A LITERS * 0.264 GAL/LITER) = N/A GAL
SAMPLERS: Am/KS SAMPLING TIME (START/END): 0955-1005
SAMPLING DATE: 10/9/98 DECONTAMINATION FLUIDS USED: DJ / methanol
SAMPLE TYPE: CRAB SAMPLE PRESERVATIVES: HCC/ANO₂/H₂SO₄/H₂O₂
SAMPLE BOTTLE IDs: 41 BR-100998
SAMPLE PARAMETERS: VOC'S, Inorganic Anions, Dissolved Metals, Nitrate, Sulfide, DOC, Diss. Ammonia, TDS
COMMENTS AND OBSERVATIONS: EXTRACTION WELL

PUMP #: N/A
LEVEL: N/A

ODOR: N/A

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

Melissa Bader
Bethany Allen

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 42 BR WELL LOCK STATUS: not locked
WELL CONDITION: good WEATHER: drizzling cloudy
GAUGE DATE: 100898 GAUGE TIME: 0835
SOUNDING METHOD: water level meter MEASUREMENT REF: top of steel casing
STICK UP/DOWN (ft): up WELL DIAMETER (in.): 4"
PURGE DATE: 100898 PURGE TIME: 0855
PURGE METHOD: fast purge / low flow FIELD PERSONNEL: B. Allen / M. Bader
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm) Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 140 E. CASING VOLUME/FT (GAL): 0.65
B. OPEN INTERVAL (ft): 20 F. CASING VOLUME (GAL) (D*E): 69.62
C. DEPTH TO WATER (ft): 12.9 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 104.43
D. H₂O COLUMN(ft) (A-B-C): 107.1 ≈ 105 gal

0918

Parameter	Beginning	1 <u>(20 ft)</u>	2	3	4	5	
Time (min)	0855	0918 1017	1022	1027	1032		
Depth to Water (ft)	12.9	22.65	25.84	24.14	23.80	23.57	
Purge Rate (L/min)	2 gal/min or 1 gpm	0.5	0.5	0.5	0.5	0.5	
Volume Purged (L)	81 liters per minute	59 * 46 = 105		2.5	5.0	7.5	
pH		59 gal purged		8.06	8.40	8.66	
Temperature (°C)	total 106 gallons			17.4	17.2	16.9	
Conductivity (μmhos/cm)	46 gal			0.345	0.342	0.344	
Dissolved Oxygen (mg/L)				0.02	0.09	0.12	
Turbidity (NTU)				0	0	0	
Eh (mv)				-258.8	-257.3	-260.2	113.05

TOTAL VOLUME WATER PURGED: 105 GAL + (30.5 LITERS * 0.264 GAL/LITER) = 80.52 GAL 185.52
SAMPLERS: BDA / MB SAMPLING TIME (START/END): 1100 / 1118
SAMPLING DATE: 100898 DECONTAMINATION FLUIDS USED: DI Water / Methanol
SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: HNO₃, H₂SO₄, HgCl₂, ZnAc₂, HCl, H₂O₂
SAMPLE BOTTLE IDs: 42BR-100898

SAMPLE PARAMETERS: VOC, TOS, Methanol, DOC, Dissolved Metals, Dissolved Ammonia, Inorganic Arsenic, Sulfate
COMMENTS AND OBSERVATIONS: USGS boxes on wells. Decrease purge rate from 2gpm to 1gpm b/c water level was decreasing too quickly + did not have enough tubing. 46 gallons purged from 0855 to 0918

PUMP #: 7

ODOR: NONE

PUMP LEVEL #: 20 feet for fast purge
35 feet at 0918

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 100898
Well ID: BRP3-100898	Field Personnel: BDA/TKB	

Parameter	6	7	8	9	10	11
Time (min.)	1037	1042	1047	1052	1118	
Depth to Water (ft)	21.91	21.41	21.31	21.16	22.76	
Purge Rate (L/min)	.5	.5	.5	.5	.5	
Volume Purged (L)	10	12.5	15	17.5	30.5	
pH	8.70	8.77	8.78	8.79	9.22	
Temperature (°C)	17.4	17.3	17.2	17.2	16.8	
Conductivity (µmhos/cm)	.340	.341	.344	.344	.346	
Dissolved Oxygen (mg/L)	-0.11	-0.10	-0.11	-0.11	0.05	
Turbidity (NTU)	0	0	0	0	0	
Eh (mv)	-2596	11.21	11.39	11.48	-122	

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (µmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
 WELL I.D.: 43 BR WELL LOCK STATUS: good
 WELL CONDITION: good WEATHER: overcast, 50°
 GAUGE DATE: 10/12/98 GAUGE TIME: 0920
 SOUNDING METHOD: Interfer probe MEASUREMENT REF: TOC (Inside Steel pipe)
 STICK UP/DOWN (ft): WELL DIAMETER (in.): 4"
 PURGE DATE: 10/12/98 PURGE TIME: N/A
 PURGE METHOD: No purge FIELD PERSONNEL: BA AM
 AMBIENT AIR VOCs (ppm) Start: 0.0 End: 0.0 WELL MOUTH VOCs (ppm): Start: 0.0 End: 0.0

A. TOTAL WELL DEPTH (ft): 410 E. CASING VOLUME/FT (GAL): 0.65
 B. OPEN INTERVAL (ft): 25 F. CASING VOLUME (GAL) (D*E): 214.83
 C. DEPTH TO WATER (ft): 54.50 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 322.25
 D. H₂O COLUMN(ft) (A-B-C): 330.50

Parameter	Beginning	1	2	3	4	5
Time (min)	<u>0945</u>					
Depth to Water (ft)						
Purge Rate (L/min)	<u>—</u>					
Volume Purged (L)						
pH	<u>10.88</u>					
Temperature (°C)	<u>14.7</u>					
Conductivity (µmhos/cm)	<u>1.52</u>					
Dissolved Oxygen (mg/L)	<u>10.98</u>					
Turbidity (NTU)	<u>125</u>					
Eh (mv)	<u>-107.2</u>					

TOTAL VOLUME WATER PURGED: GAL + (LITERS * 0.264 GAL/LITER) = GAL
 SAMPLERS: BA, A SAMPLING TIME (START/END): 1000
 SAMPLING DATE: 10/12/98 DECONTAMINATION FLUIDS USED: DI
 SAMPLE TYPE: SAMPLE PRESERVATIVES: HCl, HNO₃, HgCl₂, H₂SO₄
 SAMPLE BOTTLE IDs: 43BR-101298
 SAMPLE PARAMETERS: VOC, TDS, Methane, DOC, Dissolved Metals, Inorganic Anions, Alkalinity
 COMMENTS AND OBSERVATIONS: Sample Collected

SAMPLE COLLECTED w/ BAILER LOWERED TO OPEN INTERVAL

PUMP #: NA

ODOR: None observed

PUMP LEVEL: NA



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 44 BR WELL LOCK STATUS: good
WELL CONDITION: good WEATHER: overcast 50°

GAUGE DATE: 10/12/98 GAUGE TIME: 0925
SOUNDING METHOD: Interfer probe MEASUREMENT REF: TOC (inside pipe)
STICK UP/DOWN (ft): 4" WELL DIAMETER (in.): 4"

PURGE DATE: No Purge PURGE TIME: NA
PURGE METHOD: — FIELD PERSONNEL: BA
AMBIENT AIR VOCs (ppm) Start: 0.0 End: 0.0 WELL MOUTH VOCs (ppm) Start: 0.0 End: 0.0

A. TOTAL WELL DEPTH (ft): 330 E. CASING VOLUME/FT (GAL): 0.65
B. OPEN INTERVAL (ft): 25 F. CASING VOLUME (GAL) (D*E):
C. DEPTH TO WATER (ft): 58.84 G. 1.5 CASING VOLUMES (GAL) (F*1.5):
D. H₂O COLUMN(ft) (A-B-C):

Parameter	Beginning	1	2	3	4	5
Time (min)	1025					
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH	10.12					
Temperature (°C)	16.1					
Conductivity (µmhos/cm)	825					
Dissolved Oxygen (mg/L)	11.29					
Turbidity (NTU)	2					
Eh (mv)	-50.2					

TOTAL VOLUME WATER PURGED: NA GAL + (LITERS * 0.264 GAL/LITER) = GAL
SAMPLERS: 2H, AM, BA SAMPLING TIME (START/END): 1135
SAMPLING DATE: 10/12/98 DECONTAMINATION FLUIDS USED: DH2O, Methanol
SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: HCL, HgCL, H2SO4, HAKB
SAMPLE BOTTLE IDs: 44BR-101298 (FBB - taken on bauer) for VOCs
SAMPLE PARAMETERS: VOC, DOC, Methane, Dissolved Ammonia, Dissolved Metals, TDS, Inorganic Alkalinity, Arsenic, Sulfate
COMMENTS AND OBSERVATIONS: SAMPLE COLLECTED w/ BAITER FROM OPEN INTERVAL

PUMP #: None ODOR: None PUMP LEVEL: None
Detected

4140 / 800

Page 1 of 1



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
 WELL I.D.: 45BR WELL LOCK STATUS: Locked
 WELL CONDITION: Good WEATHER: Warm Sunny
EXTRACTION WELL
 GAUGE DATE: 101498 GAUGE TIME: 1540
 SOUNDING METHOD: water level meter MEASUREMENT REF: top of well casing
 STICK UP/DOWN (ft): 3 feet WELL DIAMETER (in.): 4"
 PURGE DATE: 101498 PURGE TIME: NA
 PURGE METHOD: low flow FIELD PERSONNEL: NA
 AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm): Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 210 E. CASING VOLUME/FT (GAL): 0.65
 B. OPEN INTERVAL (ft): 25 F. CASING VOLUME (GAL) (D*E): —
 C. DEPTH TO WATER (ft): NA G. 1.5 CASING VOLUMES (GAL) (F*1.5): —
 D. H₂O COLUMN (ft) (A-B-C): NA

Parameter	Beginning	1	2	3	4	5
Time (min)		1555	1600			
Depth to Water (ft)		—	Sample			
Purge Rate (L/min)		—	Taken			
Volume Purged (L)		—				
pH		7.57				
Temperature (°C)		14.2				
Conductivity (μmhos/cm)		331				
Dissolved Oxygen (mg/L)		1.18				
Turbidity (NTU)		—8				
Eh (mv)		-46.0				

TOTAL VOLUME WATER PURGED: — GAL + (— LITERS * 0.264 GAL/LITER) = — GAL
 SAMPLERS: R. Winkler / M. Bader SAMPLING TIME (START/END): 1600 / 1643
 SAMPLING DATE: 101498 DECONTAMINATION FLUIDS USED: DI Water / Method
 SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: HCl, HNO₃, H₂SO₄, H₂O₂, NaOH, Zn
 SAMPLE BOTTLE IDs: 45BR-101498
 SAMPLE PARAMETERS: VOC, Methane, TDS, Sulfides, Alkalinity, DOC, Dissolved Ammonia, Dissolved Nitrate
 COMMENTS AND OBSERVATIONS: Well is on at this time. No purge necessary.
INORGANIC ANIONS

PUMP #: Extraction
 LEVEL: Well

ODOR: None

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 46 OR WELL LOCK STATUS: Good
WELL CONDITION: good WEATHER: overcast
GAUGE DATE: 10/12/98 GAUGE TIME: 1355
SOUNDING METHOD: Interface Probe MEASUREMENT REF: TOC (Inside steel pipe)
STICK UP/DOWN (ft): 4" WELL DIAMETER (in.): 4"

PURGE DATE: 10/12/98 PURGE TIME: 1420 - 1630
PURGE METHOD: Fast / Low Flow FIELD PERSONNEL: AM, BA
AMBIENT AIR VOCs (ppm) Start: 0.0 End: 0.0 WELL MOUTH VOCs (ppm) Start: 0.0 End: 0.0

A. TOTAL WELL DEPTH (ft): 223 E. CASING VOLUME/FT (GAL): 0.65
B. OPEN INTERVAL (ft): 25 F. CASING VOLUME (GAL) (D*E): 58.253
C. DEPTH TO WATER (ft): 108.38 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 87.38
D. H₂O COLUMN(ft) (A-B-C): 89.62

Parameter	Begin	Beginning	2	3	4	5	6
Time (min)	1420	1605	1610	1615	1620	1625	1630
Depth to Water (ft)	150+	150+	150+	150+	150+	150+	150+
Purge Rate (L/min)	14m	.4	.2	.2	.2	.2	.2
Volume Purged (L)		2.0	3.0	4.0	5.0	6.0	7.0
pH	Fast	11.49	11.50	11.45	11.40	11.39	11.39
Temperature (°C)	purge	17.3	16.9	16.9	16.8	16.8	16.8
Conductivity (µmhos/cm)		1.16	1.21	1.21	1.22	1.22	1.22
Dissolved Oxygen (mg/L)		1.02	0.71	0.65	0.60	0.61	0.60
Turbidity (NTU)		0	0	1	0	0	0
Eh (mv)		-108.4	-125.2	-128.8	-133.8	-132.8	-132.6

TOTAL VOLUME WATER PURGED: 40 GAL + (7 LITERS * 0.264 GAL/LITER) = 41.79 GAL

SAMPLERS: AM, BA SAMPLING TIME (START/END): 1632

SAMPLING DATE: 10/12/98 DECONTAMINATION FLUIDS USED: methanol, DI

SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: HCL, HgCl, H₂SO₄, HNO₃

SAMPLE BOTTLE IDs: 46 BE-101298

SAMPLE PARAMETERS: VOC, DOC, Methane, Dissolved DOC, Metals, Dissolved NH₄, Inorganic Ammonia, Alkalinity, Sulfide.

COMMENTS AND OBSERVATIONS: 1530 - purge at 150' slow up purge to see if well recharges (~12 L/min) - purge out ~40 gal by 1605 - set up to check parameters because well level decreasing.

PUMP #: F
LEVEL: 160'

ODOR: None observed

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/12/98
Well ID: 46BR	Field Personnel: AM, BA	

Parameter	6	7	8	9	10	11
Time (min.)	1650					
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH	11.60					
Temperature (°C)	16.6					
Conductivity (μmhos/cm)	1.21					
Dissolved Oxygen (mg/L)	0.83					
Turbidity (NTU)	16					
Eh (mv)	-51.6					

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 47BR WELL LOCK STATUS: LOCKED
WELL CONDITION: GOOD WEATHER: OVERCAST, 75° scatter rain

GAUGE DATE: 10/8/98 GAUGE TIME: 1005
SOUNDING METHOD: Enter phase probe / Slope Indicator MEASUREMENT REF: TOP OF Inner Casing
STICK UP DOWN (ft): WELL DIAMETER (in.): 4"

PURGE DATE: 10/8/98 PURGE TIME: 1025
PURGE METHOD: LOW FLOW FIELD PERSONNEL: SAP/BA
AMBIENT AIR VOCs (ppm) Start: 0 End: WELL MOUTH VOCs (ppm) Start: 24.0 End:

A. TOTAL WELL DEPTH (ft): 18 E. CASING VOLUME/FT (GAL): 0.65
B. OPEN INTERVAL (ft): 15 F. CASING VOLUME (GAL) (D*E): 5.56
C. DEPTH TO WATER (ft): 8.45 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 8.34
D. H₂O COLUMN(ft) (A-B-C): 8.55

Parameter	Beginning	1	2	3	4	5
Time (min)	1025	1035	1040	1045	1050	1055
Depth to Water (ft)	8.45	13.9	13.9	13.72	13.55	13.42
Purge Rate (L/min)	1 gpm	0.3	0.3	0.3	0.3	0.3
Volume Purged (L)		—	1.5	3.0	4.5	6.0
pH		6.25	6.30	6.31	6.31	6.31
Temperature (°C)		13.4	18.4	18.5	18.6	18.7
Conductivity (µmhos/cm)	Fast	0.530	0.528	0.527	0.526	0.526
Dissolved Oxygen (mg/L)	Purge	0.85	0.85	0.87	0.86	0.90
Turbidity (NTU)		34	42	60	78	83
Eh (mv)		-114.2	-127.6	-133.6	-140.4	-142.8

TOTAL VOLUME WATER PURGED: 10 GAL + (36.6 LITERS * 0.264 GAL/LITER) = 19.67 GAL

SAMPLERS: SAP/BA SAMPLING TIME (START/END): 1211/1230

SAMPLING DATE: 10/2/98 DECONTAMINATION FLUIDS USED: DI H₂O, Methanol

SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: HCl, H₂SO₄

SAMPLE BOTTLE IDs: 47BR-100898

SAMPLE PARAMETERS: VOC + 10, DISSOLVED METALS, SULFIDE, METHANE, ALKALINITY

COMMENTS AND OBSERVATIONS: Purge water containerized and disposed of at Treatment plant (20 gal).

PUMP #: F
LEVEL: 15 FT

ODOR: smells like hydrocarbons

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/8/98
Well ID: 117B ₂	Field Personnel: BA/SAP	

Parameter	6	7	8	9	10	11
Time (min.)	1100	1105	1110	* 1115	1120	1125
Depth to Water (ft)	13.30	13.15	13.72	13.72	13.72	14.00
Purge Rate (L/min)	0.3	0.3	0.3	0.3	0.3	0.3
Volume Purged (L)	0.3 7.5	9.0	10.5	12.0	13.5	15.0
pH	6.31	6.30	6.30	6.27	6.34	6.34
Temperature (°C)	18.8	18.9	19.2	20.8	20.7	20.3
Conductivity (µmhos/cm)	0.523	0.524	0.522	0.506	0.506	0.499
Dissolved Oxygen (mg/L)	0.89	0.77	0.81	0.72	0.53	0.66
Turbidity (NTU)	77	72	74	41	35	28
Eh (mv)	-153.0	-154.2	-161.2	-159.2	-167.4	-171.4

Parameter	12	13	14	15	16	17
Time (min)	1130	1135 *	1140	1145	1150	1155
Depth to Water (ft)	14.00	14.30	14.28	14.24	14.82	14.82
Purge Rate (L/min)	0.3	0.3	0.3	0.3	0.3	0.3
Volume Purged (L)	16.5	18.0	19.5	21.0 20.3	22.5	24.0
pH	6.35	6.32	6.33	6.34	6.36	6.34
Temperature (°C)	20.3	20.3	20.3	20.3	20.2	19.8
Conductivity (µmhos/cm)	0.497	0.495	0.495	0.496	0.492	0.497
Dissolved Oxygen (mg/L)	0.43	0.58	0.48	0.37	0.51	0.42
Turbidity (NTU)	28	18	15	13	10	7
Eh (mv)	-174.0	-174.9 -169.9	-176.8	-181.4	-175.9	-189.0

COMMENTS AND OBSERVATIONS * Cleaned flow tube.

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/8/92
Well ID: 47BR	Field Personnel: SAP/BA	

Parameter	18	19	20	21	22	23
Time (min.)	1200	1205	1210	1211	1230	
Depth to Water (ft)	14.82	14.82	14.70	14.20	14.90	
Purge Rate (L/min)	0.3	0.3	0.3		0.3	
Volume Purged (L)	25.5	27.0	28.5		36.6	
pH	6.33	6.33	6.34		6.38	
Temperature (°C)	19.8	20.0	20.1		20.4	
Conductivity (μmhos/cm)	0.495	0.494	0.494		0.482	
Dissolved Oxygen (mg/L)	0.40	0.42	0.41		0.42	
Turbidity (NTU)	5	4	3		2	
Eh (mv)	-191.0	-190.2	-189.4		-185.4	

Parameter	24	25	26	27	28	29
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____

86/13



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 4" BR WELL LOCK STATUS: UNLOCKED
WELL CONDITION: OK WEATHER: DRIZZLE, 60's

GAUGE DATE: N/A GAUGE TIME: N/A
SOUNDING METHOD: N/A MEASUREMENT REF: N/A
STICK UP/DOWN (ft): N/A WELL DIAMETER (in.): 4"

PURGE DATE: N/A PURGE TIME: N/A
PURGE METHOD: EXTRACTION WELL FIELD PERSONNEL: AM/KS
AMBIENT AIR VOCs (ppm) Start: End: WELL MOUTH VOCs (ppm) Start: End:

- A. TOTAL WELL DEPTH (ft): 100
- B. OPEN INTERVAL (ft): 18
- C. DEPTH TO WATER (ft): N/A
- D. H₂O COLUMN(ft) (A-B-C): N/A
- E. CASING VOLUME/FT (GAL): 0.65
- F. CASING VOLUME (GAL) (D*E): N/A
- G. 1.5 CASING VOLUMES (GAL) (F*1.5): N/A

Parameter	Beginning	1	2	3	4	5
Time (min)	0855	0912				
Depth to Water (ft)	N/A	N/A				
Purge Rate (L/min)	N/A					
Volume Purged (L)	N/A					
pH	6.02	6.04				
Temperature (°C)	15.1	14.9				
Conductivity (µmhos/cm)	0.289	0.293				
Dissolved Oxygen (mg/L)	2.26	2.30				
Turbidity (NTU)	0	0				
Eh (mv)	N/A	N/A				

TOTAL VOLUME WATER PURGED: N/A GAL + (N/A LITERS * 0.264 GAL/LITER) = N/A GAL
SAMPLERS: AM/KS SAMPLING TIME (START/END): 0900 - 0910
SAMPLING DATE: 10/9/98 DECONTAMINATION FLUIDS USED: DEP / METHANOL
SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: HCL, HNO₃, H₂SO₄, H₂CO₃
SAMPLE BOTTLE IDs: 48BR-100998
SAMPLE PARAMETERS:
COMMENTS AND OBSERVATIONS: EXTRACTION WELL

PUMP #: N/A
LEVEL: N/A

ODOR:

7/15

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 49BR WELL LOCK STATUS: locked
WELL CONDITION: good WEATHER: cloudy 65°
GAUGE DATE: 10/12/98 GAUGE TIME: 15:00
SOUNDING METHOD: water level meter MEASUREMENT REF: top steel casing
STICK UP/DOWN (ft): Flush mount 2 1/2" below grade WELL DIAMETER (in.): 4"
PURGE DATE: 10/12/98 PURGE TIME: 15:11
PURGE METHOD: low flow fast purge FIELD PERSONNEL: M. Goldberg / M. Eder / B. Allen
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm) Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 60 E. CASING VOLUME/FT (GAL): 0.65
B. OPEN INTERVAL (ft): 18 F. CASING VOLUME (GAL) (D*E): 25.02
C. DEPTH TO WATER (ft): 6.59 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 37.58
D. H₂O COLUMN(ft) (A-B-C): 35.41 ~38 gal.

Parameter	Beginning	1	2	3	4	5
Time (min)	1511	1549	1554	1559	1604	1609
Depth to Water (ft)	6.59	8.42	7.85	7.65	7.29	7.21
Purge Rate (L/min)	4 liters/min	4.0 L/min	0.5	0.5	0.5	0.5
Volume Purged (L)	or 1 gal/min	38 gal		5.0	7.5	10.0
pH				6.57	6.98	7.02
Temperature (°C)				19.0	19.0	19.0
Conductivity (µmhos/cm)				0.268	0.252	0.250
Dissolved Oxygen (mg/L)				0.01	0.12	0.22
Turbidity (NTU)				10	2	2
Eh (mv)				49.7	61.5	33.4

TOTAL VOLUME WATER PURGED: 38 GAL + (42.6 LITERS * 0.264 GAL/LITER) = 150.46 GAL
SAMPLERS: BDA/MB/MS SAMPLING TIME (START/END): 1709-1723
SAMPLING DATE: 10/12/98 DECONTAMINATION FLUIDS USED: Methanol/DI H₂O
SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: HgCl₂, HCL, HNO₃, H₂SO₄, NaOH, ZnAc
SAMPLE BOTTLE IDs: 49BR-101298
SAMPLE PARAMETERS: VOC, TDS, Alkalinity, Diss Ammonia, DOC, Sulfide, Methane, Diss. Metals, Energy, Anions
COMMENTS AND OBSERVATIONS: NO readings at 1554 b/c we needed to adjust our equipment, pump at 42 feet.

PUMP #: D
LEVEL: 42 ft.

ODOR: NO NE

50
30
50

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/29/8
Well ID: 49BR-	Field Personnel: B. Allen / M. Bodey / M. Goldberg	

Parameter	6	7	8	9	10	11
Time (min.)	1614	1619	1624	1629	1634	1639
Depth to Water (ft)	7.11	6.92	6.89	8.88	6.91	6.91
Purge Rate (L/min)	0.5	0.5	0.5	0.5	0.5	0.5
Volume Purged (L)	12.5	15.0	17.5	20.0	22.5	25.0
pH	7.05	7.12	7.13	7.15	7.17	7.18
Temperature (°C)	19.0	19.1	19.2	19.0	19.1	19.1
Conductivity (µmhos/cm)	0.246	0.243	0.243	0.243	0.242	0.242
Dissolved Oxygen (mg/L)	0.22	0.20	0.22	0.23	0.22	0.22
Turbidity (NTU)	2	1	1	1	1	2
Eh (mv)	14.5	2.0	-2.9	-5.5	-9.8	-17.0

Parameter	12	13	14	15	16	17
Time (min)	1644	1649	1654	1659	1704	1709
Depth to Water (ft)	6.91	6.91	6.91	6.92	6.92	Sample taken
Purge Rate (L/min)	0.5	0.5	0.5	0.5	0.5	taken
Volume Purged (L)	27.5	30.0	32.5	35.0	37.5	
pH	7.19	7.20	7.20	7.21	7.21	
Temperature (°C)	19.2	19.2	19.2	19.2	19.2	
Conductivity (µmhos/cm)	0.241	0.241	0.241	0.241	0.241	
Dissolved Oxygen (mg/L)	0.24	0.24	0.25	0.25	0.26	
Turbidity (NTU)	2	2	2	2	2	
Eh (mv)	-27.2	-36.8	-41.2	-45.1	-48.6	

COMMENTS AND OBSERVATIONS Sample taken at 1709.

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/2/98
Well ID: 49BR-101218	Field Personnel: M. Butler / B. Allen / M. Goldberg	

Post sample.

Parameter	18	19	20	21	22	23
Time (min.)	17.23					
Depth to Water (ft)	8.00					
Purge Rate (L/min)	0.3					
Volume Purged (L)	42.6					
pH	7.19					
Temperature (°C)	19.0					
Conductivity (µmhos/cm)	243					
Dissolved Oxygen (mg/L)	0.19					
Turbidity (NTU)	9					
Eh (mv)	-39.9					

Parameter	24	25	26	27	28	29
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (µmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS _____

10/11

Page 1 of 2



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
 WELL I.D.: 50BR WELL LOCK STATUS: locked
 WELL CONDITION: Good WEATHER: Cloudy, 60s, Vct
 GAUGE DATE: 101498 GAUGE TIME: 844
 SOUNDING METHOD: water levelmeter MEASUREMENT REF: Top of well casing
 STICK UP DOWN (ft): 4 feet WELL DIAMETER (in.): 4"
 PURGE DATE: 101498 PURGE TIME: 850
 PURGE METHOD: low flow FIELD PERSONNEL: B. Parnell / A. Winkler / M. B.
 AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm): Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 80 E. CASING VOLUME/FT (GAL): 0.65
 B. OPEN INTERVAL (ft): 20 F. CASING VOLUME (GAL) (D*E): 26.36
 C. DEPTH TO WATER (ft): 19.45 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 39.54
 D. H₂O COLUMN (ft) (A-B-C): 40.55 ~40

Parameter	Beginning	1	2	3	4	5
Time (min)	850	930	935	940	945	950
Depth to Water (ft)	19.45	18.97	19.61	19.61	19.62	19.62
Purge Rate (L/min)	1 gallon/min	0.2	0.2	0.2	0.2	0.2
Volume Purged (L)	40 gallons	1.0	2.0	3.0	4.0	5.0
pH		6.19	6.23	6.29	6.34	6.39
Temperature (°C)		13.1	13.1	13.2	13.2	13.2
Conductivity (µmhos/cm)		0.320	0.318	0.314	0.311	0.307
Dissolved Oxygen (mg/L)		0.42	0.40	0.43	0.49	0.53
Turbidity (NTU)		-2	-2	-2	-2	-2
Eh (mv)		-6.0	-8.4	-12.6	-14.0	-15.0

TOTAL VOLUME WATER PURGED: 40 GAL + (36 LITERS * 0.264 GAL/LITER) = 49.5 GAL
 SAMPLERS: MBAWIDP SAMPLING TIME (START/END): 954 / 1029
 SAMPLING DATE: 101498 DECONTAMINATION FLUIDS USED: DI Water / Methanol
 SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: 1+Cl, HNO₃, H₂Cl₂, ZnAc₂, N-OH, H₂SO₄
 SAMPLE BOTTLE IDs: 50BR-101498 Dissolved Ammonia
 SAMPLE PARAMETERS: VOC, Methane, TDS, Sulfides, DOC, Dissolved Metals, Alkalinity, pH
 COMMENTS AND OBSERVATIONS: Turbidity reading negative numbers, but sample clear.

PUMP #: C
 LEVEL: 50.5

ODOR: None

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/14/99
Well ID: 50BR-101498	Field Personnel: Winkler, Parrella, BAKER	

Post Sample

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μ mhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 51 BR WELL LOCK STATUS: LOCKED
WELL CONDITION: GOOD WEATHER: OVERCAST, 65°
GAUGE DATE: 10/7/98 GAUGE TIME: 1319
SOUNDING METHOD: Slope Indicator MEASUREMENT REF: Top of inner casing
STICK UP/DOWN (ft): 4" WELL DIAMETER (in.): 4"
PURGE DATE: 10/7/98 PURGE TIME: 1329
PURGE METHOD: FAST PURGE/LOW FLOW FIELD PERSONNEL: SAP/BA
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm): Start: 0.3 End: 0
A. TOTAL WELL DEPTH (ft): 96 E. CASING VOLUME/FT (GAL): 0.65
B. OPEN INTERVAL (ft): 10 F. CASING VOLUME (GAL) (D*E): 44.36
C. DEPTH TO WATER (ft): 17.75 G. 1.5 CASING VOLUMES (GAL) (F*1.5): 66.54
D. H₂O COLUMN(ft) (A-B-C): 68.25

Parameter	Beginning	1	2	3	4	5
Time (min)	1329	1357	1402	1407	1412	1417
Depth to Water (ft)	17.75	18.25	18.25	18.20	18.20	18.20
Purge Rate (L/min)	2 gpm	0.3	0.3	0.3	0.3	0.3
Volume Purged (L)	60 gal	—	1.5	3.0	4.5	6.0
pH		7.12	7.24	7.37	7.44	7.49
Temperature (°C)	Fast	13.9	14.1	14.6	15.0	15.8
Conductivity (µmhos/cm)		0.263	0.261	0.259	0.257	0.253
Dissolved Oxygen (mg/L)	Purge	0.86	0.89	0.99	0.91	0.85
Turbidity (NTU)		5	3	2	2	3
Eh (mv)		6.61	10.6	-11.6	-20.0	-36.2

TOTAL VOLUME WATER PURGED: 60 GAL + (27 LITERS * 0.264 GAL/LITER) = 67.13 GAL
SAMPLERS: SAP/BA SAMPLING TIME (START/END): 1443 → 1528
SAMPLING DATE: 10/7/98 DECONTAMINATION FLUIDS USED: HCL, DI H₂O, methanol
SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: HCL, HNO₃, H₂SO₄
SAMPLE BOTTLE IDs: 51BR-100798 MS/MSD / DUP1-100798
SAMPLE PARAMETERS: VOC + 10, Dissolved metals, Dissolved ammonia, DOC, TDS, Sulfide, Methane
COMMENTS AND OBSERVATIONS: Started pump at 20 ft then lowered to 30 ft

Purged water was contained and disposed of at Treatment plant.
PUMP #: E ODOR:
LEVEL: 30 ft

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/7/92
Well ID: <u>S1BR</u>	Field Personnel: <u>STP/SA</u>	

Parameter	6	7	8	9	10	11
Time (min.)	1422	1427	1432	1437	1442	1443
Depth to Water (ft)	18.20	18.20	18.20	18.20	18.20	
Purge Rate (L/min)	0.3	0.3	0.3	0.3	0.3	
Volume Purged (L)	7.5	9.0	10.5	12.0	13.5	
pH	7.53	7.57	7.60	7.68	7.73	
Temperature (°C)	16.1	15.8	15.8	16.3	16.7	
Conductivity (μmhos/cm)	0.252	0.254	0.254	0.255	0.254	
Dissolved Oxygen (mg/L)	0.83	0.86	0.83	0.80	0.80	
Turbidity (NTU)	3	3	3	3	3	
Eh (mv)	-44.4	-55.6	-64.6	-64.8	-62.4	

Parameter	12	13	14	15	16	17
Time (min)	1528					
Depth to Water (ft)	18.28					
Purge Rate (L/min)	0.3					
Volume Purged (L)	²⁷ 13.5					
pH	7.80					
Temperature (°C)	16.7					
Conductivity (μmhos/cm)	0.262					
Dissolved Oxygen (mg/L)	0.86					
Turbidity (NTU)	6					
Eh (mv)	36.6					

COMMENTS AND OBSERVATIONS _____

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 11-MW-1 WELL LOCK STATUS: NOT locked
WELL CONDITION: good WEATHER: cloudy at 60°F
GAUGE DATE: 100598 GAUGE TIME: 1130
SOUNDING METHOD: water level meter MEASUREMENT REF: +0 c
STICK UP/DOWN (ft): up WELL DIAMETER (in.): 4"
PURGE DATE: 100598 PURGE TIME: 1140
PURGE METHOD: low FIELD PERSONNEL: *All (BA, BH)
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm): Start: 0.5 ppm End: 0.0 ppm

A. WELL DEPTH (ft): 22 D. WELL VOLUME/FT (GAL): 0.65
B. DEPTH TO WATER (ft): 16.91 9.6 (22) E. WELL VOLUME (GAL) (C*D): 3.302
C. H₂O COLUMN (ft) (A-B): 5.08 F. THREE WELL VOLUMES (GAL) (E*3): 9.906 gal
± 10 gal.

Parameter	Beginning	1	2	3	4	5
Time (min)	1140	1145	1150	1155	1200	1205
Depth to Water (ft)	16.91	16.88	17.01	17.17	17.02	17.03
Purge Rate (L/min)	0.8 L/min	0.4 L/min	0.4 L/min	0.4 L/min	0.4	0.4
Volume Purged (L)		2.0 L	4.0 L	6.0 L	8.0 L	10.0 L
pH		5.25	5.23	5.27	5.28	5.29
Temperature (°C)		16.9	17.9	18.7	18.5	19.0
Conductivity (µmhos/cm)		0.160	0.122	0.120	0.122	0.123
Dissolved Oxygen (mg/L)		2.68	2.36	2.34	2.07	1.98
Turbidity (NTU)		330	495	532	277	277
Eh (mv)		—	91.2	100.8	108.2	114.9

TOTAL VOLUME WATER PURGED: — GAL + (40 LITERS * 0.264 GAL/LITER) = 10.56 GAL
SAMPLERS: MB, RH, BH, BA, BH, AM, KS, SAP SAMPLING TIME (START/END): 1330/1410
SAMPLING DATE: 100598 DECONTAMINATION FLUIDS USED: methanol, DI,
SAMPLE TYPE: CAHAB SAMPLE PRESERVATIVES: HCL H₂SO₄ HNO₃
SAMPLE BOTTLE IDs: 11mw1-100598
SAMPLE PARAMETERS: VOC, IDS, Inorg. Anions, Dis. metals, DOC, Alkalinity, Sulfide, Methane
COMMENTS AND OBSERVATIONS: NO ODOR - START AT ≈ 18 feet tubing or 18 ft well depth.
went to 2 hrs, to get Turbidity below 10 and if never did.

PUMP #: D
LEVEL: 18 feet.

ODOR: NONE

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 100598
Well ID: 11mw1	Field Personnel: AL	

Parameter	6	7	8	9	10	11
Time (min.)	1210	1215	1220	1225	1230	1235
Depth to Water (ft)	17.05	17.12	17.08	17.07	17.07	17.07
Purge Rate (L/min)	0.4	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)	12.0	14.0	16.0	18.0	20.0	22.0
pH	5.29	5.25	5.21	5.21	5.20	5.20
Temperature (°C)	19.4	20.0	20.0	20.04	20.6	20.9
Conductivity (µmhos/cm)	0.124	0.123	0.125	0.120	0.128	0.120
Dissolved Oxygen (mg/L)	2.04	1.97	1.91	1.90	1.96	1.87
Turbidity (NTU)	270	150	173	243	179	139
Eh (mv)	119.6	131.8	131.8	130.6	130.2	131.4

Parameter	12	13	14	15	16	17
Time (min)	1240	1245	1250	1255	1300	1305
Depth to Water (ft)	17.07	17.06	17.07	17.07	17.07	17.07
Purge Rate (L/min)	.4	.4	.4	.4	.4	.4
Volume Purged (L)	24.0	26.0	28.0	30.0	32.0	34.0
pH	5.20	5.19	5.19	5.18	5.18	5.17
Temperature (°C)	21.1	21.3	21.3	21.4	21.5	21.6
Conductivity (µmhos/cm)	.119	.119	.119	.119	.118	.119
Dissolved Oxygen (mg/L)	1.84	1.86	1.67	1.96	1.86	1.94
Turbidity (NTU)	99	80	58	38	34	24
Eh (mv)	133.8	126.6	133.4	136.8	128.0	136.2

COMMENTS AND OBSERVATIONS

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/5/98
Well ID: 11AW1	Field Personnel: ALI	

Parameter	18	19	20	21	22	23
Time (min.)	1310	1315	1320	1410		
Depth to Water (ft)	17.06	17.07	17.07			
Purge Rate (L/min)	.4	.4	.4			
Volume Purged (L)	36.0	38.0	40.0			
pH	5.16	5.16	5.16	5.07		
Temperature (°C)	21.8	21.7	21.9	21.7		
Conductivity (μmhos/cm)	.118	.118	.118	.123		
Dissolved Oxygen (mg/L)	1.99	1.81	1.94	2.84		
Turbidity (NTU)	18	20	16	16		
Eh (mv)	139	138.8	141.2	125.8		

Parameter	24	25	26	27	28	29
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 35-MW-1 WELL LOCK STATUS: locked
WELL CONDITION: good (recently been regraded) WEATHER: cloudy 65°-70°
GAUGE DATE: 10/2/98 GAUGE TIME: 1150
SOUNDING METHOD: water level meter MEASUREMENT REF: top of PVC casing
STICK UP/DOWN (ft): up by 2ft 7in. WELL DIAMETER (in.): 4"
PURGE DATE: 10/2/98 PURGE TIME: 1204
PURGE METHOD: low flow FIELD PERSONNEL: B. Allen M. Baden
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm) Start: 0 End: 0

A. WELL DEPTH (ft): 25 D. WELL VOLUME/FT (GAL): 0.65
B. DEPTH TO WATER (ft): 17.5 ~~16.6~~ E. WELL VOLUME (GAL) (C*D): 4.88
C. H₂O COLUMN (ft) (A-B): 7.5 F. THREE WELL VOLUMES (GAL) (E*3): 14.625

Parameter	Beginning	1	2	3	4	5
Time (min)	1204	1214	1219	1224	1229	1234
Depth to Water (ft)	17.50	18.01	18.11	18.12	18.12	18.45
Purge Rate (L/min)	0.4	0.4	0.4	0.4	0.4	0.5
Volume Purged (L)	16.0 <u>14.0</u>	6.0	8.0	10.0	12.0	12.05
pH		5.43	5.41	5.42	5.41	5.39
Temperature (°C)		16.1	16.2	16.5	17.6	17.9
Conductivity (µmhos/cm)		0.338	0.338	0.337	0.336	0.332
Dissolved Oxygen (mg/L)		2.76	2.80	2.30	2.12	2.71
Turbidity (NTU)		48	42	45	45	55
Eh (mv)		201.6	212.1	215.5	217.2	220.7

TOTAL VOLUME WATER PURGED: 1 GAL + (37.5 LITERS * 0.264 GAL/LITER) = 10.9 GAL
SAMPLERS: BDA/MB SAMPLING TIME (START/END): 1304/1329
SAMPLING DATE: 10/2/98 DECONTAMINATION FLUIDS USED: methanol / D5 H₂O
SAMPLE TYPE: GRA SAMPLE PRESERVATIVES: HgCl₂, HCl, H₂SO₄, HNO₃, NaOH, ZnAc
SAMPLE BOTTLE IDS: 35-MW-1-101298
SAMPLE PARAMETERS: Pesticides, Trace metals, Methane, DOC, DOC-10, Alkalinity, Sulfides, Energy, Anions, Diss. Metals, TDS, Dissol. Ammonia
COMMENTS AND OBSERVATIONS: changed out water in flow thru cell at 1234.
NO ODORS, used ~25 feet of tubing and pump at ~20 foot level.

PUMP #: C
LEVEL: 20 feet

ODOR: NONE

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/298
Well ID: 35mw-1	Field Personnel: Bethany Allen Melissa Bader	

Parameter	6	7	8	9	10	11
Time (min.)	1239	1244	1249	1254	1259	1304
Depth to Water (ft)	18.61	18.70	18.76	18.79	18.84	sample taken
Purge Rate (L/min)	0.5	0.5	0.5	0.5	0.5	
Volume Purged (L)	15.0	17.5	20.0	22.5	25.0	
pH	5.40	5.39	5.39	5.39	5.38	
Temperature (°C)	17.9	18.0	18.1	18.2	18.0	
Conductivity (μmhos/cm)	0.332	0.331	0.331	0.330	0.339	
Dissolved Oxygen (mg/L)	2.71	2.62	2.47	2.31	2.99	
Turbidity (NTU)	53	42	42	49	87	
Eh (mv)	222.6	225.4	227.6	228.6	230.4	

Post Sample

Parameter	12	13	14	15	16	17
Time (min)	1329					
Depth to Water (ft)	20.81					
Purge Rate (L/min)	0.5					
Volume Purged (L)	37.5					
pH	5.41					
Temperature (°C)	16.8					
Conductivity (μmhos/cm)	0.345					
Dissolved Oxygen (mg/L)	1.23					
Turbidity (NTU)	91					
Eh (mv)	243.1					

COMMENTS AND OBSERVATIONS Cleaned flow thru cell at 1257. Turbidity high due to regrouting in area around well, RATH OFS us to take sample at 1304

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 35-MW-2 WELL LOCK STATUS: unlocked
WELL CONDITION: good WEATHER: cloudy 55°-60°
GAUGE DATE: 101298 GAUGE TIME: 0934
SOUNDING METHOD: water level meter MEASUREMENT REF: top of well casing
STICK UP/DOWN (ft): stick up by 2 feet 3 inches WELL DIAMETER (in.): 4"
PURGE DATE: 101298 PURGE TIME: 0957
PURGE METHOD: low flow FIELD PERSONNEL: B. Allen + M. Baden
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm) Start: 0 End: 0

A. WELL DEPTH (ft): 22 D. WELL VOLUME/FT (GAL): 0.65
B. DEPTH TO WATER (ft): 12.93 E. WELL VOLUME (GAL) (C*D): 5.90
C. H₂O COLUMN (ft) (A-B): 9.07 F. THREE WELL VOLUMES (GAL) (E*3): 17.68

Parameter	Beginning	1	2	3	4	5
Time (min)	0957	1002	1007	1012	1017	1022
Depth to Water (ft)	12.93	13.09	13.35	13.37	13.17	12.84
Purge Rate (L/min)	0.4	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)		2.0	4.0	6.0	8.0	10.0
pH		4.38	4.96	4.67	4.58	4.54
Temperature (°C)		15.8	16.2	16.0	15.8	15.8
Conductivity (µmhos/cm)		0.321	.292	.290	.291	.288
Dissolved Oxygen (mg/L)		3.10	3.08	2.29	1.98	1.88
Turbidity (NTU)		18	25	42	30	15
Eh (mv)		170.1	192.1	198.6	203.4	206.3

TOTAL VOLUME WATER PURGED: 0.5 GAL + (31.4 LITERS * 0.264 GAL/LITER) = 8.77 GAL
SAMPLERS: BDA + mB SAMPLING TIME (START/END): 1055/1116
SAMPLING DATE: 101298 DECONTAMINATION FLUIDS USED: Methanol / DI Water
SAMPLE TYPE: GRABS SAMPLE PRESERVATIVES: HgCl₂, HNO₃, As₂O₃, HCl, ZnAc₂, H₂O₂
SAMPLE BOTTLE IDs: 35mw2-101298 (For EBS, samples were taken for Pesticides + TAL metals w/ ms/1)
SAMPLE PARAMETERS: VOC, TIO, TDS, DOC, DISS. AMMONIA, DISS. METALS, INORG. AMMONIA, SULFIDES, METHANE, ALKALINITY
COMMENTS AND OBSERVATIONS:

DUPLICATE DUP.1 FOR PEST/TAL METALS ONLY

PUMP #: B
LEVEL: 17 feet

ODOR: NONE

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/2/98
Well ID: 35MW-2-101298	Field Personnel: B. Allen & M. Bader	

Parameter	6	7	8	9	10	11
Time (min.)	1027	1032	1037	1042	1047	1052
Depth to Water (ft)	12.84	12.80	12.81	12.80	12.79	12.78
Purge Rate (L/min)	0.4	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)	12.0	14.0	16.0	18.0	20.0	22.0
pH	4.65	4.71	4.72	4.74	4.88	4.96
Temperature (°C)	15.9	15.9	16.0	16.1	16.2	16.2
Conductivity (µmhos/cm)	0.289	0.289	0.289	0.288	0.287	0.287
Dissolved Oxygen (mg/L)	1.94	1.50	1.57	2.04	1.88	1.87
Turbidity (NTU)	13	9	7	6	4	4
Eh (mv)	209.4	211.0	212.4	214.3	217.5	218.8

Post sample

Parameter	12	13	14	15	16	17
Time (min)	1116					
Depth to Water (ft)	13.36					
Purge Rate (L/min)	0.4					
Volume Purged (L)	31.4					
pH	5.43					
Temperature (°C)	15.0					
Conductivity (µmhos/cm)	0.284					
Dissolved Oxygen (mg/L)	2.09					
Turbidity (NTU)	36					
Eh (mv)	224.7					

COMMENTS AND OBSERVATIONS

4/657/1,517



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
 WELL I.D.: BRP-1 WELL LOCK STATUS: glove - EW
 WELL CONDITION: good WEATHER: clearing, sun
 GAUGE DATE: 10/13/98 GAUGE TIME: 1310 EW
 SOUNDING METHOD: slope indicator MEASUREMENT REF: TOC - well casing
 STICK UP/DOWN (ft): EW WELL DIAMETER (in.): 6"
 PURGE DATE: 10/13/98 PURGE TIME: Fast 1323-1345
 PURGE METHOD: Fast / Low Purge FIELD PERSONNEL: Andy McBride / Brian Anderson
 AMBIENT AIR VOCs (ppm) Start: 0.0 End: 0.0 WELL MOUTH VOCs (ppm): Start: 0.0 End: 0.0

- A. TOTAL WELL DEPTH (ft): 60
- B. OPEN INTERVAL (ft): 39.5
- C. DEPTH TO WATER (ft): 5.23
- D. H₂O COLUMN(ft) (A-B-C): 15.27
- E. CASING VOLUME/FT (GAL): 1.5
- F. CASING VOLUME (GAL) (D*E): 22.905
- G. 1.5 CASING VOLUMES (GAL) (F*1.5): 34.37

Parameter	Beginning	1	2	3	4	5
Time (min)	1323	1350	1355	1400	1405	1430
Depth to Water (ft)		5.31	5.31	5.31	5.31	5.34
Purge Rate (L/min)	FAST Purge	0.2	0.2	0.2	0.2	
Volume Purged (L)	2.2 gal	0.2	1.2	2.2	3.2	
pH		6.16	6.10	6.05	6.03	6.18
Temperature (°C)		18.2	18.2	18.3	18.4	18.6
Conductivity (µmhos/cm)		.569	.568	.568	.566	.567
Dissolved Oxygen (mg/L)		0.56	0.67	0.70	0.65	0.87
Turbidity (NTU)		3	4	4	4	3
Eh (mv)		-91.6	-111.4	-115.2	-120.1	-117.8

TOTAL VOLUME WATER PURGED: 43 GAL + (3.2 LITERS * 0.264 GAL/LITER) = 44 GAL
 SAMPLERS: AM, BA SAMPLING TIME (START/END): 1407
 SAMPLING DATE: 10/13/98 DECONTAMINATION FLUIDS USED: n/a
 SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: HCl, H₂SO₄, HNO₃
 SAMPLE BOTTLE IDs: BRP-1-101398
 SAMPLE PARAMETERS: VOC, TDS, DO, DISS. AMMONIA, DISS. METALS, INORGANIC ANIONS, METHANE, SULFIDE, ALKALINITY
 COMMENTS AND OBSERVATIONS:

PUMP #: -(EW) ODOOR: slight petrochem like.
 LEVEL: -

39,076 / 59,000



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: BRP-2 WELL LOCK STATUS: UNLOCKED
WELL CONDITION: O.K. WEATHER: CLOUDY, 60's
GAUGE DATE: 10/9/98 GAUGE TIME: 1120
SOUNDING METHOD: T.O.C. MEASUREMENT REF: T.O.C.
STICK UP/DOWN (ft): 1.5 FT WELL DIAMETER (in.): 6"
PURGE DATE: 10/9/98 PURGE TIME: 1125
PURGE METHOD: EXTRACTION WELL FIELD PERSONNEL: AM/KS
AMBIENT AIR VOCs (ppm) Start: 0.0 End: 0.0 WELL MOUTH VOCs (ppm): Start: 0.0 End: 3.4

A. TOTAL WELL DEPTH (ft): 47.1 E. CASING VOLUME/FT (GAL): 1.5
B. OPEN INTERVAL (ft): 20 F. CASING VOLUME (GAL) (D*E): N/A
C. DEPTH TO WATER (ft): 7.35 G. 1.5 CASING VOLUMES (GAL) (F*1.5): N/A
D. H₂O COLUMN(ft) (A-B-C):

Parameter	Beginning	1	2	3	4	5
Time (min)	1125	1130	1135	1140	1145	1150
Depth to Water (ft)	7.35	7.65	7.80	18.01	18.26	
Purge Rate (L/min)	N/A					→
Volume Purged (L)	N/A					→
pH	6.51	6.40	6.35	6.33	6.33	6.34
Temperature (°C)	15.6	15.5	15.5	15.5	15.5	15.5
Conductivity (μmhos/cm)	1.01	1.01	1.02	1.01	1.01	1.01
Dissolved Oxygen (mg/L)	1.47	1.24	0.13	0.06	0.01	0.01
Turbidity (NTU)	-10(?)	-10	-10	-10	-10	-10
Eh (mv)	N/A					→

TOTAL VOLUME WATER PURGED: N/A GAL + (N/A LITERS * 0.264 GAL/LITER) = N/A GAL
SAMPLERS: AM/KS SAMPLING TIME (START/END): 1240-1270
SAMPLING DATE: 10/9/98 DECONTAMINATION FLUIDS USED: DE/METANOL
SAMPLE TYPE: GAS SAMPLE PRESERVATIVES: HCL, HNO₃, H₂SO₄, HgCl₂
SAMPLE BOTTLE IDs: BRP-2 - 100998
SAMPLE PARAMETERS: LOC, TDS, DOC/DISS. AMMONIA, METHANE, SULFIDE, DISS. METALS, INORGANIC ANIONS
COMMENTS AND OBSERVATIONS: BRP-2 EXTRACTION WELL PURGED TO TREATMENT PLANT

PUMP #:
LEVEL:

ODOR:

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date:
Well ID:	Field Personnel:	

Parameter	6	7	8	9	10	11
Time (min.)	1159	1202	1205	1220		
Depth to Water (ft)	15.75	16.92	17.20	18.03		
Purge Rate (L/min)	N/A	N/A				
Volume Purged (L)	N/A	N/A				
pH	6.35	6.35	6.35	6.45		
Temperature (°C)	15.3	15.3	15.3	15.2		
Conductivity (μmhos/cm)	0.792	0.793	0.793	0.792		
Dissolved Oxygen (mg/L)	0.25	0.20	0.18	0.10		
Turbidity (NTU)	-10	-10	-10	-10		
Eh (mv)	N/A	N/A	N/A	N/A		

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS Pump TURNED OFF JUST PRIOR TO 1155 READING
RESAMPLED @ 1157

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

*Bethany Allen
Melissa Butler*

SITE NAME: NAWC TRENTON
WELL I.D.: BRP-3
WELL CONDITION: Good
GAUGE DATE: 100898
SOUNDING METHOD: water level meter
STICK UP/DOWN (ft): down

PROJECT NUMBER: 29600.43
WELL LOCK STATUS: locked
WEATHER: pouring rain 70°F
GAUGE TIME: 1345
MEASUREMENT REF: top of steel casing
WELL DIAMETER (in.): 6"

PURGE DATE: 100898
PURGE METHOD: fast purge / low flow
AMBIENT AIR VOCs (ppm) Start: 0 End: 0

PURGE TIME: 1358
FIELD PERSONNEL: B. Allen M. Butler
WELL MOUTH VOCs (ppm) Start: 0 End: 0

A. TOTAL WELL DEPTH (ft): 45
B. OPEN INTERVAL (ft): 20
C. DEPTH TO WATER (ft): 8.32
D. H₂O COLUMN(ft) (A-B-C): 16.68

E. CASING VOLUME/FT (GAL): 1.5
F. CASING VOLUME (GAL) (D*E): 25.02
G. 1.5 CASING VOLUMES (GAL) (F*1.5): 37.53
~ 38 gal.

Parameter	Beginning	1	2	3	4	5
Time (min)	1358	1436	1441	1446	1451	1456
Depth to Water (ft)	8.32	8.31	8.31	8.28	8.22	8.24
Purge Rate (L/min)	1 gpm	0.3	0.3	0.3	0.3	.3
Volume Purged (L)			1.5	3.0	4.5	6.0
pH			7.36	7.35	7.32	7.48
Temperature (°C)			17.4	18.0	18.2	18.4
Conductivity (µmhos/cm)			0.421	0.426	0.481	.482
Dissolved Oxygen (mg/L)			0.51	0.78	1.13	1.00
Turbidity (NTU)			59	280	279	285
Eh (mv)			-114.1	-114.6	-104.7	-103.3

TOTAL VOLUME WATER PURGED: 38 GAL + (16.5 LITERS * 0.264 GAL/LITER) = 86.54 GAL
SAMPLERS: BRA MB SAMPLING TIME (START/END): 1531
SAMPLING DATE: 100898 DECONTAMINATION FLUIDS USED: DI H₂O Methanol
SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: HCL, HNO₃, H₂SO₄, HCl
SAMPLE BOTTLE IDs: BRP3-100898

SAMPLE PARAMETERS: vol, sulfides, Methane, DO, Enorg. Anions, Dissolved Metals, Alkalinity, Diss. Ammonia, TDS

COMMENTS AND OBSERVATIONS: Foster Wheeler has regraded around this well +
Gravel like material surrounds it by 2 feet. There is
a lot of construction going on in the area + regrading of the area.
After 2 hours of purged water + no decrease in turbidity + ductosity.

ODOR - NONE
Pump - C

LEVEL - 15 feet

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 100898
Well ID: BRP3-100898	Field Personnel: BDA/MRB	

*change
7.20.16*

Parameter	6	7	8	9	10	11
Time (min.)	1501	1506	1511	1516	1521	1526
Depth to Water (ft)	8.26	8.21	8.21	8.21	8.21	8.21
Purge Rate (L/min)	0.3	0.3	0.3	0.3	.3	.3
Volume Purged (L)	7.5	9.0	10.5	12.0	13.5	15
pH	7.49	7.12	7.11	7.05	7.02	7.00
Temperature (°C)	18.5	19.0	19.0	19.0	19.0	19.0
Conductivity (μmhos/cm)	0.481	0.612	0.613	.613	.613	.614
Dissolved Oxygen (mg/L)	1.35	2.01	1.93	1.68	1.81	1.97
Turbidity (NTU)	296	242	247	239	230	242
Eh (mv)	-99.1	Broken Filter		-50	-62.4	-66

*Post
Sample*

Parameter	12	13	14	15	16	17
Time (min)	1531	1539				
Depth to Water (ft)	1 took	8.21				
Purge Rate (L/min)	sample	.3				
Volume Purged (L)		18.5				
pH		7.77				
Temperature (°C)		16.4				
Conductivity (μmhos/cm)		.475				
Dissolved Oxygen (mg/L)		.11				
Turbidity (NTU)		48				
Eh (mv)		-86.1				

COMMENTS AND OBSERVATIONS _____

575981

Melissa Dader
Michael Goldberg



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: WEST DITCH WELL WELL LOCK STATUS: N/A
WELL CONDITION: Good WEATHER: Sunny, 70s
GAUGE DATE: - GAUGE TIME: -
SOUNDING METHOD: - MEASUREMENT REF: -
STICK UP/DOWN (ft): - WELL DIAMETER (in.): -
PURGE DATE: - EW PURGE TIME: -
PURGE METHOD: - EW FIELD PERSONNEL: - MB/MG
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm): Start: 0 End: 0
A. TOTAL WELL DEPTH (ft): - E. CASING VOLUME/FT (GAL): -
B. OPEN INTERVAL (ft): - F. CASING VOLUME (GAL) (D*E): -
C. DEPTH TO WATER (ft): - G. 1.5 CASING VOLUMES (GAL) (F*1.5): -
D. H₂O COLUMN(ft) (A-B-C): -

P₈₅₊
Sample

Parameter	Beginning	1	2	3	4	5
Time (min)		1015	1050			
Depth to Water (ft)		NA	NA			
Purge Rate (L/min)		0.3	0.3			
Volume Purged (L)		NA	NA			
pH		6.10	6.72			
Temperature (°C)		15.5	15.7			
Conductivity (µmhos/cm)		1634	1566			
Dissolved Oxygen (mg/L)		2.14	2.07			
Turbidity (NTU)		1	9			
Eh (mv)		-42.2	-54.2			

TOTAL VOLUME WATER PURGED: - GAL + (- LITERS * 0.264 GAL/LITER) = - GAL
SAMPLERS: M. Goldberg, M.B.J. SAMPLING TIME (START/END): 1030/1050
SAMPLING DATE: 10/15/98 DECONTAMINATION FLUIDS USED: DI Water/Methanol
SAMPLE TYPE: Grub SAMPLE PRESERVATIVES: HCl, HNO₃, H₂SO₄, H₂O₂, NaOH, ZnAc
SAMPLE BOTTLE IDs: WD-101698
SAMPLE PARAMETERS: TDS, Methane, Sulfides, VOC-10, Alkalinity, DO, Diss. Lead, Heavy Metals
COMMENTS AND OBSERVATIONS: Chuck from EIT hooked up a sample port to get samples. Well was working, no need for purging. No place to sit

PUMP #: Extraction ODOR: None
LEVEL: Well

100/512

GONE



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME:	NAWC TRENTON	PROJECT NUMBER:	29600.43
WELL I.D.:	025	WELL LOCK STATUS:	
WELL CONDITION:		WEATHER:	
GAUGE DATE:		GAUGE TIME:	
SOUNDING METHOD:		MEASUREMENT REF:	
STICK UP/DOWN (ft):		WELL DIAMETER (in.):	4"
PURGE DATE:		PURGE TIME:	
PURGE METHOD:		FIELD PERSONNEL:	
AMBIENT AIR VOCs (ppm)	Start: End:	WELL MOUTH VOCs (ppm):	Start: End:
A. WELL DEPTH (ft):	8	D. WELL VOLUME/FT (GAL):	0.65
B. DEPTH TO WATER (ft):		E. WELL VOLUME (GAL) (C*D):	
C. H ₂ O COLUMN (ft) (A-B):		F. THREE WELL VOLUMES (GAL) (E*3):	

Parameter	Beginning	1	2	3	4	5
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (µmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

TOTAL VOLUME WATER PURGED: _____ GAL + (_____ LITERS * 0.264 GAL/LITER) = _____ GAL

SAMPLERS: _____ SAMPLING TIME (START/END): _____

SAMPLING DATE: _____ DECONTAMINATION FLUIDS USED: _____

SAMPLE TYPE: _____ SAMPLE PRESERVATIVES: _____

SAMPLE BOTTLE IDs: _____

SAMPLE PARAMETERS: _____

COMMENTS AND OBSERVATIONS: _____

PUMP #:
LEVEL:

ODOR:

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 12.5 WELL LOCK STATUS: good
WELL CONDITION: good WEATHER: overcast, 60°
GAUGE DATE: 10/7/98 GAUGE TIME: 0900
SOUNDING METHOD: Interface MEASUREMENT REF: TOC - Inner PVC
STICK UP/DOWN (ft): 4" WELL DIAMETER (in.): 4"
PURGE DATE: 10/07/98 PURGE TIME: 0916
PURGE METHOD: Low Flow FIELD PERSONNEL: BA, SAP
AMBIENT AIR VOCs (ppm) Start: 0.0 End: 0.0 WELL MOUTH VOCs (ppm): Start: 0.7 End: 0.0

A. WELL DEPTH (ft): 22.5 D. WELL VOLUME/FT (GAL): 0.65
B. DEPTH TO WATER (ft): 17.5 E. WELL VOLUME (GAL) (C*D): 3.25
C. H₂O COLUMN (ft) (A-B): 5.0 F. THREE WELL VOLUMES (GAL) (E*3): 9.75

Parameter	Beginning	1	2	3	4	5
Time (min)	0925	0930	0940	0945	0950	0955
Depth to Water (ft)	17.51	17.50	17.51	17.51	17.50	17.50
Purge Rate (L/min)	0.2	0.2	0.2	0.2	0.2	0.2
Volume Purged (L)	1.8	2.8	4.8	5.8	6.8	7.8
pH	5.79	5.76	6.01	5.88	6.00	6.01
Temperature (°C)	14.3	14.3	16.6	17.8	17.8	17.8
Conductivity (µmhos/cm)	.465	.463	.463	.467	.457	.456
Dissolved Oxygen (mg/L)	0.96	1.71	1.84	2.10	1.46	1.37
Turbidity (NTU)	-10 ^{4a}	-10 ^{4b}	2	2	1	1
Eh (mv)	91.8	62.8	28.4	24.0	25.0	23.8

TOTAL VOLUME WATER PURGED: — GAL + (14.8 LITERS * 0.264 GAL/LITER) = 3.91 GAL
SAMPLERS: BH, BA SAMPLING TIME (START/END): 1040 - 1100
SAMPLING DATE: 10/07/98 DECONTAMINATION FLUIDS USED: D1 / Methanol
SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: HCl, HgCl₂, H₂SO₄, HNO₃
SAMPLE BOTTLE IDs: 125-100798
SAMPLE PARAMETERS: VOCs, TDS, Methane, DOC, NH₄, Dissolved Metals, Inorganic Phosphorus, ALK, & Sulfate
COMMENTS AND OBSERVATIONS: *^a Problem with turbidity reading. *^b - recalibrate

Pump
F

PUMP #: 9717070
LEVEL: 19 feet.

ODOR: slight petroleum

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/7/98
Well ID: 12S	Field Personnel: BA, SAP	

Parameter	6	7	8	9	10	11
Time (min.)	1000	1005	1010	1015	1020	1025
Depth to Water (ft)	17.50	17.51	17.51	17.51	17.45	17.45
Purge Rate (L/min)	0.2	0.2	0.2	0.2	0.2	0.2
Volume Purged (L)	8.8	9.8	10.8	11.8	12.8	13.8
pH	6.02	6.01	6.04	6.05	6.04	6.03
Temperature (°C)	17.6	18.1	18.2	18.1	18.0	17.9
Conductivity (μmhos/cm)	.455	.450	.449	.450	.451	.451
Dissolved Oxygen (mg/L)	1.40	1.45	0.86	0.40	0.95	1.26
Turbidity (NTU)	1	1	1	1	1	1
Eh (mv)	18.0	-3.0	-3.0	-17.4	-19.6	-19.2

Post Sample

Parameter	12	13	14	15	16	17
Time (min)	1030	1035	1100			
Depth to Water (ft)	17.45	17.45	17.30			
Purge Rate (L/min)	0.1	0.1	-			
Volume Purged (L)	14.3	14.8				
pH	6.03	6.03	6.03			
Temperature (°C)	17.8	17.8	19.2			
Conductivity (μmhos/cm)	.452	.452	.439			
Dissolved Oxygen (mg/L)	0.96	0.63	2.92			
Turbidity (NTU)	1	1	1			
Eh (mv)	-19.8	-20.0	14.8			

COMMENTS AND OBSERVATIONS _____

Extraction Well



Michelle Rader
Bethany Allen

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
 WELL I.D.: 315 WELL LOCK STATUS: locked shut
 WELL CONDITION: GOOD WEATHER: overcast, rainy, 60's
 GAUGE DATE: 10/9/98 GAUGE TIME: 845
 SOUNDING METHOD: water level meter MEASUREMENT REF: top of well casing
 STICK UP/DOWN (ft): 1.82 feet - height of extraction well casing WELL DIAMETER (in.): 4"
 PURGE DATE: 10/9/98 PURGE TIME: 846
 PURGE METHOD: low flow FIELD PERSONNEL: B. Allen & M. Rader
 AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm): Start: 0 End: 0

A. WELL DEPTH (ft): 20 D. WELL VOLUME/FT (GAL): 0.65
 B. DEPTH TO WATER (ft): 2.5 E. WELL VOLUME (GAL) (C*D): 11.375
 C. H₂O COLUMN (ft) (A-B): 17.5 F. THREE WELL VOLUMES (GAL) (E*3): 17.055
 low flow

Parameter	Beginning	1	2	3	4	5
Time (min)	846	8.56	913	918	923	928
Depth to Water (ft)	-	-	-	-	-	-
Purge Rate (L/min)	1 gpm	.5/L/min	0.5	0.5	.5	.5
Volume Purged (L)	4 L/min		16 L/min	2.5	5.0	7.5
pH			6.53	6.66	6.60	6.61
Temperature (°C)			17.5	17.6	18.4	18.4
Conductivity (µmhos/cm)		307	.307	.301	.288	.288
Dissolved Oxygen (mg/L)			4.75	4.39	3.36	3.25
Turbidity (NTU)			not functioning		730	719
Eh (mv)			19.3	19.4	16.9	17.0

TOTAL VOLUME WATER PURGED: 17 GAL + (49.1 LITERS * 0.264 GAL/LITER) = 146.624 GAL
 SAMPLERS: B. Allen & M. Rader SAMPLING TIME (START/END): 1040 / 1110
 SAMPLING DATE: 10/09/98 DECONTAMINATION FLUIDS USED: 0.1L water / Methanol
 SAMPLE TYPE: Grab SAMPLE PRESERVATIVES: HCl, HNO₃, H₂SO₄, Zn, NaOH, H₂O₂
 SAMPLE BOTTLE IDs: 315-100998
 SAMPLE PARAMETERS: VOC, TDS, Methane, DOC, Dissolved Ammonia, Dissolved Metals, Inorganic Anions, AIA
 COMMENTS AND OBSERVATIONS: Depth to Water Probe Reading Could not be taken due to size of well & wires in there. Chooseto use depth reading from test sampler.

PUMP #: NA
LEVEL: NA

CDOR: None

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 100998
Well ID: 315-100998	Field Personnel: B. Allen + M. Bule	

Parameter	6	7	8	9	10	11
Time (min.)	933	938	943	948	953	956 958
Depth to Water (ft)	—	—	—	—	—	—
Purge Rate (L/min)	0.5	.5	0.5	.5	.5	.5
Volume Purged (L)	10.0	12.5	15.0	17.5	20	22.5
pH	6.67	6.69	6.70	6.60	6.68	6.68
Temperature (°C)	18.4	18.4	18.4	19.2	19.3	19.2
Conductivity (µmhos/cm)	.287	.287	.286	.281	.279	.279
Dissolved Oxygen (mg/L)	3.42	2.49	2.29	3.09	2.29	2.27
Turbidity (NTU)	682	663	603	370	363	339
Eh (mv)	16.0	15.4	15.0	14.9	16.6	17.7

Parameter	12	13	14	15	16	17
Time (min)	1003	1008	1013	1018	1023	1028
Depth to Water (ft)	—	—	—	—	—	—
Purge Rate (L/min)	0.5	.5	.5	.5	.5	ub. 15.3
Volume Purged (L)	25.0	27.5	30	32.5	35.0	37.5 36.5
pH	6.69	6.70	6.70	5.76	6.16	6.30
Temperature (°C)	19.2	19.0	19.0	19.4	19.2	19.0
Conductivity (µmhos/cm)	.279	.280	.280	.331	.315	.304
Dissolved Oxygen (mg/L)	2.28	2.20	2.19	2.76	1.74	1.29
Turbidity (NTU)	340	319	326	148	150	147
Eh (mv)	19.2	19.6	19.9	21.5	20.4	18.7

COMMENTS AND OBSERVATIONS 948 - cleaned flw through cell. 1018 After 16 was changed to mis function in LCD & cell was cleaned

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 100998
Well ID: 315-100988	Field Personnel: MB/BDA	

Parameter	18	19	20	21	22	23
Time (min.)	1033	1038	1110			
Depth to Water (ft)	—	—	—			
Purge Rate (L/min)	.3	.3	.3			
Volume Purged (L)	38.0	39.5	49.1			
pH	6.32	6.33	6.29			
Temperature (°C)	19.0	19.0	18.5			
Conductivity (μmhos/cm)	.303	.302	.305			
Dissolved Oxygen (mg/L)	1.34	1.29	1.57			
Turbidity (NTU)	145	145	121			
Eh (mv)	18.2	18.3	27.2			

Parameter	24	25	26	27	28	29
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS 2 hours since beginning purging
chose to sample.



FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 325 WELL LOCK STATUS: unlocked
WELL CONDITION: good WEATHER: Cloudy 60°F
GAUGE DATE: 101398 GAUGE TIME: 1106
SOUNDING METHOD: water level meter MEASUREMENT REF: top of PVC casing
STICK UP/DOWN (ft): flush mount WELL DIAMETER (in.): 4"
PURGE DATE: 101398 PURGE TIME: 1124
PURGE METHOD: low flow FIELD PERSONNEL: Jeffrey Allen
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm): Start: 0 End: 0

A. WELL DEPTH (ft): 14.8 D. WELL VOLUME/FT (GAL): 0.65
B. DEPTH TO WATER (ft): 8.59 E. WELL VOLUME (GAL) (C*D): 4.04
C. H₂O COLUMN (ft) (A-B): 6.21 F. THREE WELL VOLUMES (GAL) (E*3): 12.12
≈ 13.5 gal

Parameter	Beginning	1	2	3	4	5
Time (min)	1124	1134	1139	1144	1149	1154
Depth to Water (ft)	8.59	8.75	8.72	8.69	8.68	8.69
Purge Rate (L/min)	0.4	0.4	0.4	0.4	0.4	0.4
Volume Purged (L)		4.0	6.0	8.0	10.0	12.0
pH		6.18	6.18	6.18	6.18	6.18
Temperature (°C)		18.4	18.5	18.5	18.5	18.6
Conductivity (μmhos/cm)		0.439	0.440	0.443	0.443	0.443
Dissolved Oxygen (mg/L)		1.89	1.86	1.56	1.48	1.56
Turbidity (NTU)		7	7	6	6	6
Eh (mv)		122.9	126.1	126.9	126.0	124.9

TOTAL VOLUME WATER PURGED: 1 GAL + (32.8 LITERS * 0.264 GAL/LITER) = 8.66 GAL
SAMPLERS: BDA/mg SAMPLING TIME (START/END): 1200-1246
SAMPLING DATE: 101398 DECONTAMINATION FLUIDS USED: Y
SAMPLE TYPE: GRAB SAMPLE PRESERVATIVES: Methanol DI H₂O
SAMPLE BOTTLE IDs: 325-101398/325-101398 ms/msd/ur-2-101398 HgCl₂, HCl, ZnAc, H₂SO₄, NaOH, HNO₃
SAMPLE PARAMETERS: VOC + 10 by 8263, TDS, Methane, Sulfide, Alkalinity, Diss. Metals, Diss. Ammonia, Inorg. Ani.
COMMENTS AND OBSERVATIONS: Used Pump B and placed it approximately 10 feet down. NO ODOORS. NO PID readings.

PUMP # B
LEVEL: 9 feet or 10 feet

ODOR: NONE

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 101398
Well ID: 325-	Field Personnel: B. Allen / M. Goldberg	

lost sample

Parameter	6	7	8	9	10	11
Time (min.)	1159	1200	1246			
Depth to Water (ft)	8.69	<i>sample taken</i>	9.33			
Purge Rate (L/min)	0.4		0.4			
Volume Purged (L)	14.0		32.8			
pH	6.19		6.30			
Temperature (°C)	18.5		17.8			
Conductivity (μmhos/cm)	0.443		0.429			
Dissolved Oxygen (mg/L)	1.52		1.19			
Turbidity (NTU)	6		2			
Eh (mv)	122.3		145.8			

Parameter	12	13	14	15	16	17
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (μmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

COMMENTS AND OBSERVATIONS *ms/msd and Dup-2 taken*
Sample IDs were 325-101398ms/msd / 325-101398 / Dup-2-101398

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 37.5 WELL LOCK STATUS: Locked
WELL CONDITION: Good WEATHER: Sunny 65°-70°F
GAUGE DATE: 100598 GAUGE TIME: 1530
SOUNDING METHOD: water level meter MEASUREMENT REF: LOC
STICK UP/DOWN (ft): the flush mount WELL DIAMETER (in.): 4"
+ casing below grade
PURGE DATE: 100598 PURGE TIME: 1553
PURGE METHOD: low flow FIELD PERSONNEL: MB/BDA
AMBIENT AIR VOCs (ppm) Start: 0 End: 0 WELL MOUTH VOCs (ppm): Start: 0 End: 0

A. WELL DEPTH (ft): 16 D. WELL VOLUME/FT (GAL): 0.65 4.277
B. DEPTH TO WATER (ft): 9.42 10.42 6.58 E. WELL VOLUME (GAL) (C*D): 3.627 3.977 2.44
C. H₂O COLUMN (ft) (A-B): 5.58 6.58 4.58 F. THREE WELL VOLUMES (GAL) (E*3): 10.88 8.93 7.32
2.44 gal ≈ 9 gal.

Parameter	Beginning	1	2	3	4	5
Time (min)	1553	1558	1603	1608	1613	1618
Depth to Water (ft)	9.19	9.28	10.01	10.05	10.08	10.31
Purge Rate (L/min)	0.3	0.3	0.3	0.3	0.3	0.3
Volume Purged (L)		1.5	3.0	4.5	6.0	7.5
pH		4.88	4.88	4.85	4.74	4.69
Temperature (°C)		19.2	19.3	19.4	19.6	20.0
Conductivity (µmhos/cm)		1.66	1.67	1.68	1.68	1.69
Dissolved Oxygen (mg/L)		1.10	1.28	1.19	1.65	1.15
Turbidity (NTU)		-10	-10	-10	-10	-10
Eh (mv)		93.6	95.0	95.0	94.2	94.2

TOTAL VOLUME WATER PURGED: ✓ GAL + (24 LITERS * 0.264 GAL/LITER) = 6.34 GAL
SAMPLERS: BDA/mb SAMPLING TIME (START/END): 1715/1740
SAMPLING DATE: 100598 DECONTAMINATION FLUIDS USED: methanol, DI
SAMPLE TYPE: G.A.A.B SAMPLE PRESERVATIVES: HCl, HNO₃, H₂SO₄
SAMPLE BOTTLE IDs: 375-100598

SAMPLE PARAMETERS: VOC, TDS, Methane, Diss. Ammonia, Diss. Metals, Inorg. Anions, Sulfides, Alkalinity

COMMENTS AND OBSERVATIONS: Increase flow slightly at 1613. Water Quality
Reading. Purge water is clear. Changed ~~755~~ before 1638 water
quality reading.

PUMP #: F
LEVEL: 15 ft.

ODOR: NO ODOR

FIELD RECORD OF WELL GAUGING, PURGING, AND SAMPLING (OVERFLOW PAGE)

Site Name: NAWC TRENTON	Project No.: 29600.43	Date: 10/05/98
Well ID: 375	Field Personnel: BDA / MB	

* changed Horiba
pH

Parameter	6	7	8	9	10	11
Time (min.)	1623	1628	1633	1638	1643	1648
Depth to Water (ft)	10.41	10.46	10.75	10.82	10.82	10.91
Purge Rate (L/min)	0.3	0.3	0.3	0.3	0.3	0.3
Volume Purged (L)	9.0	10.5	12.0	13.5	15.0	16.5
pH	4.65	4.66	4.74	4.84	4.87	4.90
Temperature (°C)	20.3	20.5	21.4	21.3	21.3	21.3
Conductivity (μmhos/cm)	1.68	1.61	1.27	1.26	1.24	1.24
Dissolved Oxygen (mg/L)	1.29	1.32	1.51	1.70	1.61	1.46
Turbidity (NTU)	-10	-10	* 1	0	0	0
Eh (mv)	92.8	91.9	85.5	94.6	112.7	127.2

Post sample

Parameter	12	13	14	15	16	17
Time (min)	1653	1658	1703	1708	1713	1740
Depth to Water (ft)	11.20	11.31	11.46	11.48	11.51	14.11
Purge Rate (L/min)	0.3	0.3	0.3	0.3	0.3	0.3
Volume Purged (L)	18.0	19.5	21.0	22.5	24.0	32.1
pH	4.95	4.95	4.95	4.93	4.95	5.02
Temperature (°C)	21.6	21.7	21.9	21.8	21.8	19.5
Conductivity (μmhos/cm)	1.23	1.22	1.22	1.23	1.23	1.51
Dissolved Oxygen (mg/L)	1.62	1.60	1.36	1.33	1.33	2.24
Turbidity (NTU)	0	0	0	0	0	3
Eh (mv)	140.7	146.2	152.1	154.7	155.9	234.8

2.3
8.1

COMMENTS AND OBSERVATIONS

**FIELD RECORD OF WELL GAUGING,
PURGING, AND SAMPLING**

13,755/20,934
DRY

SITE NAME: NAWC TRENTON PROJECT NUMBER: 29600.43
WELL I.D.: 4/5 WELL LOCK STATUS: _____
WELL CONDITION: _____ WEATHER: _____

GAUGE DATE: _____ GAUGE TIME: _____
SOUNDING METHOD: _____ MEASUREMENT REF: _____
STICK UP/DOWN (ft): _____ WELL DIAMETER (in.): 8"

PURGE DATE: _____ PURGE TIME: _____
PURGE METHOD: _____ FIELD PERSONNEL: _____
AMBIENT AIR VOCs (ppm) Start: _____ End: _____ WELL MOUTH VOCs (ppm): Start: _____ End: _____

A. WELL DEPTH (ft): 13 D. WELL VOLUME/FT (GAL): 2.6
B. DEPTH TO WATER (ft): _____ E. WELL VOLUME (GAL) (C*D): _____
C. H₂O COLUMN (ft) (A-B): _____ F. THREE WELL VOLUMES (GAL) (E*3): _____

Parameter	Beginning	1	2	3	4	5
Time (min)						
Depth to Water (ft)						
Purge Rate (L/min)						
Volume Purged (L)						
pH						
Temperature (°C)						
Conductivity (µmhos/cm)						
Dissolved Oxygen (mg/L)						
Turbidity (NTU)						
Eh (mv)						

TOTAL VOLUME WATER PURGED: _____ GAL + (_____ LITERS * 0.264 GAL/LITER) = _____ GAL
SAMPLERS: _____ SAMPLING TIME (START/END): _____
SAMPLING DATE: _____ DECONTAMINATION FLUIDS USED: _____
SAMPLE TYPE: _____ SAMPLE PRESERVATIVES: _____
SAMPLE BOTTLE IDs: _____
SAMPLE PARAMETERS: _____
COMMENTS AND OBSERVATIONS: _____

PUMP #:
LEVEL:

ODOR:

APPENDIX B

LABORATORY REPORT NARRATIVES



November 9, 1998

Mr. Steve Feldmann
EA Engineering, Science, and Technology, Inc.
Two Oak Way
Berkeley Heights, NJ 07922

Re: NAWC Trenton Navy Site 1 FFS (29600.43)

Dear Mr. Feldmann:

Enclosed is our report on the analysis of three water samples and one field blank collected for the NAWC Trenton Navy project on 5 October 1998. The EDDs will follow. The invoice is included.

Please contact me if you have any questions or require further information and refer to report 981648. Unless other arrangements are made, we reserve the right to dispose of your samples sixty (60) days from the date of this letter. We will retain the raw data for seven years from this date.

Sincerely,

A handwritten signature in cursive script that reads 'Michael J. Walsh'.

Michael J. Walsh
Laboratory Project Manager

enclosure

LABORATORY DATA REPORT

Prepared for:

**EA Engineering, Science, and Technology, Inc.
NAWC Trenton Navy**

Prepared by:

**EA Laboratories
19 Loveton Circle
Sparks, MD 21152**

Report 981648

November 1998

1. NARRATIVE

010000

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981648
Laboratory Project Manager: Michael J. Walsh
Report Date: 9 November 1998

This report contains the results of the analysis of three water samples and one field blank collected on 5 October 1998 in support of the referenced project.

SAMPLE RECEIPT

The samples field blank, and one trip blank arrived intact by Federal Express at EA Laboratories on 6 October 1998. Upon receipt, the samples and blank were inspected and compared with the chain-of-custody record. The samples and blank were then logged into the laboratory computer system with assigned laboratory accession numbers and released for analysis.

<u>Client Sample Designation</u>	<u>EA Lab Number</u>
FB-1	9812309
TRIP BLANK	9812310
37S-10/5/98	9812311
03BR-100598	9812312
11MW1-100598	9812313

Following this narrative section is list of analytical methods (Table 1), glossaries of data qualifiers (Tables 2 and 3), and the original chain-of-custody record. Analytical results and quality control information are summarized in the appended data package which has been formatted to be consistent with the deliverable requirements of this project.

QUALITY CONTROL

The following sections are ordered as the data appears in this report. They contain observations made during sample analysis, summarize the results of quality control measurements, and address the impact on data usability based upon project Data Quality Objectives. For each fractional analysis the narrative includes:

- Sample chronology: This section summarizes the sample history by fraction including the sample preparation method and date, analytical method, and analysis date. Anything unusual about the samples, digestates, or extracts is identified. Holding time compliance is evaluated in this section.
- Laboratory method performance: All quality control criteria for method performance must be met for all target analytes for data to be reported. These criteria generally apply to instrument tune, calibration, method blanks, and Laboratory Control Samples (LCS). In some instances where method criteria fail, useable data can be obtained and are reported with client approval. The

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981648
Laboratory Project Manager: Michael J. Walsh
Report Date: 9 November 1998

narrative will then include a thorough discussion of the impact on data quality.

- Sample performance: Quality control field samples are analyzed to determine any measurement bias due to the sample matrix based on evaluation of matrix spikes (MS), matrix spike duplicates (MSD), and laboratory duplicates (D). If acceptance criteria are not met, matrix interferences are confirmed either by reanalysis or by inspection of the LCS results to verify that laboratory method performance is in control. Data are reported with appropriate qualifiers or discussion.

VOLATILES by GC/MS - WATER (EA9812309 - EA9812313)

Sample Chronology: Five aqueous samples and associated quality control were analyzed on 17-18 October 1998 for the client specified list of analytes plus library searches (TICs) following the procedures specified in the CLP Statement of Work OLC02.1. All holding times were met.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples with the following exception:

- Ketones were spiked into the initial calibration standards at concentrations of 2,4,10,20, and 50 ug/L rather than the method specified 5,10,25,50, and 125 ug/L. Data usability is not affected.

Sample Performance: All quality control criteria were met for the reported samples.

- A matrix spike/matrix spike duplicate analysis was performed on sample 11MW1-100598. Recoveries are evaluated versus the requirements for the laboratory control sample (LCS); recoveries of trichloroethene are masked by the native concentration of this analyte in the sample.

ANIONS - WATER (EA9812309, EA9812311-EA9812313)

Sample Chronology: The samples and associated quality control were analyzed on 6 October 1998 by USEPA Method 300.0 for the anions chloride, nitrate and sulfate. All holding times were met.

Samples 37S-10/5/98 (25X), 03BR-100598 (2X) and 11MW1-100598 (2X) were reanalyzed at a dilution to bring the concentrations of target anions within calibration range. The results of both the undiluted and diluted analyses are included in this report.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples with the following exception:

The LCS recovery for sulfate (91%) was within the method acceptance limits of 90-110% but just outside of the project acceptance limits of 93-104%. This recovery is not indicative of a significant

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981648
Laboratory Project Manager: Michael J. Walsh
Report Date: 9 November 1998

measurement bias. Data usability should not be impacted.

Sample Performance: All quality control criteria were met for the reported samples.

METALS - WATER (EA9812309,EA9812311-EA9812313)

Sample Chronology: Four samples were prepared on 5 November 1998 and analyzed for dissolved barium, calcium, iron, magnesium, potassium, and sodium according to EPA method 200.7 on 5-6 November 1998.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples with the following exception:

Iron was detected in the preparation blank at a concentration (186 ug/L) greater than the reporting limit (100 ug/L). All samples which were not non-detects or had concentrations less than 10X the blank were redigested and reanalyzed with an acceptable blank.

Sample Performance: All quality control criteria were met for the reported samples.

GENERAL CHEMISTRY - WATER (EA9812309, EA9812311-EA9812312, EA9812313)

Sample Chronology: Four samples were analyzed for the following USEPA methods. All holding times were met.

<u>Parameter</u>	<u>Method#</u>	<u>Prep Date</u>	<u>Analysis Date</u>
Dissolved Ammonia	350.1	27 October 1998	28 October 1998
DOC	415.1	N/A	28 October 1998
TDS	160.1	N/A	9 October 1998

Laboratory Method Performance: All laboratory method performance criteria were met.

Sample Performance: All quality control criteria were met.

CERTIFICATION OF RESULTS

The Laboratory certifies that this report meets the project requirements for analytical data as stated in the Analytical Task Order (ATO) and the chain-of-custody. In addition, the Laboratory certifies that the data as reported meet the Data Quality Objectives for precision, accuracy, and completeness specified for this project or as stated in EA Laboratories Quality Assurance program for other than the conditions detailed

010003

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981648
Laboratory Project Manager: Michael J. Walsh
Report Date: 9 November 1998

above. It is recommended by the Laboratory that this analytical report should only be reproduced in its entirety. EA Laboratories is not responsible for any assumptions of data quality if partial packages are used to interpret data. Release of the data contained in this report has been authorized by the appropriate Laboratory Manager as verified by the following signature.




November 9, 1998

Michael J. Walsh, Laboratory Project Manager

010004

13400/580841

020001

Company Name: EA NT		Project Manager or Contact: STEVE FELDMAN		Parameters/Method Numbers for Analysis										Chain of Custody Record	
Project No. 29600 43		Phone: 908-665-2440												 EA Laboratories 19 Loveton Circle Sparks, MD 21152 Telephone: (410) 771-4920 Fax: (410) 771-4407	
Dept.: 2131 Task: 7216		Project Name: NAVY, TRENTON												Report Deliverables: 1 2 3 4 5 ① ② ③ ④ ⑤ EDD: Yes No Summer NJ DEP DUE TO CLIENT: Nov. 6, 1998	
Sample Storage Location: F9/VCH		ATO Number: 7085												EA Labs Accession Number	
Page 1 of 1		Report #: 981645												Remarks	
Date	Time	Water	Soil	Sample Identification 19 Characters		No. of Containers	VOC +10 BY CLP	TDS BY 160.1	DOC BY 415.1	DISSOLVED METALS BY 350.1	DISSOLVED METALS BY 200.7	INORGANIC ANIONS BY 300.0			
10/5/98	1630	X		FB-1		7	X	X	X	X	X	X	9812309 LPM: DAVID ARENHAN		
10/5/98	-	X		TRIP BLANK		3	X						9812310 Michael Walsh		
10/5/98	1715	X		375-10/5/98		7	X	X	X	X	X	X	9812311 VOC +10 BY CLP		
10/5/98	1718	X		0301A-V100596		7	X	X	X	X	X	X	9812312 W/TIC		
10/5/98	1330	X		1.17741-05		7	X	X	X	X	X	X	9812313 VOC +10 by CLP are by low concentration OLC 02.0		
10/5/98	1330	X		1.17741-05		7	X	X	X	X	X	X			
														- All parameters have been Field Filtered except for VOC & TDS	
														- Report dissolved organic carbon to MOL (0.2 mg/L)	
														4 6" btl	
														4 1" 1 L btl	
														4 1" btl	
														4 1" btl	
														15 VOC VIALS	
														L14791	
														000003936	
Samples by: (Signature) Ronald L. Howard		Date/Time 10/5/98 1718		Relinquished by: (Signature) Ronald L. Howard		Date/Time 10/5/98 1900		Received by: (Signature) [Signature]		Date/Time 10/5/98 1900		Airbill Number: 1852811785		Sample Shipped by: (Circle) Fed Ex Puro. UPS	
Relinquished by: (Signature) [Signature]		Date/Time 10/5/98		Received by Laboratory: (Signature) [Signature]		Date/Time 10/6/98		Airbill Number: 1852811785		Hand Carried [Signature]		Other: 1852811785			
Cooler Temp. 3° C pH: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Comments: _____ Custody Seals Intact <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No															
NOTE: Please indicate method number for analyses requested. This will help clarify any questions with laboratory techniques.															



November 23, 1998

Mr. Steve Feldmann
EA Engineering, Science, and Technology, Inc.
Two Oak Way
Berkeley Heights, NJ 07922

Re: NAWC Trenton Navy Site 1 FFS (29600.43)

Dear Mr. Feldmann:

Enclosed is our report on the analysis of six water samples collected for the NAWC Trenton Navy project on 6 October 1998. The EDDs will follow. The invoice is included.

Please contact me if you have any questions or require further information and refer to report 981653. Unless other arrangements are made, we reserve the right to dispose of your samples sixty (60) days from the date of this letter. We will retain the raw data for seven years from this date.

Sincerely,

A handwritten signature in cursive script that reads 'Michael J. Walsh'.

Michael J. Walsh
Laboratory Project Manager

enclosure

LABORATORY DATA REPORT

Prepared for:

**EA Engineering, Science, and Technology, Inc.
NAWC Trenton Navy**

Prepared by:

**EA Laboratories
19 Loveton Circle
Sparks, MD 21152**

Report 981653

November 1998

1. NARRATIVE

010000

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: **EA Eng., Sci., & Tech., Inc.**
Site: **NAWC Trenton Navy Site 1 FFS**
Project number: **29600.43**

EA Laboratories Report: **981653**
Laboratory Project Manager: **Michael J. Walsh**
Report Date: **23 November 1998**

This report contains the results of the analysis of six water samples collected on 6 October 1998 in support of the referenced project.

SAMPLE RECEIPT

The samples and one trip blank arrived intact by Federal Express at EA Laboratories on 7 October 1998. Upon receipt, the samples and blank were inspected and compared with the chain-of-custody record. The samples and blank were then logged into the laboratory computer system with assigned laboratory accession numbers and released for analysis.

<u>Client Sample Designation</u>	<u>EA Lab Number</u>
TRIP BLANK	9812354
FB2-100698	9812355
21BR-100698	9812356
19BR-100698	9812357
28BR-100698	9812358
37BR-100698	9812359
11BR-100698	9812360

Following this narrative section is list of analytical methods (Table 1), glossaries of data qualifiers (Tables 2 and 3), and the original chain-of-custody record. Analytical results and quality control information are summarized in the appended data package which has been formatted to be consistent with the deliverable requirements of this project.

QUALITY CONTROL

The following sections are ordered as the data appears in this report. They contain observations made during sample analysis, summarize the results of quality control measurements, and address the impact on data usability based upon project Data Quality Objectives. For each fractional analysis the narrative includes:

- Sample chronology: This section summarizes the sample history by fraction including the sample preparation method and date, analytical method, and analysis date. Anything unusual about the samples, digestates, or extracts is identified. Holding time compliance is evaluated in this section.
- Laboratory method performance: All quality control criteria for method performance must be met for all target analytes for data to be reported. These criteria generally apply to instrument tune,

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981653
Laboratory Project Manager: Michael J. Walsh
Report Date: 23 November 1998

calibration, method blanks, and Laboratory Control Samples (LCS). In some instances where method criteria fail, useable data can be obtained and are reported with client approval. The narrative will then include a thorough discussion of the impact on data quality.

- Sample performance: Quality control field samples are analyzed to determine any measurement bias due to the sample matrix based on evaluation of matrix spikes (MS), matrix spike duplicates (MSD), and laboratory duplicates (D). If acceptance criteria are not met, matrix interferences are confirmed either by reanalysis or by inspection of the LCS results to verify that laboratory method performance is in control. Data are reported with appropriate qualifiers or discussion.

VOLATILES by GC/MS - WATER (EA9812354 - EA9812360)

Sample Chronology: Seven samples and associated quality control were analyzed following the procedures specified in the CLP Statement of Work OLC02.1 on 20 October 1998 for the Target Compound List (TCL) and library searches (TICs) using a 25mL purge volume. All holding times were met.

Sample 11BR-100698 required a 2X dilution in order to bring the concentrations of target analytes within the instrument calibration range.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples with the following exceptions;

- the batch method blank, VB810203, had the surrogate recovery of bromofluorobenzene (147%) above the upper QC limit of 120%. This high recovery may be indicative of a positive bias. However, since no target analytes were detected in the blank, there should be no impact on data usability.

Sample Performance: All quality control criteria were met for the reported samples.

ANIONS - WATER (EA9812355-EA9812360)

Sample Chronology: The samples and associated quality control were analyzed on 7 October 1998 by USEPA Method 300.0 for the anions chloride, nitrate and sulfate. All holding times were met.

Samples 21DR-100698 (5X), 28BR-100698 (5X), 37BR-100698 (2X) and 11BR-100698 (2X) were reanalyzed at a dilution to bring the concentrations of target anions within calibration range. The results of both the undiluted and diluted analyses are included in this report.

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: **EA Eng., Sci., & Tech., Inc.**
Site: **NAWC Trenton Navy Site 1 FFS**
Project number: **29600.43**

EA Laboratories Report: **981653**
Laboratory Project Manager: **Michael J. Walsh**
Report Date: **23 November 1998**

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples.

Sample Performance: All quality control criteria were met for the reported samples.

METALS - WATER (EA9812355-EA9812360)

Sample Chronology: Six samples were prepared on 5 November 1998 and analyzed for dissolved barium, calcium, iron, magnesium, potassium, and sodium according to EPA method 200.7 on 5-6 November 1998.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples with the following exception:

- Iron was detected in the preparation blank at a concentration (186 ug/L) greater than the reporting limit (100 ug/L). All samples which were not non-detects or had concentrations less than 10X the blank were redigested and reanalyzed with an acceptable blank.

Sample Performance: All quality control criteria were met for the reported samples.

GENERAL CHEMISTRY - WATER (EA9812355-EA9812360)

Sample Chronology: Six samples were analyzed for the following USEPA methods. All holding times were met.

<u>Parameter</u>	<u>Method#</u>	<u>Prep Date</u>	<u>Analysis Date</u>
Dissolved Ammonia	350.1	27 October 1998	28 October 1998
DOC	415.1	N/A	28 October 1998
TDS	160.1	N/A	13 October 1998

Laboratory Method Performance: All laboratory method performance criteria were met.

Sample Performance: All quality control criteria were met.

CERTIFICATION OF RESULTS

010003

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43


EA Laboratories Report: 981653
Laboratory Project Manager: Michael J. Walsh
Report Date: 23 November 1998

The Laboratory certifies that this report meets the project requirements for analytical data as stated in the Analytical Task Order (ATO) and the chain-of-custody. In addition, the Laboratory certifies that the data as reported meet the Data Quality Objectives for precision, accuracy, and completeness specified for this project or as stated in EA Laboratories Quality Assurance program for other than the conditions detailed above. It is recommended by the Laboratory that this analytical report should only be reproduced in its entirety. EA Laboratories is not responsible for any assumptions of data quality if partial packages are used to interpret data. Release of the data contained in this report has been authorized by the appropriate Laboratory Manager as verified by the following signature.

 November 23, 1998
Michael J. Walsh, Laboratory Project Manager

010004

114791/981646

Company Name: EA-NJ		Project Manager or Contact: STEVE FELDMANN Phone: 908-665-2440		Parameters/Method Numbers for Analysis										Chain of Custody Record						
Project No. 29600.43		Project Name: NAVY, TRENTON		<div style="display: flex; flex-direction: column; align-items: center;"><div>020 170 020</div><div>VOC + 10 CLP</div><div>TDS BY 160.1</div><div>DOC BY 415.1</div><div>DISSOLVED AMMONIA BY 350.1</div><div>DISSOLVED METALS BY 200.7</div><div>INORGANIC AMMONIUM BY 300.0</div></div>										 EA Laboratories 19 Loveton Circle Sparks, MD 21152 Telephone: (410) 771-4920 Fax: (410) 771-4407						
Dept.: 2131 Task: 7216		ATO Number: 7085												Report Deliverables: W/ 4D BACK-UP 1 2 3 4 D E EDD: Yes/No D-BASE EXCEL Summary tables						
Sample Storage Location: VIA/IT/metals-AZ1		Report #: 981653												DUE TO CLIENT: 30-DAY HARDCOPY						
Page 1 of 1														EA Labs Accession Number		Hard Copy due Nov 7, 1998 EODs due Nov 21, 1998 Remarks				
Date	Time	Water	Soil	Sample Identification 19 Characters		No. of Containers														
10/6/98	—	X		TRIP BLANK		3	X										9812354	LPM: DAVID DRENNAN		
10/6/98	1550	X		FB2-100698		7	X	X	X	X	X	X					9812355			
10/6/98	1322	X		21DR-100698		7	X	X	X	X	X	X					9812356	VOC + 10 BY CLP OLC 020		
10/6/98	1020	X		19DR-100698		7	X	X	X	X	X	X					9812357	LOW CONCENTRATION		
10/6/98	1056	X		28DR-100698		7	X	X	X	X	X	X					9812358			
10/6/98	1425	X		37DR-100698		7	X	X	X	X	X	X					9812359	ALL PARAMETERS EXCEPT		
10/6/98	1614	X		11DR-100698		7	X	X	X	X	X	X					9812360	VOC + TDS HAVE BEEN FIELD FILTERED		
																		ANY QUESTIONS, CALL STEVE FELDMANN		
Dissolved inorganic anions are: Sulfate, Chloride, & Nitrate																				
Dissolved Metals: Ca, Mg, K, Na, Fe, Ba																				
Report dissolved organic carbon to MOL (0.2 mg/L)																				
COCON03941																				
6A 1L, 6A 500mL																				
6C, 6B																				
21 VOA																				
L14819																				
Samples by: (Signature) <i>Ronald A. Howard</i>		Date/Time 10/6/98 1614		Relinquished by: (Signature) <i>Ronald A. Howard</i>		Date/Time 10/6/98 1730		Received by: (Signature)		Date/Time										
Relinquished by: (Signature) <i>[Signature]</i>		Date/Time		Received by Laboratory: (Signature) <i>[Signature]</i>		Date/Time 10/7/98 1020		Albill Number: 1852811763 1852811774		Sample Shipped by: (Circle) Fed Ex. Puro. UPS		Hand Carried Other:								
Cooler Temp. <u>2</u> °C pH: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Comments: Custody Seals Intact <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No																				
NOTE: Please indicate method number for analyses requested. This will help clarify any questions with laboratory techniques.																				

020001



November 17, 1998

Mr. Steve Feldmann
EA Engineering, Science, and Technology, Inc.
Two Oak Way
Berkeley Heights, NJ 07922

Re: NAWC Trenton Navy Site 1 FFS (29600.43)

Dear Mr. Feldmann:

Enclosed is our report on the analysis of nine water samples collected for the NAWC Trenton Navy project on 7 October 1998. The EDDs will follow. The invoice is included.

Please contact me if you have any questions or require further information and refer to report 981664. Unless other arrangements are made, we reserve the right to dispose of your samples sixty (60) days from the date of this letter. We will retain the raw data for seven years from this date.

Sincerely,

A handwritten signature in cursive script that reads "Michael J. Walsh".

Michael J. Walsh
Laboratory Project Manager

enclosure

LABORATORY DATA REPORT

Prepared for:

**EA Engineering, Science, and Technology, Inc.
NAWC Trenton Navy**

Prepared by:

**EA Laboratories
19 Loveton Circle
Sparks, MD 21152**

Report 981664

November 1998

1. NARRATIVE

010000

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981664
Laboratory Project Manager: Michael J. Walsh
Report Date: 17 November 1998

This report contains the results of the analysis of nine water samples collected on 7 October 1998 in support of the referenced project.

SAMPLE RECEIPT

The samples and one trip blank arrived intact by Federal Express at EA Laboratories on 12 October 1998. Upon receipt, the samples and blank were inspected and compared with the chain-of-custody record. The samples and blank were then logged into the laboratory computer system with assigned laboratory accession numbers and released for analysis.

<u>Client Sample Designation</u>	<u>EA Lab Number</u>
TRIP BLANK	9812410
FB3-100798	9812411
MW34BR-100798	9812412
12BR-100798	9812413
02BR-100798	9812414
12S-100798	9812415
9BR-100798	9812416
51BR-100798	9812417
DUP1-100798	9812418
MW6BR-100798	9812419

Following this narrative section is list of analytical methods (Table 1), glossaries of data qualifiers (Tables 2 and 3), and the original chain-of-custody record. Analytical results and quality control information are summarized in the appended data package which has been formatted to be consistent with the deliverable requirements of this project.

QUALITY CONTROL

The following sections are ordered as the data appears in this report. They contain observations made during sample analysis, summarize the results of quality control measurements, and address the impact on data usability based upon project Data Quality Objectives. For each fractional analysis the narrative includes:

- **Sample chronology:** This section summarizes the sample history by fraction including the sample preparation method and date, analytical method, and analysis date. Anything unusual about the samples, digestates, or extracts is identified. Holding time compliance is evaluated in this section.

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981664
Laboratory Project Manager: Michael J. Walsh
Report Date: 17 November 1998

-
- Laboratory method performance: All quality control criteria for method performance must be met for all target analytes for data to be reported. These criteria generally apply to instrument tune, calibration, method blanks, and Laboratory Control Samples (LCS). In some instances where method criteria fail, useable data can be obtained and are reported with client approval. The narrative will then include a thorough discussion of the impact on data quality.
 - Sample performance: Quality control field samples are analyzed to determine any measurement bias due to the sample matrix based on evaluation of matrix spikes (MS), matrix spike duplicates (MSD), and laboratory duplicates (D). If acceptance criteria are not met, matrix interferences are confirmed either by reanalysis or by inspection of the LCS results to verify that laboratory method performance is in control. Data are reported with appropriate qualifiers or discussion.

VOLATILES by GC/MS - WATER (EA9812410, EA9812411, EA9812413 - EA9812419)

Sample Chronology: Nine samples and associated quality control were analyzed following the procedures specified in the CLP Statement of Work OLC02.1 on 21 and 22 October and 8 and 9 November 1998 for the Target Compound List (TCL) and library searches (TICs) using a 25mL purge volume. All holding times were met for all initial analyses. All reanalyses and dilutions were performed outside the method holding time.

Samples 02BR-100798 and DUP1-100798 required a 10X dilution in order to bring the concentrations of target analytes within the instrument calibration range. Sample 12S-100798 required a 20X dilution. Sample 51BR-100798 required a 5X dilution.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples with the following exceptions;

- the batch LCS, VL811081, had the recoveries of carbon tetrachloride (155%), 1,2-dichloropropane (153%) and cis-1,3-dichloropropane (147%) above the upper QC limit of 140%. These high recoveries may be indicative of a positive method bias, however, since none of these analytes were detected in the samples there should be no impact on data usability.

Sample Performance: All quality control criteria were met for the reported samples with the following exceptions;

- the batch MS/MSD performed on sample 51BR-100798, had the surrogate recoveries of BFB (78% and 65%) below the lower QC limit of 80%. These low recoveries may be indicative of a

010002

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981664
Laboratory Project Manager: Michael J. Walsh
Report Date: 17 November 1998

negative bias for these QC samples. Sample MW6BR-100798 had the surrogate recovery of BFB (64%) below the lower QC limit of 80%. This sample was reanalyzed with similar results. These low recoveries may be indicative of a negative bias for these sample analyses.

- the batch MSD, performed on sample 15BR-100798, had the recovery of trichloroethene (612%) above the upper QC limit of 140% (the MS recovery was 114%). This high recovery appears to have been influenced by the high native concentration of trichloroethene in the sample.

ANIONS - WATER (EA9812411 - EA9812419)

Sample Chronology: Nine aqueous samples and associated quality control were analyzed on 08 October 1998 by USEPA Method 300.0 for the anions chloride, nitrate, and sulfate. All holding times were met.

- Sample MW34BR-100798 was reanalyzed at a five times (5X) dilution, and samples 9BR-100798, 51BR-100798, DUP1-100798, and MW6BR-100798 were reanalyzed at two times (2X) dilutions in order to bring the concentrations of target anions within calibration range.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples.

- The laboratory control sample (LCS) ZL810081 met the laboratory's QC limits of 90-110% recovery for all target anions. The recoveries of nitrate ion (93%) and sulfate ion (90%), however, failed to meet the project criteria of 95-109% and 93-104% recovery, respectively. Data usability should not be impacted.

Sample Performance: All quality control criteria were met for the reported samples with the following exception:

- The matrix spike duplicate (MSD) performed on sample 51BR-100798 had the recovery of sulfate ion just above the upper QC limit of 125% at 126%. The high recovery is based on estimated values (concentrations above the calibration range); data usability is not affected.

METALS - WATER (EA9812411-EA9812419)

Sample Chronology: Nine samples were prepared on 5 November 1998 and analyzed for dissolved barium, calcium, iron, magnesium, potassium, and sodium according to EPA method 200.7 on 5-6

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981664
Laboratory Project Manager: Michael J. Walsh
Report Date: 17 November 1998

November 1998.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples with the following exception:

- Iron was detected in the preparation blank at a concentration (186 ug/L) greater than the reporting limit (100 ug/L). All samples which were not non-detects or had concentrations less than 10X the blank were redigested and reanalyzed with an acceptable blank.

Sample Performance: All quality control criteria were met for the reported samples.

GENERAL CHEMISTRY - WATER (EA9812411-EA9812419)

Sample Chronology: Nine samples were analyzed for the following USEPA methods. All holding times were met.

<u>Parameter</u>	<u>Method#</u>	<u>Prep Date</u>	<u>Analysis Date</u>
Dissolved Ammonia	350.1	27 October 1998	28 October 1998
DOC	415.1	N/A	29 October 1998
TDS	160.1	N/A	13 October 1998

Laboratory Method Performance: All laboratory method performance criteria were met.

Sample Performance: All quality control criteria were met with the following exception:

- The ammonia MS/MSD were not recovered. This may bias the sample results low.

CERTIFICATION OF RESULTS

The Laboratory certifies that this report meets the project requirements for analytical data as stated in the Analytical Task Order (ATO) and the chain-of-custody. In addition, the Laboratory certifies that the data as reported meet the Data Quality Objectives for precision, accuracy, and completeness specified for this project or as stated in EA Laboratories Quality Assurance program for other than the conditions detailed above. It is recommended by the Laboratory that this analytical report should only be reproduced in its entirety. EA Laboratories is not responsible for any assumptions of data quality if partial packages are

010004

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981664
Laboratory Project Manager: Michael J. Walsh
Report Date: 17 November 1998

used to interpret data. Release of the data contained in this report has been authorized by the appropriate Laboratory Manager as verified by the following signature.



November 17, 1998
Michael J. Walsh, Laboratory Project Manager

010005



November 17, 1998

Mr. Steve Feldmann
EA Engineering, Science, and Technology, Inc.
Two Oak Way
Berkeley Heights, NJ 07922


Re: NAWC Trenton Navy Site 1 FFS (29600.43)

Dear Mr. Feldmann:

Enclosed is our report on the analysis of nine water samples collected for the NAWC Trenton Navy project on 8 October 1998. The EDDs will follow. The invoice is included.

Please contact me if you have any questions or require further information and refer to report 981667. Unless other arrangements are made, we reserve the right to dispose of your samples sixty (60) days from the date of this letter. We will retain the raw data for seven years from this date.

Sincerely,



Michael J. Walsh
Laboratory Project Manager

enclosure

LABORATORY DATA REPORT

Prepared for:

**EA Engineering, Science, and Technology, Inc.
NAWC Trenton Navy**

Prepared by:

**EA Laboratories
19 Loveton Circle
Sparks, MD 21152**

Report 981667

November 1998

1. NARRATIVE

010000

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981667
Laboratory Project Manager: Michael J. Walsh
Report Date: 17 November 1998

This report contains the results of the analysis of nine water samples collected on 8 October 1998 in support of the referenced project.

SAMPLE RECEIPT

The samples and one trip blank arrived intact by Federal Express at EA Laboratories on 9 October 1998. Upon receipt, the samples and blank were inspected and compared with the chain-of-custody record. The samples and blank were then logged into the laboratory computer system with assigned laboratory accession numbers and released for analysis.

<u>Client Sample Designation</u>	<u>EA Lab Number</u>
31BR-100898	9812523
TRIP BLANK	9812524
FB4-100898	9812525
27BR-100898	9812526
39BR-100898	9812527
42BR-100898	9812528
47BR-100898	9812529
07BR-100898	9812530
BRP-3-100898	9812531
40BR-100898	9812532

Following this narrative section is list of analytical methods (Table 1), glossaries of data qualifiers (Tables 2 and 3), and the original chain-of-custody record. Analytical results and quality control information are summarized in the appended data package which has been formatted to be consistent with the deliverable requirements of this project.

QUALITY CONTROL

The following sections are ordered as the data appears in this report. They contain observations made during sample analysis, summarize the results of quality control measurements, and address the impact on data usability based upon project Data Quality Objectives. For each fractional analysis the narrative includes:

- **Sample chronology:** This section summarizes the sample history by fraction including the sample preparation method and date, analytical method, and analysis date. Anything unusual about the samples, digestates, or extracts is identified. Holding time compliance is evaluated in this section.

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981667
Laboratory Project Manager: Michael J. Walsh
Report Date: 17 November 1998

-
- Laboratory method performance: All quality control criteria for method performance must be met for all target analytes for data to be reported. These criteria generally apply to instrument tune, calibration, method blanks, and Laboratory Control Samples (LCS). In some instances where method criteria fail, useable data can be obtained and are reported with client approval. The narrative will then include a thorough discussion of the impact on data quality.
 - Sample performance: Quality control field samples are analyzed to determine any measurement bias due to the sample matrix based on evaluation of matrix spikes (MS), matrix spike duplicates (MSD), and laboratory duplicates (D). If acceptance criteria are not met, matrix interferences are confirmed either by reanalysis or by inspection of the LCS results to verify that laboratory method performance is in control. Data are reported with appropriate qualifiers or discussion.

ANIONS - WATER (EA9812523, EA9812525 - EA9812532)

Sample Chronology: Nine aqueous samples and associated quality control were analyzed on 09 October 1998 by USEPA Method 300.0 for the anions chloride, nitrate, and sulfate. All holding times were met.

- Samples 47BR-100898 and 40BR-100898 were reanalyzed at a two times (2X) dilutions, and samples 07BR-100898 and BRP3-100898 were reanalyzed at five times (5X) dilutions in order to bring the concentrations of target anions within calibration range.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples.

Sample Performance: All quality control criteria were met for the reported samples.

METALS - WATER (EA9812523, EA9812525-EA9812532)

Sample Chronology: Nine samples were prepared on 6 November 1998 and analyzed for dissolved barium, calcium, iron, magnesium, potassium, and sodium according to EPA method 200.7 on 8-9 November 1998.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples.

Sample Performance: All quality control criteria were met for the reported samples with the following exception:

The recovery of calcium in the matrix spike (71 %) is below the lower control limit (75 %), indicating

010002

EA Laboratories
ANALYTICAL NARRATIVE

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981667
Laboratory Project Manager: Michael J. Walsh
Report Date: 17 November 1998

the potential for bias to the reported data.

GENERAL CHEMISTRY - WATER (EA9812523, EA9812525-EA9812532)

Sample Chronology: Nine samples were analyzed for the following USEPA methods. All holding times were met.

Parameter	Method#	Prep Date	Analysis Date
Dissolved Ammonia	350.1	28 October 1998	28 October 1998
DOC	415.1	N/A	29 October 1998
TDS	160.1	N/A	13 October 1998

Laboratory Method Performance: All laboratory method performance criteria were met.

Sample Performance: All quality control criteria were met with the following exception:

- The ammonia MS/MSD were not recovered. This may bias the sample results low.

CERTIFICATION OF RESULTS

The Laboratory certifies that this report meets the project requirements for analytical data as stated in the Analytical Task Order (ATO) and the chain-of-custody. In addition, the Laboratory certifies that the data as reported meet the Data Quality Objectives for precision, accuracy, and completeness specified for this project or as stated in EA Laboratories Quality Assurance program for other than the conditions detailed above. It is recommended by the Laboratory that this analytical report should only be reproduced in its entirety. EA Laboratories is not responsible for any assumptions of data quality if partial packages are used to interpret data. Release of the data contained in this report has been authorized by the appropriate Laboratory Manager as verified by the following signature.



Michael J. Walsh, Laboratory Project Manager

November 17, 1998

010003

Company Name: **EA NT**
 Project No. **29600.43**
 Dept.: **2131** Task: **7216**
 Sample Storage Location: **DIO/VCA**
 Project Manager: **STEVE FELDMANN**
 Phone: **908-665-2440**
 Project Name: **NAVY TRENTON**
 ATO Number: **7085**

Parameters/Method Numbers for Analysis											
No. of Containers	VOC + 10 by CLP	TDS by 160.1	DOC by 415.1	DISSOLVED ORGANICS BY 302.1	DISSOLVED METALS BY 200.7	LABORATORY METALS BY 300.0					

Chain of Custody Record

EA EA Laboratories
 19 Loveton Circle
 Sparks, MD 21152
 Telephone: (410) 771-4920
 Fax: (410) 771-4407

Report Deliverables: w/ 4D back-up
 1 2 3 4 D E
 EDD: Yes No **DATE, EXCEL summary files**
 DUE TO CLIENT: **30 DAY HARD COPY**

EA Labs Accession Number: **9812523**
 Hard Copy due Nov. 9, 1998
 EDDs due Nov. 23, 1998
 Remarks: **LPM: DAVID BRENNAN**

Date	Time	Water	Soil	Sample Identification 19 Characters	No. of Containers	VOC + 10 by CLP	TDS by 160.1	DOC by 415.1	DISSOLVED ORGANICS BY 302.1	DISSOLVED METALS BY 200.7	LABORATORY METALS BY 300.0
10/8/98	0841	X		31BR-100898	7	X	X	X	X	X	X
10/8/98	—	X		TR1 PBLANK	3	X					
10/8/98	1440	X		F04-100898	7	X	X	X	X	X	X
10/8/98	1100	X		270R-100898	7	X	X	X	X	X	X
10/8/98	1044	X		390R-100898	7	X	X	X	X	X	X
10/8/98	1100	X		42BR-100898	7	X	X	X	X	X	X
10/8/98	1211	X		47BR-100898	7	X	X	X	X	X	X
* 10/8/98	1405	X		07BR-100898	7	X	X	X	X	X	X
10/8/98	1531	X		BRP3-100898	7	X	X	X	X	X	X
10/8/98	1701	X		40BR-100898	7	X	X	X	X	X	X

ANY QUESTIONS, CALL
STEVE FELDMANN

* 07BR - Historically
 High TCE concentrations

Report dissolved organic
 carbon to MWL (0.2 ng/L)

L K807
CO000039510

Samples by: (Signature) **Ronald A. Harold** Date/Time **10/8/98 1701**
 Relinquished by: (Signature) **Ronald A. Harold** Date/Time **10/8/98 1800**
 Relinquished by: (Signature) **Joseph Blum** Date/Time **10/9/98 10:15**
 Received by Laboratory: (Signature) **Joseph Blum** Date/Time **10/9/98 10:15**
 Airbill Number: **801688201185**
 Sample Shipped by: (Circle) Fed Ex. ☒ Puro. ☐ UPS
 Hand Carried ☐ Other: **801688201185**
 Cooler Temp. **2** C pH: ☒ Yes ☐ No Comments: **62.5 B2** Custody Seals Intact ☒ Yes ☐ No



December 1, 1998

Mr. Steve Feldmann
EA Engineering, Science, and Technology, Inc.
Two Oak Way
Berkeley Heights, NJ 07922

Re: NAWC Trenton Navy Site 1 FFS (29600.43)

Dear Mr. Feldmann:

Enclosed is an addendum for our report on the analysis of nine water samples collected for the NAWC Trenton Navy project on 8 October 1998. The EDDs will follow.

Please contact me if you have any questions or require further information and refer to report 981667add. Unless other arrangements are made, we reserve the right to dispose of your samples sixty (60) days from the date of this letter. We will retain the raw data for seven years from this date.

Sincerely,

A handwritten signature in cursive script, appearing to read 'Michael J. Walsh'.

Michael J. Walsh
Laboratory Project Manager

enclosure

LABORATORY DATA REPORT

Prepared for:

**EA Engineering, Science, and Technology, Inc.
NAWC Trenton Navy**

Prepared by:

**EA Laboratories
19 Loveton Circle
Sparks, MD 21152**

Report 981667add

December 1998

1. NARRATIVE

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981667add
Laboratory Project Manager: Michael J. Walsh
Report Date: 1 December 1998

This report contains the results of the analysis of nine water samples collected on 8 October 1998 in support of the referenced project.

SAMPLE RECEIPT

The samples and one trip blank arrived intact by Federal Express at EA Laboratories on 9 October 1998. Upon receipt, the samples and blank were inspected and compared with the chain-of-custody record. The samples and blank were then logged into the laboratory computer system with assigned laboratory accession numbers and released for analysis.

<u>Client Sample Designation</u>	<u>EA Lab Number</u>
31BR-100898	9812523
TRIP BLANK	9812524
FB4-100898	9812525
27BR-100898	9812526
39BR-100898	9812527
42BR-100898	9812528
47BR-100898	9812529
07BR-100898	9812530
BRP-3-100898	9812531
40BR-100898	9812532

Following this narrative section is list of analytical methods (Table 1), glossaries of data qualifiers (Tables 2 and 3), and the original chain-of-custody record. Analytical results and quality control information are summarized in the appended data package which has been formatted to be consistent with the deliverable requirements of this project.

QUALITY CONTROL

The following sections are ordered as the data appears in this report. They contain observations made during sample analysis, summarize the results of quality control measurements, and address the impact on data usability based upon project Data Quality Objectives. For each fractional analysis the narrative includes:

- Sample chronology: This section summarizes the sample history by fraction including the sample preparation method and date, analytical method, and analysis date. Anything unusual about the samples, digestates, or extracts is identified. Holding time compliance is evaluated in this section.

EA Laboratories
ANALYTICAL NARRATIVE

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981667add
Laboratory Project Manager: Michael J. Walsh
Report Date: 1 December 1998

-
- **Laboratory method performance:** All quality control criteria for method performance must be met for all target analytes for data to be reported. These criteria generally apply to instrument tune, calibration, method blanks, and Laboratory Control Samples (LCS). In some instances where method criteria fail, useable data can be obtained and are reported with client approval. The narrative will then include a thorough discussion of the impact on data quality.
 - **Sample performance:** Quality control field samples are analyzed to determine any measurement bias due to the sample matrix based on evaluation of matrix spikes (MS), matrix spike duplicates (MSD), and laboratory duplicates (D). If acceptance criteria are not met, matrix interferences are confirmed either by reanalysis or by inspection of the LCS results to verify that laboratory method performance is in control. Data are reported with appropriate qualifiers or discussion.

VOLATILES by GC/MS - WATER (EA9812523 - EA9812532)

Sample Chronology: Ten samples and associated quality control were analyzed following the procedures specified in the CLP Statement of Work OLC02.1 on 22 October and 12 and 13 November 1998 for the Target Compound List (TCL) and library searches (TICs) using a 25mL purge volume. All holding times were met for all initial analyses. All reanalyses and dilutions were performed outside the method holding times.

Sample 31BR-100898 required a 5X dilution in order to bring the concentrations of target analytes within the instrument calibration range. Sample 47BR-100898 was analyzed at both a 5X dilution and a 20X dilution. Sample 07BR-100898 was analyzed at both a 2000X and a 5000X dilution. Sample 40BR-100898 was analyzed at a 20X dilution.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples with the following exceptions;

- the batch LCS/LCSD, VL810221/ VD810221, had the recoveries of vinyl chloride (55%/59%) below the lower QC limit of 40%. The batch LCS, VL811129, had the recovery of vinyl chloride (49%) below the lower QC limit. These low recoveries may be indicative of a negative method bias for this target analyte.
- the batch MSD, analyzed on 12 November 1998, was performed 32 minutes outside of instrument tune time. There should be no impact on data usability.

Sample Performance: All quality control criteria were met for the reported samples with the following exceptions;

- sample 31BR-100898 had the surrogate recovery of bromofluorobenzene (78%) below the lower QC limit of 80%. This sample was reanalyzed with similar results. These low recoveries may be

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43


EA Laboratories Report: 981667add
Laboratory Project Manager: Michael J. Walsh
Report Date: 1 December 1998

indicative of a negative bias for this sample. The diluted analyses for 47BR-10098 and 07BR-100898 (as well as the MS/MSD performed on this sample) had the surrogate recoveries of bromofluorobenzene below the lower QC limit.

- the batch MS/MSD, performed on sample 07BR-100898DL, had the recoveries of vinyl chloride (57%/57%) below the lower QC limit of 60% and the recoveries of carbon tetrachloride (156%/157%), 1,2-dichloropropane (149%/143%), trichloroethene (159%/155%) and benzene (151%/151%) above the upper QC limit of 140%.
- the batch analyzed on 12 - 13 November 1998 was inadvertently double spiked with internal standard solution. All sample result have been adjusted to reflect the appropriate amount of internal standard added to the samples.

CERTIFICATION OF RESULTS

The Laboratory certifies that this report meets the project requirements for analytical data as stated in the Analytical Task Order (ATO) and the chain-of-custody. In addition, the Laboratory certifies that the data as reported meet the Data Quality Objectives for precision, accuracy, and completeness specified for this project or as stated in EA Laboratories Quality Assurance program for other than the conditions detailed above. It is recommended by the Laboratory that this analytical report should only be reproduced in its entirety. EA Laboratories is not responsible for any assumptions of data quality if partial packages are used to interpret data. Release of the data contained in this report has been authorized by the appropriate Laboratory Manager as verified by the following signature.



Michael J. Walsh, Laboratory Project Manager

December 1, 1998



December 4, 1998

Mr. Steve Feldmann
EA Engineering, Science, and Technology, Inc.
Two Oak Way
Berkeley Heights, NJ 07922

Re: NAWC Trenton Navy Site 1 FFS (29600.43)

Dear Mr. Feldmann:

Enclosed is our report on the analysis of nine water samples collected for the NAWC Trenton Navy project on 9 October 1998. The EDDs will follow. The invoice is included.

Please contact me if you have any questions or require further information and refer to report 981674. Unless other arrangements are made, we reserve the right to dispose of your samples sixty (60) days from the date of this letter. We will retain the raw data for seven years from this date.

Sincerely,

A handwritten signature in cursive script that reads 'Michael J. Walsh'.

Michael J. Walsh
Laboratory Project Manager

enclosure

LABORATORY DATA REPORT

Prepared for:

**EA Engineering, Science, and Technology, Inc.
NAWC Trenton Navy**

Prepared by:

**EA Laboratories
19 Loveton Circle
Sparks, MD 21152**

Report 981674

December 1998

1. NARRATIVE

010000

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981674
Laboratory Project Manager: Michael J. Walsh
Report Date: 4 December 1998

This report contains the results of the analysis of nine water samples collected on 9 October 1998 in support of the referenced project.

SAMPLE RECEIPT

The samples and one trip blank arrived intact by Federal Express at EA Laboratories on 10 October 1998. Upon receipt, the samples and blank were inspected and compared with the chain-of-custody record. The samples and blank were then logged into the laboratory computer system with assigned laboratory accession numbers and released for analysis.

<u>Client Sample Designation</u>	<u>EA Lab Number</u>
48BR-100998	9812562
BRP2-100998	9812563
15BR-100998	9812564
41BR-100998	9812565
TRIPBLANK	9812566
29BR-100998	9812567
22BR-100998	9812568
08BR-100998	9812569
31S-100998	9812570
04BR-100998	9812571

Following this narrative section is list of analytical methods (Table 1), glossaries of data qualifiers (Tables 2 and 3), and the original chain-of-custody record. Analytical results and quality control information are summarized in the appended data package which has been formatted to be consistent with the deliverable requirements of this project.

QUALITY CONTROL

The following sections are ordered as the data appears in this report. They contain observations made during sample analysis, summarize the results of quality control measurements, and address the impact on data usability based upon project Data Quality Objectives. For each fractional analysis the narrative includes:

- Sample chronology: This section summarizes the sample history by fraction including the sample preparation method and date, analytical method, and analysis date. Anything unusual about the samples, digestates, or extracts is identified. Holding time compliance is evaluated in this section.

010001

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981674
Laboratory Project Manager: Michael J. Walsh
Report Date: 4 December 1998

-
- **Laboratory method performance:** All quality control criteria for method performance must be met for all target analytes for data to be reported. These criteria generally apply to instrument tune, calibration, method blanks, and Laboratory Control Samples (LCS). In some instances where method criteria fail, useable data can be obtained and are reported with client approval. The narrative will then include a thorough discussion of the impact on data quality.
 - **Sample performance:** Quality control field samples are analyzed to determine any measurement bias due to the sample matrix based on evaluation of matrix spikes (MS), matrix spike duplicates (MSD), and laboratory duplicates (D). If acceptance criteria are not met, matrix interferences are confirmed either by reanalysis or by inspection of the LCS results to verify that laboratory method performance is in control. Data are reported with appropriate qualifiers or discussion.

VOLATILES by GC/MS - WATER (EA9812562 - EA9812571)

Sample Chronology: Ten samples and associated quality control were analyzed following the procedures specified in the CLP Statement of Work OLC02.1 on 22 - 23 October and 22 - 24 November 1998 for the Target Compound List (TCL) and library searches (TICs) using a 25mL purge volume. All holding times were met for all initial analyses. All reanalyses and dilutions were performed outside the method holding time.

Sample 48BR-100998 was analyzed at both a 5X and a 50X dilution in order to bring the concentrations of target analytes within the instrument calibration range. Samples BRP2-100998 and 15BR-100998 were analyzed at both a 100X dilution and 1000X dilution. Sample 41BR-100998 was analyzed at a 20X dilution. Samples 29BR-100998 and 04BR-100998 were analyzed at a 100X dilution. Sample 22BR-100998 was analyzed at a 5X dilution. Sample 08BR-100998 was analyzed at a 25X dilution. Sample 31S-100998 was analyzed at a 10X dilution.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples with the following exceptions;

- the batch LCS, VL810225, had the recovery of vinyl chloride (55%) below the lower QC limit of 60%.

Sample Performance: All quality control criteria were met for the reported samples with the following exceptions;

- the surrogate recoveries of bromofluorobenzene (BFB) in all sample analyses on 23 October 1998, were below the lower QC limit of 80%, ranging from 58% to 74%. All samples were reanalyzed with all surrogate recoveries within the method specified QC limits with the exception of 41BR-100998RE which had the recovery of BFB (123%) above the upper QC limit of 120%.

010002

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981674
Laboratory Project Manager: Michael J. Walsh
Report Date: 4 December 1998

-
- a batch MS was not analyzed on 23 October 1998.
 - the batch MSD, performed on sample 04BR-100998RE, had the recoveries of vinyl chloride (49%), carbon tetrachloride (55%) and tetrachloroethene (55%) below the lower QC limit of 60%. All MS recoveries were within QC limits. The batch MSD, performed on sample 48BR-100998DL, had the recovery of trichloroethene (56%) below the lower QC limit of 60%. All MS recoveries were within QC limits.
 - the reanalysis of sample 41BR-100998 had one or more internal standard areas below the lower QC limit of -50% of the daily calibration standard.

ANIONS - WATER (EA9812562 - EA9812565, EA9812567 - EA9812571)

Sample Chronology: Nine aqueous samples and associated quality control were analyzed on 10 October 1998 by USEPA Method 300.0 for the anions chloride, nitrate, and sulfate. All holding times were met.

- Sample BRP2-100998 was reanalyzed at a ten times (10X) dilution; samples 15BR-100998, 22BR-100998, and 04BR-100998 were reanalyzed at five times (5X) dilutions; and samples 41BR-100998, 08BR-100998, and 31S-100998 were reanalyzed at two times (2X) dilutions in order to bring the concentrations of target anions within calibration range.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples.

Sample Performance: All quality control criteria were met for the reported samples.

METALS - WATER (EA9812562-EA9812565,EA9812567-EA9812571)

Sample Chronology: Nine samples were prepared on 6 November 1998 and analyzed for dissolved barium, calcium, iron, magnesium, potassium, and sodium according to EPA method 200.7 on 8-9 November 1998.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples.

Sample Performance: All quality control criteria were met for the reported samples with the following exception:

The recovery of calcium in the matrix spike (71%) is below the lower control limit (75%), indicating the

010003

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981674
Laboratory Project Manager: Michael J. Walsh
Report Date: 4 December 1998

potential for bias to the reported data.

GENERAL CHEMISTRY - WATER (EA9812562-EA9812565, EA9812567-EA9812571)

Sample Chronology: Nine samples were analyzed for the following USEPA methods. All holding times were met.

<u>Parameter</u>	<u>Method#</u>	<u>Prep Date</u>	<u>Analysis Date</u>
Dissolved Ammonia	350.1	28 October 1998	28 October 1998
DOC	415.1	N/A	29 October 1998
TDS	160.1	N/A	13 October 1998

Laboratory Method Performance: All laboratory method performance criteria were met.

Sample Performance: All quality control criteria were met with the following exception:

- The ammonia MS/MSD were not recovered. This may bias the sample results low. The MS/MSD were performed on a Trenton sample from another report.

CERTIFICATION OF RESULTS

The Laboratory certifies that this report meets the project requirements for analytical data as stated in the Analytical Task Order (ATO) and the chain-of-custody. In addition, the Laboratory certifies that the data as reported meet the Data Quality Objectives for precision, accuracy, and completeness specified for this project or as stated in EA Laboratories Quality Assurance program for other than the conditions detailed above. It is recommended by the Laboratory that this analytical report should only be reproduced in its entirety. EA Laboratories is not responsible for any assumptions of data quality if partial packages are used to interpret data. Release of the data contained in this report has been authorized by the appropriate Laboratory Manager as verified by the following signature.



Michael J. Walsh, Laboratory Project Manager

December 4, 1998

010004

Company Name: EA - NJ		Project Manager or Contact: STEVE FELDMANN Phone: 908-665-2442		Parameters/Method Numbers for Analysis										Chain of Custody Record		
Project No. 29600.43		Project Name: NANY TRENTON		<div style="display: flex; flex-direction: column; align-items: center;"> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">No. of Containers</div> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">VOC + 10 by CLP 0.20</div> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">TDS BY 160.1</div> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">DOC BY 415.1</div> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">DISSOLVED AMMONIA BY 350.1</div> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">DISSOLVED METALS BY 200.7</div> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">INORGANIC AMMONIA BY 300.0</div> </div>										 EA Laboratories 19 Loveton Circle Sparks, MD 21152 Telephone: (410) 771-4920 Fax: (410) 771-4407		
Dept.: 2131 Task: 7212		ATO Number: 7085														
Sample Storage Location: VOA/ZI/E3																
Page 1 of 1		Report #: 981674												Report Deliverables: w/ 4D back-up 1 2 3 4 D E EDD: Yes/No WIDE MODIFICATION BASE EXCEL Summary DUE TO CLIENT: 30 DAY HANDCOPY		
Date	Time	Water	Soil	Sample Identification 19 Characters											EA Labs Accession Number	Ident Copy due Nov. 19, 1998 ENDS due Nov. 24, 1998 Remarks
10/9/98	0905	X		45BR-100998	7	X	X	X	X	X	X	X	X	X	9812562	LPM: DAVE BRENNAN / maw
10/9/98	1200	X		BRP-2-100998	7	X	X	X	X	X	X	X	X	X	9812563	
10/9/98	1050	X		15DR-100998	7	X	X	X	X	X	X	X	X	X	9812564	VOC + 10 CLP - LOW
10/9/98	0955	X		41BR-100998	7	X	X	X	X	X	X	X	X	X	9812565	CONCENTRATION
10/9/98	-	X		TRIPOLANK	7	X									9812566	
10/9/98	1055	X		29BR-100998	7	X	X	X	X	X	X	X	X	X	9812567	ALL PARAMETERS
10/9/98	1235	X		22BR-100998	7	X	X	X	X	X	X	X	X	X	9812568	EXCEPT VOC + TDS
10/9/98	0956	X		08DR-100998	7	X	X	X	X	X	X	X	X	X	9812569	HAVE BEEN FIELD
10/9/98	1040	X		31S-100998	7	X	X	X	X	X	X	X	X	X	9812570	FILTERED
10/9/98	1415	X		04BR-100998	7	X	X	X	X	X	X	X	X	X	9812571	L14820
					Dissolved Inorganics: Sulfate, nitrate, nitrite Dissolved Metals: Cu, Mn, K, Na, Fe, Ba											
															ANY QUESTIONS, CALL STEVE FELDMANN	
															* HISTORICALLY HIGH VOC (TCE) CONCENTRATIONS	
															30 VOLS 7 C 19 A 500K 9 A 1L	
															MRP-2, 15DR, 04BR COC 444 3963 Report dissolved organic Carbon to MDL (0.2 mg/L)	
Samples by: (Signature) <i>[Signature]</i>		Date/Time 10/9/98 1415		Relinquished by: (Signature) <i>[Signature]</i>		Date/Time 10/9/98 1600		Received by: (Signature) <i>[Signature]</i>				Date/Time				
Relinquished by: (Signature) <i>[Signature]</i>		Date/Time		Received by Laboratory: (Signature) <i>[Signature]</i>		Date/Time 10/9/98 10:30		Airbill Number: 185-2810385 185-2810374				Sample Shipped by: (Circle) Fed Ex Puro. UPS Hand Carried Other:				
Cooler Temp. 2°C pH: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		Comments:		Custody Seals Intact <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No												
NOTE: Please indicate method number for analyses requested. This will help clarify any questions with laboratory techniques.																



November 16, 1998

Mr. Steve Feldmann
EA Engineering, Science, and Technology, Inc.
Two Oak Way
Berkeley Heights, NJ 07922

Re: NAWC Trenton (29600.43)

Dear Mr. Feldmann:

Enclosed is our report on the analysis of eight water samples collected for the NAWC Trenton project on 12 October 1998. The EDDs will follow. The invoice is included.

Please contact me if you have any questions or require further information and refer to report 981679. Unless other arrangements are made, we reserve the right to dispose of your samples sixty (60) days from the date of this letter. We will retain the raw data for seven years from this date.

Sincerely,

A handwritten signature in cursive script that reads 'Michael J. Walsh'.

Michael J. Walsh
Laboratory Project Manager

enclosure

LABORATORY DATA REPORT

Prepared for:

**EA Engineering, Science, and Technology, Inc.
NAWC Trenton Navy**

Prepared by:

**EA Laboratories
19 Loveton Circle
Sparks, MD 21152**

Report 981679

November 1998

1. NARRATIVE

010000

EA Laboratories
ANALYTICAL NARRATIVE

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981679
Laboratory Project Manager: Michael J. Walsh
Report Date: 16 November 1998

This report contains the results of the analysis of eight water samples collected on 12 October 1998 in support of the referenced project.

SAMPLE RECEIPT

The samples and one trip blank arrived intact by Federal Express at EA Laboratories on 13 October 1998. Upon receipt, the samples and blank were inspected and compared with the chain-of-custody record. The samples and blank were then logged into the laboratory computer system with assigned laboratory accession numbers and released for analysis.

<u>Client Sample Designation</u>	<u>EA Lab Number</u>
TRIP BLANK	9812587
FB5-101298	9812588
35MW1-101298	9812589
35MW2-101298	9812590
43BR-101298	9812591
44BR-101298	9812592
FBG-101298	9812593
46BR-101298	9812594
49BR-101298	9812595

Following this narrative section is list of analytical methods (Table 1), glossaries of data qualifiers (Tables 2 and 3), and the original chain-of-custody record. Analytical results and quality control information are summarized in the appended data package which has been formatted to be consistent with the deliverable requirements of this project.

QUALITY CONTROL

The following sections are ordered as the data appears in this report. They contain observations made during sample analysis, summarize the results of quality control measurements, and address the impact on data usability based upon project Data Quality Objectives. For each fractional analysis the narrative includes:

- **Sample chronology:** This section summarizes the sample history by fraction including the sample preparation method and date, analytical method, and analysis date. Anything unusual about the samples, digestates, or extracts is identified. Holding time compliance is evaluated in this section.

010001

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981679
Laboratory Project Manager: Michael J. Walsh
Report Date: 16 November 1998

-
- Laboratory method performance: All quality control criteria for method performance must be met for all target analytes for data to be reported. These criteria generally apply to instrument tune, calibration, method blanks, and Laboratory Control Samples (LCS). In some instances where method criteria fail, useable data can be obtained and are reported with client approval. The narrative will then include a thorough discussion of the impact on data quality.
 - Sample performance: Quality control field samples are analyzed to determine any measurement bias due to the sample matrix based on evaluation of matrix spikes (MS), matrix spike duplicates (MSD), and laboratory duplicates (D). If acceptance criteria are not met, matrix interferences are confirmed either by reanalysis or by inspection of the LCS results to verify that laboratory method performance is in control. Data are reported with appropriate qualifiers or discussion.

VOLATILES by GC/MS - WATER (EA9812587 - EA9812595)

Sample Chronology: Nine samples and associated quality control were analyzed following the procedures specified in the CLP Statement of Work OLC02.1 on 26 October and 8 and 9 November 1998 for the Target Compound List (TCL) and library searches (TICs) using a 25mL purge volume. All holding times were met for all initial analyses. All reanalyses and dilutions were performed outside the method holding time.

The batch MS/MSD analyzed on 8 and 9 November 1998, was performed on another Navy Trenton sample (9BR-100798). All data associated with these QC analyses have been included in this report.

Sample 46BR-101298 required a 500X dilution in order to bring the concentrations of target analytes within the instrument calibration range.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples with the following exceptions;

- the batch LCS, VL810263, had the recovery of vinyl chloride (24%) below the lower QC limit of 40%. This low recovery may be indicative of a negative method bias for this target analyte. This LCS also had the recovery of 1,2-dichloropropane (141%) above the upper QC limit of 140%. This high recovery may be indicative of a positive method bias, however, since this analyte was not detected in the samples there should be no impact on data usability.
- the batch LCS, VL811081, had the recoveries of carbon tetrachloride (155%), 1,2-dichloropropane (153%) and cis-1,3-dichloropropane (147%) above the upper QC limit of 140%. These high recoveries may be indicative of a positive method bias, however, since none of these analytes were detected in the samples there should be no impact on data usability.
- the target analyte, methylene chloride was detected in the method blank, VBLK01, at a

010002

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981679
Laboratory Project Manager: Michael J. Walsh
Report Date: 16 November 1998

concentration (0.2ppb) below the reporting limit of 1ppb.

- the batch MSD, performed on sample 49BR-101298, was performed 12 minutes outside of instrument tune time.

Sample Performance: All quality control criteria were met for the reported samples with the following exceptions;

- samples 43BR-101298, 44BR-101298, 46BR-101298 and 49BR-101298 (as well as the MS/MSD performed on this sample) had the surrogate recoveries of BFB below the lower QC limit of 80%. These samples were reanalyzed with similar results. These low recoveries may be indicative of a negative bias for these samples.
- the batch MS/MSD, performed on sample 49BR-101298, had the recoveries of vinyl chloride (43%/41%) below the lower QC limit of 60% and the recoveries of carbon tetrachloride (149%/144%) and benzene (144%/141%) above the upper QC limit of 140%. The batch MS/MSD, performed on sample 9BR-100798, had the recoveries of carbon tetrachloride (162%/165%), 1,2-dichloropropane (152%/161%) and benzene (169%/169%) above the upper QC limit of 140%.

ANIONS - WATER (EA9812588 - EA9812592, EA9812594, EA9812595)

Sample Chronology: Seven aqueous samples and associated quality control were analyzed on 13 October 1998 by USEPA Method 300.0 for the anions chloride, nitrate, and sulfate. All holding times were met.

- Samples 43BR-101298, 44BR-101298, and 49BR-101298 were initially analyzed at two times (2X) dilutions in order to bring the pH of the samples within analytical range. All reporting limits are increased by two times for these samples.
- Samples 35MW1-101298, 35MW2-101298, and 43BR-101298 were reanalyzed at five times (5X) dilutions in order to bring the concentrations of target anions within calibration range.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples.

Sample Performance: All quality control criteria were met for the reported samples.

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981679
Laboratory Project Manager: Michael J. Walsh
Report Date: 16 November 1998

METALS - WATER (EA9812588-EA9812592, EA9812594-EA9812595)

Sample Chronology: Seven samples were prepared on 9 November 1998 and analyzed for dissolved barium, calcium, iron, magnesium, potassium, and sodium according to EPA method 200.7 on 11-12 November 1998.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples.

Sample Performance: All quality control criteria were met for the reported samples.

GENERAL CHEMISTRY - WATER (EA9812588-EA9812592, EA9812594-EA9812595)

Sample Chronology: Seven samples were analyzed for the following USEPA methods. All holding times were met.

<u>Parameter</u>	<u>Method#</u>	<u>Prep Date</u>	<u>Analysis Date</u>
Dissolved Ammonia	350.1	6 November 1998	10 November 1998
DOC	415.1	N/A	30 October 1998
TDS	160.1	N/A	16 October 1998

Laboratory Method Performance: All laboratory method performance criteria were met.

Sample Performance: All quality control criteria were met.

CERTIFICATION OF RESULTS


The Laboratory certifies that this report meets the project requirements for analytical data as stated in the Analytical Task Order (ATO) and the chain-of-custody. In addition, the Laboratory certifies that the data as reported meet the Data Quality Objectives for precision, accuracy, and completeness specified for this project or as stated in EA Laboratories Quality Assurance program for other than the conditions detailed above. It is recommended by the Laboratory that this analytical report should only be reproduced in its entirety. EA Laboratories is not responsible for any assumptions of data quality if partial packages are used to interpret data. Release of the data contained in this report has been authorized by the appropriate Laboratory Manager as verified by the following signature.



Michael J. Walsh, Laboratory Project Manager

November 16, 1998

010004

Company Name: EA NJ		Project Manager or Contact: STEVE FELDMANN Phone: 908-665-2440		Parameters/Method Numbers for Analysis										Chain of Custody Record					
Project No. 2960043		Project Name: NAVY, TRENTON		<div style="display: flex; flex-direction: column; align-items: center;"><div>No. of Containers</div><div>VOC +10 CLP</div><div>TDS BY 160.1</div><div>DOC BY 415.1</div><div>DISSOLVED AMMONIA BY 350.1</div><div>DISSOLVED METALS BY 200.7</div><div>INORGANIC ANIONS BY 300.0</div></div>										<div style="text-align: center;">EA Laboratories 19 Loveton Circle Sparta, MD 21152 Telephone: (410) 771-4920 Fax: (410) 771-4407</div>					
Dept.: 2131 Task: 7216		ATO Number: 7085												Report Deliverables: 4D BACK-UP 1 2 3 4 D E EDD: Yes No UNDER IDENTIFICATION BASE/EXCEL Summary DUE TO CLIENT: 30 DAY Hard Copy					
Sample Storage Location: K5/K6/WA 22														EA Labs Accession Number		Hard Copy due 11-13-98 EDD, due 11-27-98 Remarks			
Page 1 of 1		Report #: 981679																	
Date	Time	Water	Soil	Sample Identification 19 Characters															
10/12/98		X		TRIPOBLANK		3	X									9812587	LPM: DANA BRENNAN		
10/12/98	1415	X		F05-101298		7	X	X	X	X	X	X				9812588			
10/12/98	1304	X		35MM41-101298		7	X	X	X	X	X	X				9812589	VOC +10 CLP - LOW		
10/12/98	1055	X		35MM42-101298		7	X	X	X	X	X	X				9812590	CONCENTRATION		
10/12/98	1000	X		43BR-101298		7	X	X	X	X	X	X				9812591			
10/12/98	1135	X		44BR-101298		7	X	X	X	X	X	X				9812592	ALL PARAMETERS		
10/12/98	1045	X		F06-101298		3	X									9812593	EXCEPT VOC +TDS		
10/12/98	1632	X		46BR-101298		7	X	X	X	X	X	X				9812594	HAVE BEEN FIELD		
10/12/98	1709	X		49BR-101298		7	X	X	X	X	X	X				9812595	FILTERED		
<div style="text-align: center;">Dissolved Inorganics = Sulfate, chloride, nitrate Dissolved Metals = Cu, Mg, K, Na, Fe, Ba</div> <div style="text-align: center;">27VOC 7C, 7HA, 7500HA 7B VOC +10 CLP</div>																			
ANY QUESTIONS, CALL STEVE FELDMANN L 14822 #46 BR - HISTORICALLY HIGH VOC (TCE) CONCENTRATIONS Report Doc to MDL (0.2mg/L)																			
Samples by: (Signature) <i>Ronald A. Harwood</i>		Date/Time 10/12/98 1204		Relinquished by: (Signature) <i>Ronald A. Harwood</i>		Date/Time 10/12/98 1800		Received by: (Signature)										Date/Time	
Relinquished by: (Signature)		Date/Time		Received by Laboratory: (Signature) <i>Jean Blue</i>		Date/Time 10/13/98 1000		Airbill Number: 1852810234										Sample Shipped by: (Circle) Fed Ex Puro UPS	
Cooler Temp. 2°C pH: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Comments: CE, BE				Custody Seals Intact <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No														Hand Carried <input checked="" type="checkbox"/> 10160820092 Other: 98125810234	
NOTE: Please indicate method number for analyses requested. This will help clarify any questions with laboratory techniques.																			



December 4, 1998

Mr. Steve Feldmann
EA Engineering, Science, and Technology, Inc.
Two Oak Way
Berkeley Heights, NJ 07922


Re: NAWC Trenton Navy Site 1 FFS (29600.43)

Dear Mr. Feldmann:

Enclosed is our report on the analysis of seven water samples collected for the NAWC Trenton Navy project on 13 October 1998. The EDDs will follow. The invoice is included.

Please contact me if you have any questions or require further information and refer to report 981689. Unless other arrangements are made, we reserve the right to dispose of your samples sixty (60) days from the date of this letter. We will retain the raw data for seven years from this date.

Sincerely,



Michael J. Walsh
Laboratory Project Manager

enclosure

LABORATORY DATA REPORT

Prepared for:

**EA Engineering, Science, and Technology, Inc.
NAWC Trenton Navy**

Prepared by:

**EA Laboratories
19 Loveton Circle
Sparks, MD 21152**

Report 981689

December 1998

1. NARRATIVE

010000

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981689
Laboratory Project Manager: Michael J. Walsh
Report Date: 4 December 1998

This report contains the results of the analysis of seven water samples collected on 13 October 1998 in support of the referenced project.

SAMPLE RECEIPT

The samples and one trip blank arrived intact by Federal Express at EA Laboratories on 14 October 1998. Upon receipt, the samples and blank were inspected and compared with the chain-of-custody record. The samples and blank were then logged into the laboratory computer system with assigned laboratory accession numbers and released for analysis.

<u>Client Sample Designation</u>	<u>EA Lab Number</u>
TRIP BLANK	9812677
FB7-101398	9812678
33BR-101398	9812679
32S-101398	9812680
30BR-101398	9812681
38BR-101398	9812682
BRP1-101398	9812683
DUP2-101398	9812684

Following this narrative section is list of analytical methods (Table 1), glossaries of data qualifiers (Tables 2 and 3), and the original chain-of-custody record. Analytical results and quality control information are summarized in the appended data package which has been formatted to be consistent with the deliverable requirements of this project.

QUALITY CONTROL

The following sections are ordered as the data appears in this report. They contain observations made during sample analysis, summarize the results of quality control measurements, and address the impact on data usability based upon project Data Quality Objectives. For each fractional analysis the narrative includes:

- **Sample chronology:** This section summarizes the sample history by fraction including the sample preparation method and date, analytical method, and analysis date. Anything unusual about the samples, digestates, or extracts is identified. Holding time compliance is evaluated in this section.
- **Laboratory method performance:** All quality control criteria for method performance must be met

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981689
Laboratory Project Manager: Michael J. Walsh
Report Date: 4 December 1998

for all target analytes for data to be reported. These criteria generally apply to instrument tune, calibration, method blanks, and Laboratory Control Samples (LCS). In some instances where method criteria fail, useable data can be obtained and are reported with client approval. The narrative will then include a thorough discussion of the impact on data quality.

- Sample performance: Quality control field samples are analyzed to determine any measurement bias due to the sample matrix based on evaluation of matrix spikes (MS), matrix spike duplicates (MSD), and laboratory duplicates (D). If acceptance criteria are not met, matrix interferences are confirmed either by reanalysis or by inspection of the LCS results to verify that laboratory method performance is in control. Data are reported with appropriate qualifiers or discussion.

VOLATILES by GC/MS - WATER (EA9812677 - EA9812680, EA9812684)

Sample Chronology: Five samples and associated quality control were analyzed on 25 - 26 October 1998 for the project specified analyte list by USEPA SW-846, Methods 5030A/8260B using a 25 ml purge volume. All holding times were met.

The batch MS/MSD was performed on another client's sample. All data associated with these QC analyses have been included in this report.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples.

Sample Performance: All quality control criteria were met for the reported samples.

VOLATILES by GC/MS - WATER (EA9812677, EA9812678, EA9812681 - EA9812683)

Sample Chronology: Five samples and associated quality control were analyzed following the procedures specified in the CLP Statement of Work OLC02.1 on 27 October and 12 - 13 November 1998 for the Target Compound List (TCL) and library searches (TICs) using a 25mL purge volume. All holding times were met for all initial analyses. All reanalyses and dilutions were performed outside the method holding time.

Sample 30BR-101398 was analyzed at 5000X dilution in order to bring the concentrations of target analytes within the instrument calibration range. Sample 38BR-101398 was analyzed at 2000X dilution. Sample BRP1-101398 was analyzed at both a 10X and a 50X dilution.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples with the following exceptions;

- the batch LCS, VL810271, had the recovery of vinyl chloride (43%) below the lower QC limit

010002

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981689
Laboratory Project Manager: Michael J. Walsh
Report Date: 4 December 1998

of 60%. The batch LCS, VL811129, had the recovery of vinyl chloride (45%) below the lower QC limit of 60%.

Sample Performance: All quality control criteria were met for the reported samples with the following exceptions;

- the surrogate recoveries of bromofluorobenzene (BFB) in sample BRP1-101398 (71%), as well as the MS/MSD performed on this sample (71%/71%), were below the lower QC limit of 80%. The surrogate recovery of (BFB) in sample 31BR-100898 (75%) was below the lower QC limit. The surrogate recoveries of (BFB) in sample 07BR-100898 (64%), as well as the MS/MSD performed on this sample (71%/72%), were below the lower QC limit. The dilution of sample BRP1-101398 had the surrogate recovery of BFB (69%) below the lower QC limit.
- the batch MS/MSD, performed on sample BRP1-101398, had the recoveries of vinyl chloride (20%/0%) below the lower QC limit of 60%. The batch MS/MSD, performed on sample 07BR-100898, had the recoveries of vinyl chloride (48%/48%) below the lower QC limit of 60% and the recoveries of carbon tetrachloride (156%/156%), 1,2-dichloropropane (148%/144%), trichloroethene (149%/145%) and benzene (152%/152%) above the upper QC limit of 140%.
- the batch analyzed on 12 - 13 November 1998 was inadvertently double spiked with internal standard solution. All sample result have been adjusted to reflect the appropriate amount of internal standard added to the samples.

ANIONS - WATER (EA9812678 - EA9812684)

Sample Chronology: Seven aqueous samples and associated quality control were analyzed on 14 October 1998 by USEPA Method 300.0 for the anions chloride, nitrate, and sulfate. All holding times were met.

- Samples 33BR-101398, 32S-101398, BRP1-101398, and DUP2-101398 were reanalyzed at two times (2X) dilutions; and samples 30BR-101398 and 38BR-101398 were reanalyzed at five times (5X) dilutions in order to bring the concentrations of target anions within calibration range.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples.

Sample Performance: All quality control criteria were met for the reported samples.

METALS - WATER (EA9812678-EA9812684)

EA Laboratories
ANALYTICAL NARRATIVE

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981689
Laboratory Project Manager: Michael J. Walsh
Report Date: 4 December 1998

Sample Chronology: Seven samples were prepared on 9 November 1998 and analyzed for dissolved barium, calcium, iron, magnesium, potassium, and sodium according to EPA method 200.7 on 11-12 November 1998.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples.

Sample Performance: All quality control criteria were met for the reported samples.

GENERAL CHEMISTRY - WATER (EA9812678-EA9812684)

Sample Chronology: Seven samples were analyzed for the following USEPA methods. All holding times were met.

<u>Parameter</u>	<u>Method#</u>	<u>Prep Date</u>	<u>Analysis Date</u>
Ammonia, Diss	350.1	9 November 1998	10 November 1998
TDS	160.1	NA	16 October 1998
DOC	415.1	NA	30 October 1998

Laboratory Method Performance: All laboratory method performance criteria were met.

Sample Performance: All quality control criteria were met.

CERTIFICATION OF RESULTS

The Laboratory certifies that this report meets the project requirements for analytical data as stated in the Analytical Task Order (ATO) and the chain-of-custody. In addition, the Laboratory certifies that the data as reported meet the Data Quality Objectives for precision, accuracy, and completeness specified for this project or as stated in EA Laboratories Quality Assurance program for other than the conditions detailed above. It is recommended by the Laboratory that this analytical report should only be reproduced in its entirety. EA Laboratories is not responsible for any assumptions of data quality if partial packages are used to interpret data. Release of the data contained in this report has been authorized by the appropriate Laboratory Manager as verified by the following signature.




Michael J. Walsh, Laboratory Project Manager

December 4, 1998

010004

11/30/98

Company Name: EA-NJ		Project Manager or Contact: STEVE FELDMANN		Parameters/Method Numbers for Analysis										Chain of Custody Record					
Project No. 29600.43		Project Name: NAVY, TRENTON		No. of Containers VOC+10 CLP VOC+10 8260 TDS BY 160.1 DOC BY 415.1 DISSOLVED AMMONIA BY 350.1 DISSOLVED METALS BY 200.7 INORGANIC ANIONS BY 300.2										 EA Laboratories 19 Loveton Circle Sparks, MD 21152 Telephone: (410) 771-4920 Fax: (410) 771-4407					
Dept.: 2131 Task: 7216		ATO Number: 7085												Report Deliverables: W/40 BACK-UP 1 2 3 4 5 E EDD Yes No D-DATE/EXCEL SUMMARY TABS					
Sample Storage Location: F12/22/VCA		Report #: 981689												DUE TO CLIENT: 30 DAY HARD COPY					
Page 1 of 1														EA Labs Accession Number		Hard copy due 11-14-98 EDD due 11-28-98 Remarks			
Date	Time	Water	Soil	Sample Identification 19 Characters															
10/13/98	—	X		TRI BLANK		6	X	X									9812677	LPM: DAVID DRENNAN/MD	
10/13/98	1615	X		FB7-101398		10	X	X	X	X	X	X	X				9812678		
10/13/98	1035	X		33BR-101398		7		X	X	X	X	X	X				9812679	VOC+10 CLP - LOW	
10/13/98	1200	X		325-101398		17		X	X	X	X	X	X				9812680	CONCENTRATIONS	
10/13/98	1143	X		30BR-101398		7	X		X	X	X	X	X				9812681		
10/13/98	1602	X		38BR-101398		7	X		X	X	X	X	X				9812682	ALL PARAMETERS	
10/13/98	1407	X		BRP1-101398		7	X		X	X	X	X	X				9812683	EXCEPT DOC + TDS	
10/13/98	—	X		DUP2-101398		7		X	X	X	X	X	X				9812684	HAVE BEEN FILTERED	
10/13/98	—	X		25BR-101398															
				Dissolved inorganics anions etc: Sulfate, chloride, nitrate														ANY QUESTIONS, CALL STEVE FELDMANN	
				Dissolved metals: Ca, Mg, K, Na, Fe, Ba														* HISTORICALLY WELLS w/ HIGH CONCENTRATIONS VOC 30BR, 38BR, BRP-1 L14837	
																		Report Doc to MDLs (0.2 mg/L)	
																		1000003978	
Samples by: (Signature) <i>Ronald A. Howard</i>		Date/Time 10/13/98/1602		Relinquished by: (Signature) <i>Ronald A. Howard</i>		Date/Time 10/13/98/1600		Received by: (Signature)		Date/Time		Airbill Number: 1852810223		Sample Shipped by: (Circle) Fed Ex Puro. UPS					
Relinquished by: (Signature)		Date/Time		Received by Laboratory: (Signature) <i>Doreen Malaga</i>		Date/Time 10/14/98/10:00		Airbill Number:		Sample Shipped by: (Circle) Fed Ex Puro. UPS		Hand Carried Other: 1852810223							
Cooler Temp 24 C pH: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		Comments:		Custody Seals Intact <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No															
NOTE: Please indicate method number for analyses requested. This will help clarify any questions with laboratory techniques.																			

030001



December 8, 1998

Mr. Steve Feldmann
EA Engineering, Science, and Technology, Inc.
Two Oak Way
Berkeley Heights, NJ 07922


Re: NAWC Trenton Navy Site 1 FFS (29600.43)

Dear Mr. Feldmann:

Enclosed is our report on the analysis of nine water samples collected for the NAWC Trenton Navy project on 14 October 1998. The EDDs will follow. The invoice is included.

Please contact me if you have any questions or require further information and refer to report 981698. Unless other arrangements are made, we reserve the right to dispose of your samples sixty (60) days from the date of this letter. We will retain the raw data for seven years from this date.

Sincerely,



Michael J. Walsh
Laboratory Project Manager

enclosure

LABORATORY DATA REPORT

Prepared for:

**EA Engineering, Science, and Technology, Inc.
NAWC Trenton Navy**

Prepared by:

**EA Laboratories
19 Loveton Circle
Sparks, MD 21152**

Report 981698

December 1998

1. NARRATIVE

010000

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981698
Laboratory Project Manager: Michael J. Walsh
Report Date: 8 December 1998

This report contains the results of the analysis of nine water samples collected on 14 October 1998 in support of the referenced project.

SAMPLE RECEIPT

The samples and one trip blank arrived intact by Federal Express at EA Laboratories on 15 October 1998. Upon receipt, the samples and blank were inspected and compared with the chain-of-custody record. The samples and blank were then logged into the laboratory computer system with assigned laboratory accession numbers and released for analysis.

<u>Client Sample Designation</u>	<u>EA Lab Number</u>
TRIP BLANK	9812752
FB8-101498	9812753
50BR-101498	9812754
20BR-101498	9812755
16BR-101498	9812756
5BR-101498	9812757
DUP4-101498	9812758
36BR-101498	9812759
45BR-101498	9812760
DUP-3-101498	9812761

Following this narrative section is list of analytical methods (Table 1), glossaries of data qualifiers (Tables 2 and 3), and the original chain-of-custody record. Analytical results and quality control information are summarized in the appended data package which has been formatted to be consistent with the deliverable requirements of this project.

QUALITY CONTROL

The following sections are ordered as the data appears in this report. They contain observations made during sample analysis, summarize the results of quality control measurements, and address the impact on data usability based upon project Data Quality Objectives. For each fractional analysis the narrative includes:

- Sample chronology: This section summarizes the sample history by fraction including the sample preparation method and date, analytical method, and analysis date. Anything unusual about the samples, digestates, or extracts is identified. Holding time compliance is evaluated in this section.

010001

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981698
Laboratory Project Manager: Michael J. Walsh
Report Date: 8 December 1998

-
- Laboratory method performance: All quality control criteria for method performance must be met for all target analytes for data to be reported. These criteria generally apply to instrument tune, calibration, method blanks, and Laboratory Control Samples (LCS). In some instances where method criteria fail, useable data can be obtained and are reported with client approval. The narrative will then include a thorough discussion of the impact on data quality.
 - Sample performance: Quality control field samples are analyzed to determine any measurement bias due to the sample matrix based on evaluation of matrix spikes (MS), matrix spike duplicates (MSD), and laboratory duplicates (D). If acceptance criteria are not met, matrix interferences are confirmed either by reanalysis or by inspection of the LCS results to verify that laboratory method performance is in control. Data are reported with appropriate qualifiers or discussion.

VOLATILES by GC/MS - WATER (EA9812752 - EA9812761)

Sample Chronology: Ten samples and associated quality control were analyzed following the procedures specified in the CLP Statement of Work OLC02.1 on 28 and 31 October and 12 - 13 November 1998 for the Target Compound List (TCL) and library searches (TICs) using a 25mL purge volume. All holding times were met for all initial analyses with the exception of DUP-3-101498 which was analyzed 3 days outside of method holding times due to a computer failure. All reanalyses and dilutions were performed outside the method holding time.

The batch MS/MSDs, analyzed on 31 October and 12 and 13 November 1998, were performed on other client's samples. All data associated with these QC analyses have been included in this report. However, recoveries for these QC analyses have not been evaluated since they are not associated with the samples in this report.

Sample 16BR-101498 required a 20X dilution in order to bring the concentrations of target analytes within the instrument calibration range. Sample DUP-3-101498 required 200X dilution. Sample 36BR-101498 was analyzed at 10000X dilution. Sample 20BR-101498 was analyzed at both a 50X and a 1000X dilution. Sample 45BR-101498 was analyzed at both a 200X dilution and a 1000X dilution.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples with the following exceptions;

- the batch LCS, VL810281, had the recovery of carbon tetrachloride (141%) above the upper QC limit of 140%. The batch LCS, VL811031, had the recoveries of carbon tetrachloride (173%) and 1,2-dichloropropane (151%) above the upper QC limit of 140%. The batch LCS, VL811129, had the recovery of vinyl chloride (46%) below the lower QC limit of 60%. These high/low recoveries may be indicative of a method bias for these particular analytes.

010002

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981698
Laboratory Project Manager: Michael J. Walsh
Report Date: 8 December 1998

Sample Performance: All quality control criteria were met for the reported samples with the following exceptions;

- the surrogate recoveries of bromofluorobenzene (BFB) in sample BRP1-101398 (71%), as well as the MS/MSD performed on this sample (71%/71%), were below the lower QC limit of 80%. The surrogate recovery of (BFB) in sample 31BR-100898 (75%) was below the lower QC limit. The surrogate recoveries of (BFB) in sample 07BR-100898 (64%), as well as the MS/MSD performed on this sample (71%/72%), were below the lower QC limit. The dilution of sample BRP1-101398 had the surrogate recovery of BFB (69%) below the lower QC limit.
- the batch MS, performed on sample 45BR-101498, had the recoveries of carbon tetrachloride (149%), 1,2-dichloropropane (146%) and benzene (162%) above the upper QC limit of 140%. This MS also had the recovery of trichloroethene (0%) below the lower QC limit of 60%. The individual MSD had the recovery of benzene (156%).
- the batch analyzed on 12 - 13 November 1998 was inadvertently double spiked with internal standard solution. All sample result have been adjusted to reflect the appropriate amount of internal standard added to the samples.

ANIONS - WATER (EA9812753 - EA9812761)

Sample Chronology: Nine aqueous samples and associated quality control were analyzed on 15 October 1998 by USEPA Method 300.0 for the anions chloride, nitrate, and sulfate. All holding times were met.

- Samples 50BR-101498, 16BR-101498, DUP4-101498, 36BR-101498, 45BR-101498, and DUP-3-101498 were reanalyzed at two times (2X) dilutions; and samples 20BR-101498 and 5BR-101498 were reanalyzed at five times (5X) dilutions in order to bring the concentrations of target anions within calibration range.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples.

Sample Performance: All quality control criteria were met for the reported samples.

METALS - WATER (EA9812753-EA9812561)

Sample Chronology: Nine samples were prepared on 10 November 1998 and analyzed for dissolved barium, calcium, iron, magnesium, potassium, and sodium according to EPA method 200.7 on 11-12 November 1998.

010003

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981698
Laboratory Project Manager: Michael J. Walsh
Report Date: 8 December 1998

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples.

Sample Performance: All quality control criteria were met for the reported samples.

GENERAL CHEMISTRY - WATER (EA9812753-EA9812761)

Sample Chronology: Nine samples were analyzed for the following USEPA methods. All holding times were met.

Parameter	Method#	Prep Date	Analysis Date
Ammonia, Diss	350.1	11 November 1998	11 November 1998
TDS	160.1	NA	16 October 1998
DOC	415.1	NA	30 October 1998

Laboratory Method Performance: All laboratory method performance criteria were met.

Sample Performance: All quality control criteria were met with the following exception:

- The dissolved ammonia MS/MSD recoveries (50%, 50%) were below the 75-125% control limits. This may bias the sample results low.


CERTIFICATION OF RESULTS

The Laboratory certifies that this report meets the project requirements for analytical data as stated in the Analytical Task Order (ATO) and the chain-of-custody. In addition, the Laboratory certifies that the data as reported meet the Data Quality Objectives for precision, accuracy, and completeness specified for this project or as stated in EA Laboratories Quality Assurance program for other than the conditions detailed above. It is recommended by the Laboratory that this analytical report should only be reproduced in its entirety. EA Laboratories is not responsible for any assumptions of data quality if partial packages are used to interpret data. Release of the data contained in this report has been authorized by the appropriate Laboratory Manager as verified by the following signature.


December 8, 1998
Michael J. Walsh, Laboratory Project Manager

010004

144022/ 18167

Company Name: EA-NJ		Project Manager or Contact: STEVE FELDMANN Phone: 908-665-2440		Parameters/Method Numbers for Analysis										Chain of Custody Record											
Project No. 29600.43		Project Name: NAVY, TRENTON		<div>0.20 VOC + 10 CLP TDS BY 160.1 DOC BY 415.1 DISSOLVED AMMONIA BY 350.1 DISSOLVED METALS BY 200.7 INORGANIC AMMONIA BY 300.0</div>										 EA Laboratories 19 Loveton Circle Sparks, MD 21152 Telephone: (410) 771-4920 Fax: (410) 771-4407											
Dept.: 2131 Task: 7216		ATO Number: 7085												Report Deliverables: 6/4D BACK-UP 1 2 3 4 5 EDD: (Yes/No) NO UNDER MODIFICATIONS D-BASE/EXCEL Summary DUE TO CLIENT: 30 DAY HARDCOPY											
Sample Storage Location: K5/VOA/23																									
Page / of / Report #: 8/1698														EA Labs Accession Number		Hard Copy due - 11-15-98 EDD due - 11-29-98 Remarks									
Date	Time	Water	Soil	Sample Identification 19 Characters		No. of Containers																			
10/14/98	—	X		TRIABLANTE		36	X										9812752	LPM: DAVE BRENNAN							
10/14/98	1630	X		FBS-101498		7	X	X	X	X	X	X					9812753	L14839							
10/14/98	0954	X		50BR-101498		17	X	X	X	X	X	X					9812754	VOC + 10 CLP - LOW							
10/14/98	1055	X		20BR-101498		7	X	X	X	X	X	X					9812755	CONCENTRATIONS							
10/14/98	1330	X		16BR-101498		7	X	X	X	X	X	X					9812756								
10/14/98	1307	X		5BR-101498		7	X	X	X	X	X	X					9812757	ALL PARAMETERS							
10/14/98	—	X		DMP4-101498		7	X	X	X	X	X	X					9812758	EXCEPT VOC + TDS							
10/14/98	1450	X		36BR-101498		7	X	X	X	X	X	X					9812759	HAVE BEEN FILTERED							
10/14/98	1600	X		45OR-101498		17	X	X	X	X	X	X					9812760								
10/14/98	—	X		DUP-3																					
10/14/98	—	X		DUP-3-101498		7	X	X	X	X	X	X					9812761	ANY QUESTIONS CALL STEVE FELDMANN							
																		* RLV MS/MSD ON 50BR-101498 & 45BR-101498							
																		11B							
																		22A		* HISTORICALLY HIGH					
																		11C		CONCENTRATIONS OF					
																		42VOAS		VOC 20BR/36BR					
																		0000003988		Report VOC to MOL (0.2MOL)					
Samples by: (Signature) <i>Ronald G. Harwood</i>				Date/Time 10/14/98 1630		Relinquished by: (Signature) <i>Ronald G. Harwood</i>				Date/Time 10/14/98 1800		Received by: (Signature)				Date/Time									
Relinquished by: (Signature)				Date/Time		Received by Laboratory: (Signature) <i>Dyan V. ...</i>				Date/Time 10/15/98 1000		Airbill Number: 1852811741.				Sample Shipped by: (Circle) Fed Ex. <input checked="" type="checkbox"/> Puro. <input type="checkbox"/> UPS									
Cooler Temp. 2.5C pH: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Comments: _____																		Custody Seals Intact <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		Hand Carried <input type="checkbox"/>		Other:			
NOTE: Please indicate method number for analyses requested. This will help clarify any questions with laboratory techniques.																									

020001



November 25, 1998

Mr. Steve Feldmann
EA Engineering, Science, and Technology, Inc.
Two Oak Way
Berkeley Heights, NJ 07922

Re: NAWC Trenton (29600.43)

Dear Mr. Feldmann:

Enclosed is our report on the analysis of nine water samples collected for the NAWC Trenton project on 15 October 1998. The EDDs will follow. The invoice is included.

Please contact me if you have any questions or require further information and refer to report 981705. Unless other arrangements are made, we reserve the right to dispose of your samples sixty (60) days from the date of this letter. We will retain the raw data for seven years from this date.

Sincerely,

A handwritten signature in cursive script that reads 'Michael J. Walsh'.

Michael J. Walsh
Laboratory Project Manager

enclosure

LABORATORY DATA REPORT

Prepared for:

**EA Engineering, Science, and Technology, Inc.
NAWC Trenton Navy**

Prepared by:

**EA Laboratories
19 Loveton Circle
Sparks, MD 21152**

Report 981705

November 1998

1. NARRATIVE

010000

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981705
Laboratory Project Manager: Michael J. Walsh
Report Date: 25 November 1998

This report contains the results of the analysis of nine water samples collected on 15 October 1998 in support of the referenced project.

SAMPLE RECEIPT

The samples and one trip blank arrived intact by Federal Express at EA Laboratories on 16 October 1998. Upon receipt, the samples and blank were inspected and compared with the chain-of-custody record. The samples and blank were then logged into the laboratory computer system with assigned laboratory accession numbers and released for analysis.

<u>Client Sample Designation</u>	<u>EA Lab Number</u>
35BR-101598	9812819
ST27-101598	9812820
ST26-101598	9812821
OF25-101598	9812822
OF24-101598	9812823
OF22-101598	9812824
DUP5-101598	9812825
OF23-101598	9812826
FD9-101598	9812827
TRIP BLANK	9812828

Following this narrative section is list of analytical methods (Table 1), glossaries of data qualifiers (Tables 2 and 3), and the original chain-of-custody record. Analytical results and quality control information are summarized in the appended data package which has been formatted to be consistent with the deliverable requirements of this project.

QUALITY CONTROL

The following sections are ordered as the data appears in this report. They contain observations made during sample analysis, summarize the results of quality control measurements, and address the impact on data usability based upon project Data Quality Objectives. For each fractional analysis the narrative includes:

- Sample chronology: This section summarizes the sample history by fraction including the sample preparation method and date, analytical method, and analysis date. Anything unusual about the samples, digestates, or extracts is identified. Holding time compliance is evaluated in

010001

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981705
Laboratory Project Manager: Michael J. Walsh
Report Date: 25 November 1998

this section.

- Laboratory method performance: All quality control criteria for method performance must be met for all target analytes for data to be reported. These criteria generally apply to instrument tune, calibration, method blanks, and Laboratory Control Samples (LCS). In some instances where method criteria fail, useable data can be obtained and are reported with client approval. The narrative will then include a thorough discussion of the impact on data quality.
- Sample performance: Quality control field samples are analyzed to determine any measurement bias due to the sample matrix based on evaluation of matrix spikes (MS), matrix spike duplicates (MSD), and laboratory duplicates (D). If acceptance criteria are not met, matrix interferences are confirmed either by reanalysis or by inspection of the LCS results to verify that laboratory method performance is in control. Data are reported with appropriate qualifiers or discussion.

VOLATILES by GC/MS - WATER (EA9812819 - EA9812828)

Sample Chronology: Ten samples and associated quality control were analyzed on 30 October and 9 November 1998 for the project specified analyte list by USEPA SW-846, Methods 5030A/8260B using a 25 ml purge volume. All samples were analyzed one day outside of method holding times. All dilutions were analyzed ten days outside of method holding times.

The batch MS/MSD, analyzed on 9 November 1998, was performed on another client's sample. All data associated with these QC analyses have been included in this report.

Samples OF22-101598 and DUP5-101598 required a 5X dilution in order to bring the concentrations of target analytes within the instrument calibration range.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples.

Sample Performance: All quality control criteria were met for the reported samples.

ANIONS - WATER (EA9812819, EA9812827)

Sample Chronology: Two aqueous samples and associated quality control were analyzed on 16 October 1998 by USEPA Method 300.0 for the anions chloride, nitrate, and sulfate. All holding times were met.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported

010002

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981705
Laboratory Project Manager: Michael J. Walsh
Report Date: 25 November 1998

samples.

Sample Performance: All quality control criteria were met for the reported samples.

METALS - WATER (EA9812819,EA9812827)

Sample Chronology: Two samples were prepared on 10 November 1998 and analyzed for dissolved barium, calcium, iron, magnesium, potassium, and sodium according to EPA method 200.7 on 11-12 November 1998.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples.

Sample Performance: All quality control criteria were met for the reported samples.

GENERAL CHEMISTRY - WATER (EA9812819,EA9812827)

Sample Chronology: Two samples were analyzed for the following USEPA methods. All holding times were met.

<u>Parameter</u>	<u>Method#</u>	<u>Prep Date</u>	<u>Analysis Date</u>
Ammonia, Diss	350.1	9 November 1998	10 November 1998
TDS	160.1	NA	19 October 1998
Org. Carbon, Diss	415.1	NA	29 October 1998

Laboratory Method Performance: All laboratory method performance criteria were met.

Sample Performance: All quality control criteria were met.

CERTIFICATION OF RESULTS

The Laboratory certifies that this report meets the project requirements for analytical data as stated in the Analytical Task Order (ATO) and the chain-of-custody. In addition, the Laboratory certifies that the data as reported meet the Data Quality Objectives for precision, accuracy, and completeness specified for this project or as stated in EA Laboratories Quality Assurance program for other than the conditions detailed above. It is recommended by the Laboratory that this analytical report should only be

010003

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981705
Laboratory Project Manager: Michael J. Walsh
Report Date: 25 November 1998

reproduced in its entirety. EA Laboratories is not responsible for any assumptions of data quality if partial packages are used to interpret data. Release of the data contained in this report has been authorized by the appropriate Laboratory Manager as verified by the following signature.

Michael J. Walsh November 25, 1998
Michael J. Walsh, Laboratory Project Manager

010004

Company Name: EA-NT		Project Manager or Contact: RAV 29600.43 STEVE FELDMANN Phone: 908-665-2440		Parameters/Method Numbers for Analysis										Chain of Custody Record			
Project No. 29600.43		Project Name: NAVY, TRENTON		<div style="display: flex; flex-direction: column; align-items: center;"> <div style="margin-bottom: 5px;">VOC + 10 8260</div> <div style="margin-bottom: 5px;">TDS BY 160.1</div> <div style="margin-bottom: 5px;">DOC BY 411.1</div> <div style="margin-bottom: 5px;">DISSOLVED AMMONIA BY 350.1</div> <div style="margin-bottom: 5px;">DISSOLVED METALS BY 200.7</div> <div style="margin-bottom: 5px;">EMERG-METALS BY 300.0</div> </div>										 EA Laboratories 19 Loveton Circle Sparks, MD 21152 Telephone: (410) 771-4920 Fax: (410) 771-4407			
Dept.: 2131 Task: 7216		ATO Number: 7085															
Sample Storage Location: E11/VOA-23																	
Page 1 of 1		Report #: 981705												Report Deliverables: WY 4D BACK-UP 1 2 3 4 5 EDD: Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> D-Base/EXCEL SUMMARY DUE TO CLIENT: 30 DAY TAT			
Date	Time	Water	Soil	Sample Identification 19 Characters	No. of Containers											EA Labs Accession Number	Remarks
10/15/98	1145	X		35BR-101598	7	X	X	X	X	X	X					9812819	LPM/DAVID BRENNAN
10/15/98	0935	X		5T27-101598	3	X										9812820	MSW/DAVID BRENNAN
10/15/98	1115	X		5T26-101598	3	X										9812821	VOC + 10 LOW
10/15/98	1150	X		OF25-101598	3	X										9812822	CONC.
10/15/98	1203	X		OF24-101598	3	X										9812823	
10/15/98	1215	X		OF22-101598	3	X										9812824	ALL PARAMETERS
10/15/98	—	X		DUP5-101598	3	X										9812825	EXCEPT VOCs + TDS
10/15/98	1230	X		OF23-101598	3	X										9812826	HAVE BEEN FIELD
10/15/98	1510	X		FD9-101598	7	X	X	X	X	X	X					9812827	FILTERED
10/15/98	—	X		TRIPBLANK	3	X										9812828	
					Dissolved Inorganics = Sulfate, Chloride, Nitrate Dissolved Metals = Cu, Mg, K, Na, Fe, Ba												
					100000397												
					ANY QUESTIONS, CALL STEVE FELDMANN 410-4847												
					2 A' 2 B' 2 A' IL 2 B' 30 VOA's												
Samples by: (Signature) Ronald A. Howard		Date/Time 10/15/98 1510		Relinquished by: (Signature) Ronald A. Howard		Date/Time 10/15/98 1600		Received by: (Signature)				Date/Time					
Relinquished by: (Signature)		Date/Time		Received by Laboratory: (Signature)		Date/Time		Airbill Number: 1852810400				Sample Shipped by: (Circle) Fed Ex <input checked="" type="checkbox"/> Pure <input type="checkbox"/> UPS <input type="checkbox"/>					
Cooler Temp. 4° C		pH: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		Comments:		Custody Seals Intact <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No						Hand Carried <input type="checkbox"/>					
NOTE: Please indicate method number for analyses requested. This will help clarify any questions with laboratory techniques.																	

02000



November 29, 1998

Mr. Steve Feldmann
EA Engineering, Science, and Technology, Inc.
Two Oak Way
Berkeley Heights, NJ 07922

Re: NAWC Trenton (29600.43)

Dear Mr. Feldmann:

Enclosed is our report on the analysis of one water sample collected for the NAWC Trenton project on 16 October 1998. The EDDs will follow. The invoice is included.

Please contact me if you have any questions or require further information and refer to report 981710. Unless other arrangements are made, we reserve the right to dispose of your samples sixty (60) days from the date of this letter. We will retain the raw data for seven years from this date.

Sincerely,

Michael J. Walsh
Laboratory Project Manager

enclosure

LABORATORY DATA REPORT

Prepared for:

**EA Engineering, Science, and Technology, Inc.
NAWC Trenton Navy**

Prepared by:

**EA Laboratories
19 Loveton Circle
Sparks, MD 21152**

Report 981710

November 1998

1. NARRATIVE

010000

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981710
Laboratory Project Manager: Michael J. Walsh
Report Date: 29 November 1998

This report contains the results of the analysis of one water sample collected on 16 October 1998 in support of the referenced project.

SAMPLE RECEIPT

The sample and one trip blank arrived intact by Federal Express at EA Laboratories on 17 October 1998. Upon receipt, the sample and blank were inspected and compared with the chain-of-custody record. The sample and blank were then logged into the laboratory computer system with assigned laboratory accession numbers and released for analysis.

Client Sample Designation

WD-101698
TRIPBLANK

EA Lab Number

9812856
9812857

Following this narrative section is list of analytical methods (Table 1), glossaries of data qualifiers (Tables 2 and 3), and the original chain-of-custody record. Analytical results and quality control information are summarized in the appended data package which has been formatted to be consistent with the deliverable requirements of this project.

QUALITY CONTROL

The following sections are ordered as the data appears in this report. They contain observations made during sample analysis, summarize the results of quality control measurements, and address the impact on data usability based upon project Data Quality Objectives. For each fractional analysis the narrative includes:

- Sample chronology: This section summarizes the sample history by fraction including the sample preparation method and date, analytical method, and analysis date. Anything unusual about the samples, digestates, or extracts is identified. Holding time compliance is evaluated in this section.
- Laboratory method performance: All quality control criteria for method performance must be met for all target analytes for data to be reported. These criteria generally apply to instrument tune, calibration, method blanks, and Laboratory Control Samples (LCS). In some instances where method criteria fail, useable data can be obtained and are reported with client approval. The narrative will then include a thorough discussion of the impact on data quality.

010001

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981710
Laboratory Project Manager: Michael J. Walsh
Report Date: 29 November 1998

-
- Sample performance: Quality control field samples are analyzed to determine any measurement bias due to the sample matrix based on evaluation of matrix spikes (MS), matrix spike duplicates (MSD), and laboratory duplicates (D). If acceptance criteria are not met, matrix interferences are confirmed either by reanalysis or by inspection of the LCS results to verify that laboratory method performance is in control. Data are reported with appropriate qualifiers or discussion.

VOLATILES by GC/MS - WATER (EA9812856, EA9812857)

Sample Chronology: Two samples and associated quality control were analyzed following the procedures specified in the CLP Statement of Work OLC02.1 on 30 October and 13 - 14 November 1998 for the Target Compound List (TCL) and library searches (TICs) using a 25mL purge volume. All holding times were met for all initial analyses. All dilutions were performed outside the method holding times.

Sample WD-101698 required a 200X dilution in order to bring the concentrations of target analytes within the instrument calibration range.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported samples with the following exceptions;

- the batch LCS, VL811139, had the recovery of vinyl chloride (43%) below the lower QC limit of 40%. This low recovery may be indicative of a negative method bias for this target analyte.

Sample Performance: All quality control criteria were met for the reported samples with the following exceptions;

- the diluted analysis of sample WD-101698 (as well as the MS performed on this sample) had the surrogate recoveries of BFB below the lower QC limit of 80%. These low recoveries may be indicative of a negative bias for these samples.
- the batch MS, performed on sample WD-101698, had the recoveries of vinyl chloride (20%) and trichloroethene (0%) below the lower QC limit of 60% (the MSD recovery for trichloroethene was also 0%). These low recoveries appear to have been influenced by the high native concentrations of these analytes in the sample. The batch MS/MSD, performed on the dilution of WD-101698, had 14 out 24 recoveries below the lower QC limit.
- the batch analyzed on 13 November 1998 was inadvertently double spiked with internal standard

010002

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: EA Eng., Sci., & Tech., Inc.
Site: NAWC Trenton Navy Site 1 FFS
Project number: 29600.43

EA Laboratories Report: 981710
Laboratory Project Manager: Michael J. Walsh
Report Date: 29 November 1998

solution. All sample result have been adjusted to reflect the appropriate amount of internal standard added to the samples.

ANIONS - WATER (EA9812856)

Sample Chronology: One aqueous sample and associated quality control were analyzed on 17 October 1998 by USEPA Method 300.0 for the anions chloride, nitrate, and sulfate. All holding times were met.

- Sample WD-101698 was reanalyzed at a ten times (10X) dilution in order to bring the concentrations of target anions within calibration range.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported sample.

Sample Performance: All quality control criteria were met for the reported sample with the following exception:

- The matrix spike duplicate (MSD) performed on sample WD-101698 had the recovery of sulfate ion below the lower QC limit of 75% at 65%, and the relative percent difference (RPD) between the recovered concentrations of sulfate in the matrix spike and MSD was above the QC limit of 20% at 26%. The high recovery/RPD are based on estimated values (concentrations above the calibration range) for sulfate; data usability is not affected.

METALS - WATER (EA9812856)

Sample Chronology: One sample was prepared on 10 November 1998 and analyzed for dissolved barium, calcium, iron, magnesium, potassium, and sodium according to EPA method 200.7 on 11-12 November 1998.

Laboratory Method Performance: All laboratory method performance criteria were met for the reported sample.

Sample Performance: All quality control criteria were met for the reported sample.

GENERAL CHEMISTRY - WATER (EA9812856)

Sample Chronology: One sample was analyzed for the following USEPA methods. All holding times

010003

**EA Laboratories
ANALYTICAL NARRATIVE**

Client: **EA Eng., Sci., & Tech., Inc.**
Site: **NAWC Trenton Navy Site 1 FFS**
Project number: **29600.43**

EA Laboratories Report: **981710**
Laboratory Project Manager: **Michael J. Walsh**
Report Date: **29 November 1998**

were met.

<u>Parameter</u>	<u>Method#</u>	<u>Prep Date</u>	<u>Analysis Date</u>
Ammonia, Diss	350.1	6 November 1998	10 November 1998
TDS	160.1	NA	19 October 1998
DOC	415.1	NA	29 October 1998

Laboratory Method Performance: All laboratory method performance criteria were met.

Sample Performance: All quality control criteria were met.

CERTIFICATION OF RESULTS

The Laboratory certifies that this report meets the project requirements for analytical data as stated in the Analytical Task Order (ATO) and the chain-of-custody. In addition, the Laboratory certifies that the data as reported meet the Data Quality Objectives for precision, accuracy, and completeness specified for this project or as stated in EA Laboratories Quality Assurance program for other than the conditions detailed above. It is recommended by the Laboratory that this analytical report should only be reproduced in its entirety. EA Laboratories is not responsible for any assumptions of data quality if partial packages are used to interpret data. Release of the data contained in this report has been authorized by the appropriate Laboratory Manager as verified by the following signature.

 November 29, 1998
Michael J. Walsh, Laboratory Project Manager

010004

W ██████ — E/██████ oratoro ██████ ██████ YB ██████ W—E ██████ oratoro ██████ ██████ PINK — Project Manager ██████ ██████ Shaded Areas for Job Use Only